

# DRAINAGE STUDY


For:

Palm Hollister Apartments

PTS#:698277

APN 628-050-24-00  
555 Hollister Street  
San Diego, CA 92154

Prepared By:



Gregory W. Lang, P.E.  
Pasco Laret Suiter & Associates, Inc.  
119 Aberdeen Dr.  
Cardiff, CA 92007

RCE 68075

EXP: 06-30-23

**PASCO LARET SUITER**  
& ASSOCIATES  
CIVIL ENGINEERING + LAND PLANNING + LAND SURVEYING

Prepared for:  
Ambient Communities  
179 Calle Magdalena, Suite 201  
Encinitas, CA 92024

October 2021  
Revised July 2022  
Revised December 2022  
Revised April 2023

# TABLE OF CONTENTS

<b>1. INTRODUCTION .....</b>	<b>3</b>
1.1 Project Description .....	3
1.2 Existing Conditions .....	4
1.3 Proposed Conditions.....	4
1.4 Most Intense Use Conditions.....	5
1.5 100-Year Floodplain Analysis.....	5
<b>2. METHODOLOGY .....</b>	<b>6</b>
2.1 Rational Method .....	6
2.2 Runoff Coefficient.....	6
2.3 Rainfall Intensity .....	6
2.4 Detention .....	6
2.5 Section 401/404 Water Quality Certification .....	7
<b>3. CALCULATIONS / RESULTS.....</b>	<b>7</b>
3.1 Existing and Proposed Peak Flow Comparison.....	7
<b>4. CONCLUSION.....</b>	<b>7</b>
Appendix 1.....	Existing and Proposed Hydrology Exhibits
Appendix 2.....	Hydrology Support Material and Calculations
Appendix 3.....	Detention Output
Appendix 4.....	100-Year HEC-RAS Output

1. **INTRODUCTION**

1.1 **Project Description**

The project is located on a 5.92-acre site in the Otay Mesa-Nestor Community Plan area, north of Palm Avenue and east of Hollister Street in San Diego, California.

The project proposes to construct multi-family housing, walkways, parking areas, drive aisles, landscaping and amenities including a pool, bbq pavilion area, fitness center, co-working spaces, nature playground, game courts and seating areas.



**Vicinity Map**  
Not to Scale

## 1.2 Existing Conditions

The project site consists of a previously graded large flat open space area composed mainly of dirt, with some vegetation and a few vacant structures. There is a steep northward facing vegetated slope along the north side of the site.

In the existing condition, the site consists of two major drainage basins. Drainage Basin 100 is the smaller of the two basins and includes the eastern portion of the site. Storm water flows overland from the southeastern corner of the site in a northerly direction and discharges along the northeastern border.

Drainage Basin 200 consists of the remainder of the site, the central and western portion. Stormwater flows overland from the southern border of the site in a northwesterly direction and discharges along the northern border.

Offsite runoff from a small area south of the site runs onto the site along the southeastern border.

For the locations of the existing drainage basins and discharge points refer to the Existing Condition Hydrology Exhibit located in Appendix 1.

Per the United States Department of Agriculture Web Soil Survey, the project site is underlain with Hydrologic Soil Group A and D soils. Refer to Appendix 2 for soil information.

Using the Rational Method procedure outlined in the 2017 City of San Diego Drainage Design Manual, a peak flow rate was calculated for the existing condition 100-year, 6-hour storm event. The table below summarizes the existing condition hydrologic data.

**Summary of Existing Condition 100-yr Peak Discharge Rates**

<b>Discharge Node</b>	<b>Area (ac)</b>	<b>Q100 (cfs)</b>
115	1.5	1.76
215	4.0	3.55

Refer to the existing condition hydrologic calculations included in Appendix 2 for detailed analysis.

## 1.3 Proposed Conditions

The proposed project consists of the construction of multi-family housing, walkways, parking areas, drive aisles, landscaping and amenities including a pool, bbq pavilion area, fitness center, co-working spaces, nature playground, game courts and seating areas.

In the proposed condition, the site consists of two major drainage basins to mimic the existing condition. Drainage Basin 100 is the smaller of the two basins and includes the eastern portion of the site. All onsite storm water from Drainage Basin 100, except for landscaped perimeter slopes, will be captured in proposed storm drain and conveyed to an open-bottom underground vault located in the central area of Drainage Basin 100. The underground vault will provide storage to mitigate the 100-year storm event. Flow from the vault will be conveyed northerly and discharge along the northeastern border as in the existing condition. Runoff from the landscaped perimeter slopes will not be conveyed to the vault and will discharge along the northeastern border.

Drainage Basin 200 consists of the remainder of the site, the central and western portions. Onsite storm water from Drainage Basin 200, except for landscaped perimeter slopes, will be captured in proposed storm drain and conveyed to an open-bottom underground vault located in the central area of Drainage Basin 200. The underground vault will provide storage to mitigate the 100-year storm event. Flow from the vault will be conveyed northerly and discharge along the northern border as in the existing condition. Runoff from the landscaped perimeter slopes will not be conveyed to the vault and will discharge along the northern border.

Existing offsite runoff from a small area south of the site that runs onto the site along the southeastern border will be captured in proposed storm drain and bypassed through the site and will discharge at the Drainage Basin 100 discharge location.

The proposed underground storage vaults provide mitigation for the 100-year storm event peak discharge. The vaults are sized to provide additional detention to mitigate for flow from the areas that bypass the vaults so that the final discharge is less than the existing condition. Each vault will be open-bottom above a gravel layer to provide partial infiltration per the Geotechnical Report recommendation. For the locations of the proposed drainage basins and discharge points refer to the Proposed Condition Hydrology Exhibit located in Appendix 1.

Using the Rational Method procedure outlined in the 2017 City of San Diego Drainage Design Manual, a peak flow rate was calculated for the proposed condition 100-year, 6-hour storm event. The table below summarizes the proposed condition hydrologic data.

**Summary of Proposed Condition 100-yr Peak Discharge Rates**

<b>Discharge Node</b>	<b>Area (ac)</b>	<b>Q100 (cfs)</b>	<b>Q100 (cfs) Detained</b>
150	1.9	6.94	1.55
265	3.7	13.44	3.24

Refer to the proposed condition hydrologic calculations included in Appendix 2 for detailed analysis.

**1.4 Most Intense Use Conditions**

The proposed project requires an amendment to the Otay Mesa-Nestor Community Plan to change the existing land use designation from Open Space to Residential Medium-High Density (20-35 du/nra) and a Rezone to change the existing zone from AR-1-2, RM-1-1, and RS-1-5 to RM-2-6. A Rezone requires the proposed project analyze the most intense use permitted under the new zone. Under the proposed RM-2-6 zone, the project site could be developed to construct up to 206 dwelling units. This equates to an additional eight dwelling units compared to the proposed project, which plans to construct a total of 198 dwelling units. Adding eight dwelling units would not affect the drainage study as the total proposed pervious and impervious areas would remain unchanged.

**1.5 100-Year Floodplain Analysis**

The project is along the southerly edge of the Otay River. The effective 100-year floodplain width varies from approximately 2,300 to 3,100 feet along the site. The maximum floodplain encroachment from the project is approximately 20 feet or less than 1 percent. The project does not encroach into the floodway, so it meets floodway regulations. Existing and proposed condition 100-year HEC-RAS analyses were performed and are included in Appendix 4. The results showed that the 100-year water surface elevations

remained unchanged in many locations and did not vary more than 0.01 feet. The variation is well within the FEMA tie-in tolerance of 0.5 feet. Since the project has such a minor effect on the water surface elevations and the plan view floodplain, we do not believe it is necessary to process a CLOMR and LOMR. A CLOMR and LOMR would essentially preserve the existing elevations and the only alteration to the floodplain plotting will be a very minor realignment along the proposed wall. Such realignment would not be noticeable at the scale of the FIRM.

## **2. METHODOLOGY**

Pursuant to the 2017 City of San Diego Drainage Design Manual, the Rational Method is recommended for analyzing the runoff response from drainage areas less than 0.5 square mile, therefore the Rational Method was used to analyze this project's hydrologic characteristics.

### **2.1 Rational Method**

Runoff was calculated for the 100-year, 6-hour storm event using the Rational Method which is calculated using the following equation:

$$Q = C \times I \times A \qquad \text{Equation A-1 of 2017 City of SD Drainage Design Manual}$$

Where:

- Q = Flow rate in cubic feet per second (cfs)
- C = Runoff coefficient (Table A-1 of City of SD Drainage Design Manual)
- I = Rainfall Intensity in inches per hour (in/hr)
- A = Drainage basin area in acres (ac)

### **2.2 Runoff Coefficient**

The runoff coefficients for the project are based on Table A-1 and Footnote 2 from the 2017 City of San Diego Drainage Design Manual.

### **2.3 Rainfall Intensity**

Rainfall intensity was determined using the Rainfall Intensity-Duration-Frequency Curves shown in Section A.1.3 of the 2017 City of San Diego Drainage Design Manual. Based on Figure A-1 and a 5-minute time of concentration, the 100-year intensity is 4.4 inches per hour.

### **2.4 Detention**

The underground storage vaults provide mitigation for the 100-year storm event peak flow rate. The 100-year storm event detention analysis was performed using HydroCAD Stormwater Modeling software. The inflow runoff hydrographs to the vaults were modeled using RatHydro which is a Rational Method Design Storm Hydrograph software that creates a hydrograph using the results of the Rational Method calculations. HydroCAD has the ability to route the 100-year 6-hour storm event inflow hydrograph through the facilities considering dynamic tailwater effects. Based on the facility cross sectional geometry, stage storage and outlet structure data, HydroCAD calculates the detained peak flow rate and detained time to peak.

Based on the results of the HydroCAD analysis, mitigation for the 100-year storm event peak flow rate is provided, detaining the peak flow rate in the proposed condition to below the existing condition. Vault 1, located on the east half of the site is 1,100 square feet, 5.67 feet high, and includes a 26” deep gravel layer below the vault discharge pipe, providing a total storage volume of 7,192 cubic feet. Vault 2, located on the west half of the site, is 2,300 square feet, 5.67 feet high and includes a 23” gravel layer below the vault discharge pipe, providing a total storage volume of 14,807 cubic feet. Refer to Appendix 3 for the HydroCAD detention calculations and the plans for details of each facility.

## 2.5 Section 401/404 Water Quality Certification

This project does not have any waters of the United States (e.g., creek, drainage, wetland) on the property and does not require Federal permitting or approval.

## 3. CALCULATIONS / RESULTS

### 3.1 Existing and Proposed Peak Flow Comparison

The table below summarizes the 100-year 6-hour peak flow rate calculations for the project.

**Summary of 100-yr Peak Discharge Rates**

Existing					Proposed					Detained	
Discharge Node	Area (ac)	Runoff Coeff. C	Q100 (cfs)	V100 (ft/sec)	Discharge Node	Area (ac)	Runoff Coeff. C	Q100 (cfs)	V100 (ft/sec)	Q100 (cfs)	V100 (ft/sec)
115	1.5	0.35	1.76	1.71	150	1.9	0.95	6.94	10.94	1.55	6.99
215	4.0	0.35	3.55	1.39	265	3.7	0.95	13.44	14.77	3.24	10.19

In the proposed detained condition, the 100-year storm event peak discharge rates are lower than the existing flow rates. The proposed detained 100-year velocity will be dissipated below existing condition rates with large outfall structures and riprap pads as detailed on the grading plans so that no adverse impacts will occur downstream.

## 4. CONCLUSION

Based upon the analyses included in this report, the proposed underground vaults adequately mitigate the increase in peak runoff in the proposed condition to below the existing condition. The proposed project is designed to honor the existing condition discharge locations and flow rates so that there are no negative impacts to the downstream system or adjacent properties.

---

## **Appendix 1**

# **Existing and Proposed Hydrology Exhibits**

---



DESCRIPTION	SYMBOL
PROPERTY LINE	---
BASIN BOUNDARY	—
BASIN SUBAREA BOUNDARY	---
FLOW PATH	→
BASIN SUBAREA	(A=1.56)
BASIN SUMMARY Q100 EXISTING (PRE MITIGATION)	(XX) XXX.XXX AC CFS

**HYDROLOGIC SOIL GROUP**

HYDROLOGIC SOIL TYPE: A & D

**DEPTH TO GROUNDWATER**

5 FT <GROUNDWATER DEPTH> 10 FT

**PROJECT CHARACTERISTICS**



TOTAL SITE AREA: 5.92 AC

EXISTING IMPERVIOUS AREA: 0.07 AC

EXISTING LANDSCAPE AREA: 5.85 AC

**SUMMARY OF EXISTING CONDITIONS**

EXIST. DRAINAGE BASIN	EXIST. DRAINAGE AREA (AC)	RUNOFF COEFFICIENT, C	Q100 (CFS)
(A1)	1.5	0.35	1.76
(A2)	4.0	0.35	3.55



**PASCO LARET SUITER**  
**& ASSOCIATES**  
 San Diego | Encinitas | Orange County  
 Phone 858.259.8212 | www.plsaengineering.com

**EXISTING CONDITION  
 DRAINAGE EXHIBIT**  
 PALM AND HOLLISTER  
 SAN DIEGO, CA  
 PLSA JOB # 3272  
 SCALE 1"=50'  
 OCTOBER 2021  
 SHEET 1 OF 1

DESCRIPTION	SYMBOL
PROPERTY LINE	---
BASIN BOUNDARY	—
BASIN SUBAREA BOUNDARY	—
FLOW DIRECTION	→
PROPOSED IMPERVIOUS AREA	▨
BASIN SUBAREA	(A=1.56)
BASIN SUMMARY Q100	(XX XXX XXX AC CFS)

### HYDROLOGIC SOIL GROUP

HYDROLOGIC SOIL TYPE: A & D

### DEPTH TO GROUNDWATER



5 FT <GROUNDWATER DEPTH> 10 FT

### PROJECT CHARACTERISTICS

TOTAL SITE AREA:	5.92 AC
PROPOSED DISTURBED AREA:	5.59 AC
PROPOSED IMPERVIOUS AREA:	4.28 AC
PROPOSED LANDSCAPE AREA:	1.31 AC

### SUMMARY OF PROPOSED CONDITIONS

DRAINAGE BASIN	DRAINAGE AREA (AC)	RUNOFF COEFFICIENT, C	Q100 (CFS)	Q100 DETAINED (CFS)
A1	1.9	0.95	6.94	1.55
A2	3.7	0.95	13.44	3.24



### PROPOSED CONDITION DRAINAGE EXHIBIT

PALM AND HOLLISTER  
SAN DIEGO, CA  
PLSA JOB # 3272  
SCALE 1"=50'  
APRIL 2023  
SHEET 1 OF 1

**PASCO LARET SUITER & ASSOCIATES**  
San Diego | Encinitas | Orange County  
Phone 858.259.8212 | www.plsaengineering.com

---

## **Appendix 2**

# **Hydrology Support Material and Calculations**

---

**Table A-1. Runoff Coefficients for Rational Method**

Land Use	Runoff Coefficient (C)
	Soil Type <sup>(1)</sup>
<b>Residential:</b>	
Single Family	0.55
Multi-Units	0.70
Mobile Homes	0.65
Rural (lots greater than 1/2 acre)	0.45
<b>Commercial <sup>(2)</sup></b>	
80% Impervious	0.85
<b>Industrial <sup>(2)</sup></b>	
90% Impervious	0.95

**Note:**

<sup>(1)</sup> Type D soil to be used for all areas.

<sup>(2)</sup> Where actual conditions deviate significantly from the tabulated imperviousness values of 80% or 90%, the values given for coefficient C, may be revised by multiplying 80% or 90% by the ratio of actual imperviousness to the tabulated imperviousness. However, in case shall the final coefficient be less than 0.50. For example: Consider commercial property on D soil.

Actual imperviousness	=	50%
Tabulated imperviousness	=	80%
Revised C	=	$(50/80) \times 0.85 = 0.53$

The values in Table A-1 are typical for urban areas. However, if the basin contains rural or agricultural land use, parks, golf courses, or other types of nonurban land use that are expected to be permanent, the appropriate value should be selected based upon the soil and cover and approved by the City.

**A.1.3. Rainfall Intensity**

The rainfall intensity (I) is the rainfall in inches per hour (in/hr.) for a duration equal to the T<sub>c</sub> for a selected storm frequency. Once a particular storm frequency has been selected for design and a T<sub>c</sub> calculated for the drainage area, the rainfall intensity can be determined from the Intensity-Duration-Frequency Design Chart (Figure A-1).



APPENDIX A: RATIONAL METHOD AND MODIFIED RATIONAL METHOD





Figure A-1. Intensity-Duration-Frequency Design Chart





Soil Map may not be valid at this scale.

Map Scale: 1:2,080 if printed on A landscape (11" x 8.5") sheet.



























Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 11N WGS84










Natural Resources  
Conservation Service

Web Soil Survey  
National Cooperative Soil Survey

## MAP LEGEND

<b>Area of Interest (AOI)</b>	 C
Area of Interest (AOI)	 C/D
<b>Soils</b>	 D
<b>Soil Rating Polygons</b>	 Not rated or not available
A	
A/D	
B	
B/D	
C	
C/D	
D	
Not rated or not available	
<b>Soil Rating Lines</b>	 A
A	 A/D
B	 B
B/D	 B/D
C	 C
C/D	 C/D
D	 D
Not rated or not available	 Not rated or not available
<b>Soil Rating Points</b>	 A
A	 A/D
B	 B
B/D	 B/D

<b>Water Features</b>	 Streams and Canals
<b>Transportation</b>	 RAILS
	 Interstate Highways
	 US Routes
	 Major Roads
	 Local Roads
<b>Background</b>	 Aerial Photography

## MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
 Web Soil Survey URL:  
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: San Diego County Area, California  
 Survey Area Data: Version 15, May 27, 2020

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Aug 22, 2018—Aug 31, 2018

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

## Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
HrC	Huerhuero loam, 2 to 9 percent slopes	D	3.0	44.4%
HrD2	Huerhuero loam, 9 to 15 percent slopes, eroded	D	3.3	48.1%
TuB	Tujunga sand, 0 to 5 percent slopes	A	0.0	0.2%
VbB	Visalia gravelly sandy loam, 2 to 5 percent slopes	A	0.5	7.2%
<b>Totals for Area of Interest</b>			<b>6.8</b>	<b>100.0%</b>



## Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

## Rating Options

*Aggregation Method:* Dominant Condition

*Component Percent Cutoff:* None Specified

*Tie-break Rule:* Higher

## Existing Condition

\*\*\*\*\*

RATIONAL METHOD HYDROLOGY COMPUTER PROGRAM PACKAGE
Reference: SAN DIEGO COUNTY FLOOD CONTROL DISTRICT
2003,1985,1981 HYDROLOGY MANUAL
(c) Copyright 1982-2016 Advanced Engineering Software (aes)
Ver. 23.0 Release Date: 07/01/2016 License ID 1452

Analysis prepared by:

PASCO LARET SUITER & ASSOCIATES
535 NORTH HIGHWAY 101, STE A
SOLANA BEACH, CA 92075
858-259-8212

\*\*\*\*\* DESCRIPTION OF STUDY \*\*\*\*\*
\* 3272 PALM AND HOLLISTER \*
\* EXISTING CONDITION \*
\* 100-YR \*
\*\*\*\*\*

FILE NAME: 3272E00.DAT
TIME/DATE OF STUDY: 11:56 09/14/2021

-----
USER SPECIFIED HYDROLOGY AND HYDRAULIC MODEL INFORMATION:
-----

USER SPECIFIED STORM EVENT(YEAR) = 100.00
SPECIFIED MINIMUM PIPE SIZE(INCH) = 4.00
SPECIFIED PERCENT OF GRADIENTS(DECIMAL) TO USE FOR FRICTION SLOPE = 0.90
RAINFALL-INTENSITY ADJUSTMENT FACTOR = 1.000
\*USER SPECIFIED:
NUMBER OF [TIME,INTENSITY] DATA PAIRS = 9

- 1) 5.000; 4.400
2) 10.000; 3.450
3) 15.000; 2.900
4) 20.000; 2.500
5) 25.000; 2.200
6) 30.000; 2.000
7) 40.000; 1.700
8) 50.000; 1.500
9) 60.000; 1.300

SAN DIEGO HYDROLOGY MANUAL "C"-VALUES USED FOR RATIONAL METHOD
NOTE: ONLY PEAK CONFLUENCE VALUES CONSIDERED

\*USER-DEFINED STREET-SECTIONS FOR COUPLED PIPEFLOW AND STREETFLOW MODEL\*
Table with columns: NO., WIDTH (FT), CROSSFALL (FT), STREET-CROSSFALL: IN- / OUT-/PARK- SIDE / SIDE/ WAY, CURB HEIGHT (FT), GUTTER GEOMETRIES: WIDTH (FT), LIP (FT), HIKE (FT), MANNING FACTOR (n)

GLOBAL STREET FLOW-DEPTH CONSTRAINTS:
1. Relative Flow-Depth = 0.00 FEET
as (Maximum Allowable Street Flow Depth) - (Top-of-Curb)
2. (Depth)\*(Velocity) Constraint = 6.0 (FT\*FT/S)
\*SIZE PIPE WITH A FLOW CAPACITY GREATER THAN OR EQUAL TO THE UPSTREAM TRIBUTARY PIPE.\*

\*\*\*\*\*
FLOW PROCESS FROM NODE 100.00 TO NODE 105.00 IS CODE = 21
-----

>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<
=====

\*USER SPECIFIED(SUBAREA):
USER-SPECIFIED RUNOFF COEFFICIENT = .3500
S.C.S. CURVE NUMBER (AMC II) = 0
INITIAL SUBAREA FLOW-LENGTH(FEET) = 133.00
UPSTREAM ELEVATION(FEET) = 55.50
DOWNSTREAM ELEVATION(FEET) = 49.00
ELEVATION DIFFERENCE(FEET) = 6.50
URBAN SUBAREA OVERLAND TIME OF FLOW(MIN.) = 7.956
WARNING: INITIAL SUBAREA FLOW PATH LENGTH IS GREATER THAN THE MAXIMUM OVERLAND FLOW LENGTH = 100.00

(Reference: Table 3-1B of Hydrology Manual)  
 THE MAXIMUM OVERLAND FLOW LENGTH IS USED IN Tc CALCULATION!  
 100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 3.838  
 SUBAREA RUNOFF (CFS) = 0.16  
 TOTAL AREA (ACRES) = 0.12 TOTAL RUNOFF (CFS) = 0.16

\*\*\*\*\*  
 FLOW PROCESS FROM NODE 105.00 TO NODE 110.00 IS CODE = 51  
 -----

>>>>COMPUTE TRAPEZOIDAL CHANNEL FLOW<<<<<  
 >>>>TRAVELTIME THRU SUBAREA (EXISTING ELEMENT)<<<<<

=====

ELEVATION DATA: UPSTREAM (FEET) = 49.00 DOWNSTREAM (FEET) = 27.00  
 CHANNEL LENGTH THRU SUBAREA (FEET) = 137.00 CHANNEL SLOPE = 0.1606  
 CHANNEL BASE (FEET) = 10.00 "Z" FACTOR = 20.000  
 MANNING'S FACTOR = 0.030 MAXIMUM DEPTH (FEET) = 2.00  
 100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 3.587  
 \*USER SPECIFIED (SUBAREA):  
 USER-SPECIFIED RUNOFF COEFFICIENT = .3500  
 S.C.S. CURVE NUMBER (AMC II) = 0  
 TRAVEL TIME COMPUTED USING ESTIMATED FLOW (CFS) = 0.61  
 TRAVEL TIME THRU SUBAREA BASED ON VELOCITY (FEET/SEC.) = 1.73  
 AVERAGE FLOW DEPTH (FEET) = 0.03 TRAVEL TIME (MIN.) = 1.32  
 Tc (MIN.) = 9.28  
 SUBAREA AREA (ACRES) = 0.72 SUBAREA RUNOFF (CFS) = 0.90  
 AREA-AVERAGE RUNOFF COEFFICIENT = 0.350  
 TOTAL AREA (ACRES) = 0.8 PEAK FLOW RATE (CFS) = 1.05

END OF SUBAREA CHANNEL FLOW HYDRAULICS:  
 DEPTH (FEET) = 0.04 FLOW VELOCITY (FEET/SEC.) = 2.26  
 LONGEST FLOWPATH FROM NODE 100.00 TO NODE 110.00 = 270.00 FEET.

\*\*\*\*\*  
 FLOW PROCESS FROM NODE 110.00 TO NODE 115.00 IS CODE = 51  
 -----

>>>>COMPUTE TRAPEZOIDAL CHANNEL FLOW<<<<<  
 >>>>TRAVELTIME THRU SUBAREA (EXISTING ELEMENT)<<<<<

=====

ELEVATION DATA: UPSTREAM (FEET) = 27.00 DOWNSTREAM (FEET) = 23.50  
 CHANNEL LENGTH THRU SUBAREA (FEET) = 187.00 CHANNEL SLOPE = 0.0187  
 CHANNEL BASE (FEET) = 5.00 "Z" FACTOR = 10.000  
 MANNING'S FACTOR = 0.030 MAXIMUM DEPTH (FEET) = 2.00  
 100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 3.317  
 \*USER SPECIFIED (SUBAREA):  
 USER-SPECIFIED RUNOFF COEFFICIENT = .3500  
 S.C.S. CURVE NUMBER (AMC II) = 0  
 TRAVEL TIME COMPUTED USING ESTIMATED FLOW (CFS) = 1.45  
 TRAVEL TIME THRU SUBAREA BASED ON VELOCITY (FEET/SEC.) = 1.62  
 AVERAGE FLOW DEPTH (FEET) = 0.14 TRAVEL TIME (MIN.) = 1.93  
 Tc (MIN.) = 11.21  
 SUBAREA AREA (ACRES) = 0.68 SUBAREA RUNOFF (CFS) = 0.79  
 AREA-AVERAGE RUNOFF COEFFICIENT = 0.350  
 TOTAL AREA (ACRES) = 1.5 PEAK FLOW RATE (CFS) = 1.76

END OF SUBAREA CHANNEL FLOW HYDRAULICS:  
 DEPTH (FEET) = 0.16 FLOW VELOCITY (FEET/SEC.) = 1.71  
 LONGEST FLOWPATH FROM NODE 100.00 TO NODE 115.00 = 457.00 FEET.

\*\*\*\*\*  
 FLOW PROCESS FROM NODE 200.00 TO NODE 205.00 IS CODE = 21  
 -----

>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<<

=====

\*USER SPECIFIED (SUBAREA):  
 USER-SPECIFIED RUNOFF COEFFICIENT = .3500  
 S.C.S. CURVE NUMBER (AMC II) = 0  
 INITIAL SUBAREA FLOW-LENGTH (FEET) = 130.00  
 UPSTREAM ELEVATION (FEET) = 49.90  
 DOWNSTREAM ELEVATION (FEET) = 48.80  
 ELEVATION DIFFERENCE (FEET) = 1.10  
 URBAN SUBAREA OVERLAND TIME OF FLOW (MIN.) = 11.405  
 WARNING: INITIAL SUBAREA FLOW PATH LENGTH IS GREATER THAN  
 THE MAXIMUM OVERLAND FLOW LENGTH = 63.85

(Reference: Table 3-1B of Hydrology Manual)  
 THE MAXIMUM OVERLAND FLOW LENGTH IS USED IN Tc CALCULATION!  
 100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 3.295  
 SUBAREA RUNOFF (CFS) = 0.12  
 TOTAL AREA (ACRES) = 0.10 TOTAL RUNOFF (CFS) = 0.12

\*\*\*\*\*  
 FLOW PROCESS FROM NODE 205.00 TO NODE 210.00 IS CODE = 51  
 -----

>>>>COMPUTE TRAPEZOIDAL CHANNEL FLOW<<<<<  
 >>>>TRAVELTIME THRU SUBAREA (EXISTING ELEMENT)<<<<<

=====

ELEVATION DATA: UPSTREAM (FEET) = 48.80 DOWNSTREAM (FEET) = 23.00  
 CHANNEL LENGTH THRU SUBAREA (FEET) = 332.00 CHANNEL SLOPE = 0.0777  
 CHANNEL BASE (FEET) = 10.00 "Z" FACTOR = 10.000  
 MANNING'S FACTOR = 0.030 MAXIMUM DEPTH (FEET) = 2.00  
 100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 2.961  
 \*USER SPECIFIED (SUBAREA):  
 USER-SPECIFIED RUNOFF COEFFICIENT = .3500  
 S.C.S. CURVE NUMBER (AMC II) = 0  
 TRAVEL TIME COMPUTED USING ESTIMATED FLOW (CFS) = 0.93  
 TRAVEL TIME THRU SUBAREA BASED ON VELOCITY (FEET/SEC.) = 1.82  
 AVERAGE FLOW DEPTH (FEET) = 0.05 TRAVEL TIME (MIN.) = 3.04  
 Tc (MIN.) = 14.45  
 SUBAREA AREA (ACRES) = 1.56 SUBAREA RUNOFF (CFS) = 1.62  
 AREA-AVERAGE RUNOFF COEFFICIENT = 0.350  
 TOTAL AREA (ACRES) = 1.7 PEAK FLOW RATE (CFS) = 1.72

END OF SUBAREA CHANNEL FLOW HYDRAULICS:  
 DEPTH (FEET) = 0.07 FLOW VELOCITY (FEET/SEC.) = 2.24  
 LONGEST FLOWPATH FROM NODE 200.00 TO NODE 210.00 = 462.00 FEET.

\*\*\*\*\*  
 FLOW PROCESS FROM NODE 210.00 TO NODE 215.00 IS CODE = 51  
 -----

>>>>COMPUTE TRAPEZOIDAL CHANNEL FLOW<<<<<  
 >>>>TRAVELTIME THRU SUBAREA (EXISTING ELEMENT)<<<<<

=====

ELEVATION DATA: UPSTREAM (FEET) = 23.00 DOWNSTREAM (FEET) = 20.00  
 CHANNEL LENGTH THRU SUBAREA (FEET) = 396.00 CHANNEL SLOPE = 0.0076  
 CHANNEL BASE (FEET) = 10.00 "Z" FACTOR = 10.000  
 MANNING'S FACTOR = 0.030 MAXIMUM DEPTH (FEET) = 2.00  
 100 YEAR RAINFALL INTENSITY (INCH/HOUR) = 2.523  
 \*USER SPECIFIED (SUBAREA):  
 USER-SPECIFIED RUNOFF COEFFICIENT = .3500  
 S.C.S. CURVE NUMBER (AMC II) = 0  
 TRAVEL TIME COMPUTED USING ESTIMATED FLOW (CFS) = 2.77  
 TRAVEL TIME THRU SUBAREA BASED ON VELOCITY (FEET/SEC.) = 1.25  
 AVERAGE FLOW DEPTH (FEET) = 0.19 TRAVEL TIME (MIN.) = 5.26  
 Tc (MIN.) = 19.71  
 SUBAREA AREA (ACRES) = 2.36 SUBAREA RUNOFF (CFS) = 2.08  
 AREA-AVERAGE RUNOFF COEFFICIENT = 0.350  
 TOTAL AREA (ACRES) = 4.0 PEAK FLOW RATE (CFS) = 3.55

END OF SUBAREA CHANNEL FLOW HYDRAULICS:  
 DEPTH (FEET) = 0.21 FLOW VELOCITY (FEET/SEC.) = 1.39  
 LONGEST FLOWPATH FROM NODE 200.00 TO NODE 215.00 = 858.00 FEET.

=====

END OF STUDY SUMMARY:  
 TOTAL AREA (ACRES) = 4.0 TC (MIN.) = 19.71  
 PEAK FLOW RATE (CFS) = 3.55

=====

END OF RATIONAL METHOD ANALYSIS

Proposed Condition

\*\*\*\*\*

RATIONAL METHOD HYDROLOGY COMPUTER PROGRAM PACKAGE
Reference: SAN DIEGO COUNTY FLOOD CONTROL DISTRICT
2003,1985,1981 HYDROLOGY MANUAL
(c) Copyright 1982-2016 Advanced Engineering Software (aes)
Ver. 23.0 Release Date: 07/01/2016 License ID 1452

Analysis prepared by:

Pasco Laret Suiter & Associates
119 Aberdeen Drive
Cardiff, California 92007
858-259-8212

\*\*\*\*\* DESCRIPTION OF STUDY \*\*\*\*\*
\* 3272 PALM AND HOLLISTER \*
\* PROPOSED CONDITION \*
\* 100-YR \*
\*\*\*\*\*

FILE NAME: 3272P00.DAT
TIME/DATE OF STUDY: 10:34 04/03/2023

-----
USER SPECIFIED HYDROLOGY AND HYDRAULIC MODEL INFORMATION:
-----

USER SPECIFIED STORM EVENT (YEAR) = 100.00
SPECIFIED MINIMUM PIPE SIZE (INCH) = 4.00
SPECIFIED PERCENT OF GRADIENTS (DECIMAL) TO USE FOR FRICTION SLOPE = 0.90
RAINFALL-INTENSITY ADJUSTMENT FACTOR = 1.000

\*USER SPECIFIED:
NUMBER OF [TIME, INTENSITY] DATA PAIRS = 9

- 1) 5.000; 4.400
2) 10.000; 3.450
3) 15.000; 2.900
4) 20.000; 2.500
5) 25.000; 2.200
6) 30.000; 2.000
7) 40.000; 1.700
8) 50.000; 1.500
9) 60.000; 1.300

SAN DIEGO HYDROLOGY MANUAL "C"-VALUES USED FOR RATIONAL METHOD

NOTE: ONLY PEAK CONFLUENCE VALUES CONSIDERED

\*USER-DEFINED STREET-SECTIONS FOR COUPLED PIPEFLOW AND STREETFLOW MODEL\*

Table with 9 columns: NO., WIDTH (FT), CROWN TO CROSSFALL (FT), STREET-CROSSFALL: IN- / OUT- / PARK- SIDE / SIDE / WAY, CURB HEIGHT (FT), GUTTER WIDTH (FT), LIP (FT), HIKE (FT), MANNING FACTOR (n). Row 1: 1, 12.0, 7.0, 0.020/0.020/0.020, 0.50, 1.50, 0.0100, 0.125, 0.0180

GLOBAL STREET FLOW-DEPTH CONSTRAINTS:

- 1. Relative Flow-Depth = 0.00 FEET
as (Maximum Allowable Street Flow Depth) - (Top-of-Curb)
2. (Depth)\*(Velocity) Constraint = 6.0 (FT\*FT/S)

\*SIZE PIPE WITH A FLOW CAPACITY GREATER THAN
OR EQUAL TO THE UPSTREAM TRIBUTARY PIPE.\*

\*\*\*\*\*

FLOW PROCESS FROM NODE 100.00 TO NODE 105.00 IS CODE = 21

-----
>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<
=====

\*USER SPECIFIED (SUBAREA) :
USER-SPECIFIED RUNOFF COEFFICIENT = .9500

```

S.C.S. CURVE NUMBER (AMC II) = 0
INITIAL SUBAREA FLOW-LENGTH(FEET) = 46.00
UPSTREAM ELEVATION(FEET) = 46.50
DOWNSTREAM ELEVATION(FEET) = 45.50
ELEVATION DIFFERENCE(FEET) = 1.00
URBAN SUBAREA OVERLAND TIME OF FLOW(MIN.) = 1.414
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.400
NOTE: RAINFALL INTENSITY IS BASED ON Tc = 5-MINUTE.
SUBAREA RUNOFF(CFS) = 0.88
TOTAL AREA(ACRES) = 0.21 TOTAL RUNOFF(CFS) = 0.88

*****
FLOW PROCESS FROM NODE 100.00 TO NODE 105.00 IS CODE = 22
-----
>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<
=====
*USER SPECIFIED(SUBAREA):
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) = 0
USER SPECIFIED Tc(MIN.) = 5.000
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.400
SUBAREA RUNOFF(CFS) = 0.88
TOTAL AREA(ACRES) = 0.21 TOTAL RUNOFF(CFS) = 0.88

*****
FLOW PROCESS FROM NODE 105.00 TO NODE 110.00 IS CODE = 31
-----
>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) = 41.50 DOWNSTREAM(FEET) = 41.00
FLOW LENGTH(FEET) = 45.30 MANNING'S N = 0.013
DEPTH OF FLOW IN 9.0 INCH PIPE IS 4.7 INCHES
PIPE-FLOW VELOCITY(FEET/SEC.) = 3.79
ESTIMATED PIPE DIAMETER(INCH) = 9.00 NUMBER OF PIPES = 1
PIPE-FLOW(CFS) = 0.88
PIPE TRAVEL TIME(MIN.) = 0.20 Tc(MIN.) = 5.20
LONGEST FLOWPATH FROM NODE 100.00 TO NODE 110.00 = 91.30 FEET.

*****
FLOW PROCESS FROM NODE 115.00 TO NODE 110.00 IS CODE = 81
-----
>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<
=====
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.362
*USER SPECIFIED(SUBAREA):
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) = 0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.9500
SUBAREA AREA(ACRES) = 0.25 SUBAREA RUNOFF(CFS) = 1.04
TOTAL AREA(ACRES) = 0.5 TOTAL RUNOFF(CFS) = 1.91
TC(MIN.) = 5.20

*****
FLOW PROCESS FROM NODE 110.00 TO NODE 112.00 IS CODE = 31
-----
>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) = 41.00 DOWNSTREAM(FEET) = 40.00
FLOW LENGTH(FEET) = 26.90 MANNING'S N = 0.013
DEPTH OF FLOW IN 9.0 INCH PIPE IS 5.2 INCHES
PIPE-FLOW VELOCITY(FEET/SEC.) = 7.24
ESTIMATED PIPE DIAMETER(INCH) = 9.00 NUMBER OF PIPES = 1
PIPE-FLOW(CFS) = 1.91

```



```

PIPE TRAVEL TIME(MIN.) = 0.06    Tc(MIN.) = 5.26
LONGEST FLOWPATH FROM NODE 100.00 TO NODE 112.00 = 118.20 FEET.
*****
FLOW PROCESS FROM NODE 120.00 TO NODE 112.00 IS CODE = 81
-----
>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<
=====
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.350
*USER SPECIFIED(SUBAREA):
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) = 0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.9500
SUBAREA AREA(ACRES) = 0.56    SUBAREA RUNOFF(CFS) = 2.31
TOTAL AREA(ACRES) = 1.0    TOTAL RUNOFF(CFS) = 4.22
TC(MIN.) = 5.26
*****
FLOW PROCESS FROM NODE 112.00 TO NODE 125.00 IS CODE = 31
-----
>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) = 39.00    DOWNSTREAM(FEET) = 38.00
FLOW LENGTH(FEET) = 89.30    MANNING'S N = 0.013
DEPTH OF FLOW IN 15.0 INCH PIPE IS 8.8 INCHES
PIPE-FLOW VELOCITY(FEET/SEC.) = 5.62
ESTIMATED PIPE DIAMETER(INCH) = 15.00    NUMBER OF PIPES = 1
PIPE-FLOW(CFS) = 4.22
PIPE TRAVEL TIME(MIN.) = 0.26    Tc(MIN.) = 5.53
LONGEST FLOWPATH FROM NODE 100.00 TO NODE 125.00 = 207.50 FEET.
*****
FLOW PROCESS FROM NODE 125.00 TO NODE 125.00 IS CODE = 1
-----
>>>>DESIGNATE INDEPENDENT STREAM FOR CONFLUENCE<<<<
=====
TOTAL NUMBER OF STREAMS = 2
CONFLUENCE VALUES USED FOR INDEPENDENT STREAM 1 ARE:
TIME OF CONCENTRATION(MIN.) = 5.53
RAINFALL INTENSITY(INCH/HR) = 4.30
TOTAL STREAM AREA(ACRES) = 1.02
PEAK FLOW RATE(CFS) AT CONFLUENCE = 4.22
*****
FLOW PROCESS FROM NODE 130.00 TO NODE 135.00 IS CODE = 21
-----
>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<
=====
*USER SPECIFIED(SUBAREA):
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) = 0
INITIAL SUBAREA FLOW-LENGTH(FEET) = 63.00
UPSTREAM ELEVATION(FEET) = 45.70
DOWNSTREAM ELEVATION(FEET) = 45.50
ELEVATION DIFFERENCE(FEET) = 0.20
URBAN SUBAREA OVERLAND TIME OF FLOW(MIN.) = 2.405
WARNING: INITIAL SUBAREA FLOW PATH LENGTH IS GREATER THAN
         THE MAXIMUM OVERLAND FLOW LENGTH = 50.00
         (Reference: Table 3-1B of Hydrology Manual)
         THE MAXIMUM OVERLAND FLOW LENGTH IS USED IN Tc CALCULATION!
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.400
NOTE: RAINFALL INTENSITY IS BASED ON Tc = 5-MINUTE.
SUBAREA RUNOFF(CFS) = 0.21
TOTAL AREA(ACRES) = 0.05    TOTAL RUNOFF(CFS) = 0.21

```

```

*****
FLOW PROCESS FROM NODE      130.00 TO NODE      135.00 IS CODE =  22
-----
>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<
=====
*USER SPECIFIED(SUBAREA) :
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) =  0
USER SPECIFIED Tc(MIN.) =  5.000
  100 YEAR RAINFALL INTENSITY(INCH/HOUR) =  4.400
SUBAREA RUNOFF(CFS) =  0.21
TOTAL AREA(ACRES) =  0.05  TOTAL RUNOFF(CFS) =  0.21
*****
FLOW PROCESS FROM NODE      135.00 TO NODE      140.00 IS CODE =  62
-----
>>>>COMPUTE STREET FLOW TRAVEL TIME THRU SUBAREA<<<<
>>>>(STREET TABLE SECTION #  1 USED)<<<<
=====
UPSTREAM ELEVATION(FEET) =  45.50  DOWNSTREAM ELEVATION(FEET) =  44.50
STREET LENGTH(FEET) =  86.00  CURB HEIGHT(INCHES) =  6.0
STREET HALFWIDTH(FEET) =  12.00

DISTANCE FROM CROWN TO CROSSFALL GRADEBREAK(FEET) =  7.00
INSIDE STREET CROSSFALL(DECIMAL) =  0.020
OUTSIDE STREET CROSSFALL(DECIMAL) =  0.020

SPECIFIED NUMBER OF HALFSTREETS CARRYING RUNOFF =  1
STREET PARKWAY CROSSFALL(DECIMAL) =  0.020
Manning's FRICTION FACTOR for Streetflow Section(curbs-to-curbs) =  0.0180
Manning's FRICTION FACTOR for Back-of-Walk Flow Section =  0.0200

  **TRAVEL TIME COMPUTED USING ESTIMATED FLOW(CFS) =  1.34
  STREETFLOW MODEL RESULTS USING ESTIMATED FLOW:
  STREET FLOW DEPTH(FEET) =  0.27
  HALFSTREET FLOOD WIDTH(FEET) =  8.14
  AVERAGE FLOW VELOCITY(FEET/SEC.) =  1.79
  PRODUCT OF DEPTH&VELOCITY(FT*FT/SEC.) =  0.48
STREET FLOW TRAVEL TIME(MIN.) =  0.80  Tc(MIN.) =  5.80
  100 YEAR RAINFALL INTENSITY(INCH/HOUR) =  4.248
*USER SPECIFIED(SUBAREA) :
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) =  0
AREA-AVERAGE RUNOFF COEFFICIENT =  0.950
SUBAREA AREA(ACRES) =  0.56  SUBAREA RUNOFF(CFS) =  2.26
TOTAL AREA(ACRES) =  0.6  PEAK FLOW RATE(CFS) =  2.46

END OF SUBAREA STREET FLOW HYDRAULICS:
DEPTH(FEET) =  0.32  HALFSTREET FLOOD WIDTH(FEET) =  10.55
FLOW VELOCITY(FEET/SEC.) =  2.05  DEPTH*VELOCITY(FT*FT/SEC.) =  0.65
LONGEST FLOWPATH FROM NODE      130.00 TO NODE      140.00 =  149.00 FEET.
*****
FLOW PROCESS FROM NODE      140.00 TO NODE      145.00 IS CODE =  31
-----
>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) =  40.50  DOWNSTREAM(FEET) =  38.00
FLOW LENGTH(FEET) =  45.10  MANNING'S N =  0.013
DEPTH OF FLOW IN  9.0 INCH PIPE IS  5.4 INCHES
PIPE-FLOW VELOCITY(FEET/SEC.) =  8.96
ESTIMATED PIPE DIAMETER(INCH) =  9.00  NUMBER OF PIPES =  1
PIPE-FLOW(CFS) =  2.46

```

```

PIPE TRAVEL TIME (MIN.) = 0.08    Tc (MIN.) = 5.89
LONGEST FLOWPATH FROM NODE 130.00 TO NODE 145.00 = 194.10 FEET.
*****
FLOW PROCESS FROM NODE 145.00 TO NODE 125.00 IS CODE = 1
-----
>>>>DESIGNATE INDEPENDENT STREAM FOR CONFLUENCE<<<<<
>>>>AND COMPUTE VARIOUS CONFLUENCED STREAM VALUES<<<<<
=====
TOTAL NUMBER OF STREAMS = 2
CONFLUENCE VALUES USED FOR INDEPENDENT STREAM 2 ARE:
TIME OF CONCENTRATION (MIN.) = 5.89
RAINFALL INTENSITY (INCH/HR) = 4.23
TOTAL STREAM AREA (ACRES) = 0.61
PEAK FLOW RATE (CFS) AT CONFLUENCE = 2.46

** CONFLUENCE DATA **
STREAM    RUNOFF      Tc      INTENSITY      AREA
NUMBER    (CFS)        (MIN.)  (INCH/HR)      (ACRE)
  1        4.22         5.53      4.300          1.02
  2        2.46         5.89      4.232          0.61

RAINFALL INTENSITY AND TIME OF CONCENTRATION RATIO
CONFLUENCE FORMULA USED FOR 2 STREAMS.

** PEAK FLOW RATE TABLE **
STREAM    RUNOFF      Tc      INTENSITY
NUMBER    (CFS)        (MIN.)  (INCH/HR)
  1        6.53         5.53      4.300
  2        6.61         5.89      4.232

COMPUTED CONFLUENCE ESTIMATES ARE AS FOLLOWS:
PEAK FLOW RATE (CFS) = 6.61    Tc (MIN.) = 5.89
TOTAL AREA (ACRES) = 1.6
LONGEST FLOWPATH FROM NODE 100.00 TO NODE 125.00 = 207.50 FEET.
*****
FLOW PROCESS FROM NODE 145.00 TO NODE 150.00 IS CODE = 31
-----
>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<<
=====
ELEVATION DATA: UPSTREAM (FEET) = 38.00  DOWNSTREAM (FEET) = 23.00
FLOW LENGTH (FEET) = 294.00  MANNING'S N = 0.013
DEPTH OF FLOW IN 12.0 INCH PIPE IS 8.6 INCHES
PIPE-FLOW VELOCITY (FEET/SEC.) = 10.94
ESTIMATED PIPE DIAMETER (INCH) = 12.00  NUMBER OF PIPES = 1
PIPE-FLOW (CFS) = 6.61
PIPE TRAVEL TIME (MIN.) = 0.45    Tc (MIN.) = 6.33
LONGEST FLOWPATH FROM NODE 100.00 TO NODE 150.00 = 501.50 FEET.
*****
FLOW PROCESS FROM NODE 155.00 TO NODE 150.00 IS CODE = 81
-----
>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<<
=====
100 YEAR RAINFALL INTENSITY (INCH/HR) = 4.147
*USER SPECIFIED (SUBAREA) :
USER-SPECIFIED RUNOFF COEFFICIENT = .4500
S.C.S. CURVE NUMBER (AMC II) = 0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.8767
SUBAREA AREA (ACRES) = 0.28  SUBAREA RUNOFF (CFS) = 0.52
TOTAL AREA (ACRES) = 1.9  TOTAL RUNOFF (CFS) = 6.94
TC (MIN.) = 6.33

```

```

*****
FLOW PROCESS FROM NODE      200.00 TO NODE      205.00 IS CODE =  21
-----
>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<<
=====
*USER SPECIFIED(SUBAREA) :
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) = 0
INITIAL SUBAREA FLOW-LENGTH(FEET) = 45.00
UPSTREAM ELEVATION(FEET) = 45.70
DOWNSTREAM ELEVATION(FEET) = 45.00
ELEVATION DIFFERENCE(FEET) = 0.70
URBAN SUBAREA OVERLAND TIME OF FLOW(MIN.) = 1.563
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.400
NOTE: RAINFALL INTENSITY IS BASED ON Tc = 5-MINUTE.
SUBAREA RUNOFF(CFS) = 0.42
TOTAL AREA(ACRES) = 0.10 TOTAL RUNOFF(CFS) = 0.42
*****
FLOW PROCESS FROM NODE      200.00 TO NODE      205.00 IS CODE =  22
-----
>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<<
=====
*USER SPECIFIED(SUBAREA) :
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) = 0
USER SPECIFIED Tc(MIN.) = 5.000
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.400
SUBAREA RUNOFF(CFS) = 0.42
TOTAL AREA(ACRES) = 0.10 TOTAL RUNOFF(CFS) = 0.42
*****
FLOW PROCESS FROM NODE      210.00 TO NODE      205.00 IS CODE =  81
-----
>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<<
=====
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.400
*USER SPECIFIED(SUBAREA) :
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) = 0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.9500
SUBAREA AREA(ACRES) = 0.39 SUBAREA RUNOFF(CFS) = 1.63
TOTAL AREA(ACRES) = 0.5 TOTAL RUNOFF(CFS) = 2.05
TC(MIN.) = 5.00
*****
FLOW PROCESS FROM NODE      205.00 TO NODE      215.00 IS CODE =  31
-----
>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) = 40.30 DOWNSTREAM(FEET) = 39.70
FLOW LENGTH(FEET) = 77.00 MANNING'S N = 0.013
DEPTH OF FLOW IN 12.0 INCH PIPE IS 7.3 INCHES
PIPE-FLOW VELOCITY(FEET/SEC.) = 4.09
ESTIMATED PIPE DIAMETER(INCH) = 12.00 NUMBER OF PIPES = 1
PIPE-FLOW(CFS) = 2.05
PIPE TRAVEL TIME(MIN.) = 0.31 Tc(MIN.) = 5.31
LONGEST FLOWPATH FROM NODE 200.00 TO NODE 215.00 = 122.00 FEET.
*****
FLOW PROCESS FROM NODE      215.00 TO NODE      215.00 IS CODE =  81
-----
>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<<
=====

```

```

100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.340
*USER SPECIFIED(SUBAREA):
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) = 0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.9500
SUBAREA AREA (ACRES) = 0.11 SUBAREA RUNOFF (CFS) = 0.45
TOTAL AREA (ACRES) = 0.6 TOTAL RUNOFF (CFS) = 2.47
TC (MIN.) = 5.31
*****
FLOW PROCESS FROM NODE 215.00 TO NODE 220.00 IS CODE = 31
-----
>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) = 39.70 DOWNSTREAM(FEET) = 39.10
FLOW LENGTH(FEET) = 76.70 MANNING'S N = 0.013
DEPTH OF FLOW IN 12.0 INCH PIPE IS 8.3 INCHES
PIPE-FLOW VELOCITY(FEET/SEC.) = 4.26
ESTIMATED PIPE DIAMETER(INCH) = 12.00 NUMBER OF PIPES = 1
PIPE-FLOW(CFS) = 2.47
PIPE TRAVEL TIME(MIN.) = 0.30 Tc(MIN.) = 5.61
LONGEST FLOWPATH FROM NODE 200.00 TO NODE 220.00 = 198.70 FEET.
*****
FLOW PROCESS FROM NODE 220.00 TO NODE 220.00 IS CODE = 81
-----
>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<
=====
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.283
*USER SPECIFIED(SUBAREA):
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) = 0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.9500
SUBAREA AREA (ACRES) = 0.38 SUBAREA RUNOFF (CFS) = 1.55
TOTAL AREA (ACRES) = 1.0 TOTAL RUNOFF (CFS) = 3.99
TC (MIN.) = 5.61
*****
FLOW PROCESS FROM NODE 220.00 TO NODE 222.00 IS CODE = 31
-----
>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) = 39.10 DOWNSTREAM(FEET) = 38.00
FLOW LENGTH(FEET) = 114.50 MANNING'S N = 0.013
DEPTH OF FLOW IN 15.0 INCH PIPE IS 8.9 INCHES
PIPE-FLOW VELOCITY(FEET/SEC.) = 5.24
ESTIMATED PIPE DIAMETER(INCH) = 15.00 NUMBER OF PIPES = 1
PIPE-FLOW(CFS) = 3.99
PIPE TRAVEL TIME(MIN.) = 0.36 Tc(MIN.) = 5.98
LONGEST FLOWPATH FROM NODE 200.00 TO NODE 222.00 = 313.20 FEET.
*****
FLOW PROCESS FROM NODE 225.00 TO NODE 222.00 IS CODE = 81
-----
>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<
=====
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.214
*USER SPECIFIED(SUBAREA):
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) = 0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.9500
SUBAREA AREA (ACRES) = 0.71 SUBAREA RUNOFF (CFS) = 2.84
TOTAL AREA (ACRES) = 1.7 TOTAL RUNOFF (CFS) = 6.77

```

```

TC (MIN.) =      5.98

*****
FLOW PROCESS FROM NODE      270.00 TO NODE      222.00 IS CODE =  81
-----
>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<
=====
100 YEAR RAINFALL INTENSITY (INCH/HOUR) =  4.214
*USER SPECIFIED (SUBAREA) :
USER-SPECIFIED RUNOFF COEFFICIENT = .5000
S.C.S. CURVE NUMBER (AMC II) =  0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.8940
SUBAREA AREA (ACRES) =  0.24  SUBAREA RUNOFF (CFS) =  0.51
TOTAL AREA (ACRES) =  1.9  TOTAL RUNOFF (CFS) =  7.27
TC (MIN.) =  5.98

*****
FLOW PROCESS FROM NODE      222.00 TO NODE      230.00 IS CODE =  31
-----
>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<
=====
ELEVATION DATA: UPSTREAM (FEET) =  37.00  DOWNSTREAM (FEET) =  34.50
FLOW LENGTH (FEET) =  45.80  MANNING'S N =  0.013
DEPTH OF FLOW IN 12.0 INCH PIPE IS  9.1 INCHES
PIPE-FLOW VELOCITY (FEET/SEC.) =  11.41
ESTIMATED PIPE DIAMETER (INCH) =  12.00  NUMBER OF PIPES =  1
PIPE-FLOW (CFS) =  7.27
PIPE TRAVEL TIME (MIN.) =  0.07  Tc (MIN.) =  6.05
LONGEST FLOWPATH FROM NODE      200.00 TO NODE      230.00 =  359.00 FEET.

*****
FLOW PROCESS FROM NODE      230.00 TO NODE      230.00 IS CODE =  1
-----
>>>>DESIGNATE INDEPENDENT STREAM FOR CONFLUENCE<<<<
=====
TOTAL NUMBER OF STREAMS =  2
CONFLUENCE VALUES USED FOR INDEPENDENT STREAM 1 ARE:
TIME OF CONCENTRATION (MIN.) =  6.05
RAINFALL INTENSITY (INCH/HR) =  4.20
TOTAL STREAM AREA (ACRES) =  1.93
PEAK FLOW RATE (CFS) AT CONFLUENCE =  7.27

*****
FLOW PROCESS FROM NODE      235.00 TO NODE      240.00 IS CODE =  21
-----
>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<
=====
*USER SPECIFIED (SUBAREA) :
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) =  0
INITIAL SUBAREA FLOW-LENGTH (FEET) =  165.00
UPSTREAM ELEVATION (FEET) =  44.50
DOWNSTREAM ELEVATION (FEET) =  42.00
ELEVATION DIFFERENCE (FEET) =  2.50
URBAN SUBAREA OVERLAND TIME OF FLOW (MIN.) =  1.897
WARNING: INITIAL SUBAREA FLOW PATH LENGTH IS GREATER THAN
         THE MAXIMUM OVERLAND FLOW LENGTH =  65.15
         (Reference: Table 3-1B of Hydrology Manual)
         THE MAXIMUM OVERLAND FLOW LENGTH IS USED IN Tc CALCULATION!
100 YEAR RAINFALL INTENSITY (INCH/HOUR) =  4.400
NOTE: RAINFALL INTENSITY IS BASED ON Tc = 5-MINUTE.
SUBAREA RUNOFF (CFS) =  1.42
TOTAL AREA (ACRES) =  0.34  TOTAL RUNOFF (CFS) =  1.42

```

```

*****
FLOW PROCESS FROM NODE      235.00 TO NODE      240.00 IS CODE =  22
-----
>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<
=====
*USER SPECIFIED(SUBAREA):
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) =  0
USER SPECIFIED Tc(MIN.) =  5.000
  100 YEAR RAINFALL INTENSITY(INCH/HOUR) =  4.400
SUBAREA RUNOFF(CFS) =  1.42
TOTAL AREA(ACRES) =  0.34  TOTAL RUNOFF(CFS) =  1.42
*****
FLOW PROCESS FROM NODE      240.00 TO NODE      245.00 IS CODE =  31
-----
>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) =  38.00  DOWNSTREAM(FEET) =  37.60
FLOW LENGTH(FEET) =  39.60  MANNING'S N =  0.013
DEPTH OF FLOW IN  9.0 INCH PIPE IS  6.7 INCHES
PIPE-FLOW VELOCITY(FEET/SEC.) =  4.04
ESTIMATED PIPE DIAMETER(INCH) =  9.00  NUMBER OF PIPES =  1
PIPE-FLOW(CFS) =  1.42
PIPE TRAVEL TIME(MIN.) =  0.16  Tc(MIN.) =  5.16
LONGEST FLOWPATH FROM NODE      235.00 TO NODE      245.00 =  204.60 FEET.
*****
FLOW PROCESS FROM NODE      250.00 TO NODE      245.00 IS CODE =  81
-----
>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<
=====
  100 YEAR RAINFALL INTENSITY(INCH/HOUR) =  4.369
*USER SPECIFIED(SUBAREA):
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) =  0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.9500
SUBAREA AREA(ACRES) =  0.31  SUBAREA RUNOFF(CFS) =  1.29
TOTAL AREA(ACRES) =  0.6  TOTAL RUNOFF(CFS) =  2.70
TC(MIN.) =  5.16
*****
FLOW PROCESS FROM NODE      245.00 TO NODE      247.00 IS CODE =  31
-----
>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) =  37.60  DOWNSTREAM(FEET) =  35.90
FLOW LENGTH(FEET) =  217.90  MANNING'S N =  0.013
DEPTH OF FLOW IN  12.0 INCH PIPE IS  8.9 INCHES
PIPE-FLOW VELOCITY(FEET/SEC.) =  4.31
ESTIMATED PIPE DIAMETER(INCH) =  12.00  NUMBER OF PIPES =  1
PIPE-FLOW(CFS) =  2.70
PIPE TRAVEL TIME(MIN.) =  0.84  Tc(MIN.) =  6.01
LONGEST FLOWPATH FROM NODE      235.00 TO NODE      247.00 =  422.50 FEET.
*****
FLOW PROCESS FROM NODE      255.00 TO NODE      247.00 IS CODE =  81
-----
>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<
=====
  100 YEAR RAINFALL INTENSITY(INCH/HOUR) =  4.209
*USER SPECIFIED(SUBAREA):
USER-SPECIFIED RUNOFF COEFFICIENT = .9500

```

S.C.S. CURVE NUMBER (AMC II) = 0  
 AREA-AVERAGE RUNOFF COEFFICIENT = 0.9500  
 SUBAREA AREA (ACRES) = 0.84 SUBAREA RUNOFF (CFS) = 3.36  
 TOTAL AREA (ACRES) = 1.5 TOTAL RUNOFF (CFS) = 5.96  
 TC (MIN.) = 6.01

\*\*\*\*\*  
 FLOW PROCESS FROM NODE 247.00 TO NODE 260.00 IS CODE = 31  
 -----

>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<<  
 >>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<<

=====

ELEVATION DATA: UPSTREAM (FEET) = 34.90 DOWNSTREAM (FEET) = 34.50  
 FLOW LENGTH (FEET) = 60.50 MANNING'S N = 0.013  
 DEPTH OF FLOW IN 18.0 INCH PIPE IS 11.5 INCHES  
 PIPE-FLOW VELOCITY (FEET/SEC.) = 5.01  
 ESTIMATED PIPE DIAMETER (INCH) = 18.00 NUMBER OF PIPES = 1  
 PIPE-FLOW (CFS) = 5.96  
 PIPE TRAVEL TIME (MIN.) = 0.20 Tc (MIN.) = 6.21  
 LONGEST FLOWPATH FROM NODE 235.00 TO NODE 260.00 = 483.00 FEET.

\*\*\*\*\*  
 FLOW PROCESS FROM NODE 260.00 TO NODE 230.00 IS CODE = 1  
 -----

>>>>DESIGNATE INDEPENDENT STREAM FOR CONFLUENCE<<<<<  
 >>>>AND COMPUTE VARIOUS CONFLUENCED STREAM VALUES<<<<<

=====

TOTAL NUMBER OF STREAMS = 2  
 CONFLUENCE VALUES USED FOR INDEPENDENT STREAM 2 ARE:  
 TIME OF CONCENTRATION (MIN.) = 6.21  
 RAINFALL INTENSITY (INCH/HR) = 4.17  
 TOTAL STREAM AREA (ACRES) = 1.49  
 PEAK FLOW RATE (CFS) AT CONFLUENCE = 5.96

\*\* CONFLUENCE DATA \*\*

STREAM NUMBER	RUNOFF (CFS)	Tc (MIN.)	INTENSITY (INCH/HOUR)	AREA (ACRE)
1	7.27	6.05	4.201	1.93
2	5.96	6.21	4.171	1.49

RAINFALL INTENSITY AND TIME OF CONCENTRATION RATIO  
 CONFLUENCE FORMULA USED FOR 2 STREAMS.

\*\* PEAK FLOW RATE TABLE \*\*

STREAM NUMBER	RUNOFF (CFS)	Tc (MIN.)	INTENSITY (INCH/HOUR)
1	13.07	6.05	4.201
2	13.18	6.21	4.171

COMPUTED CONFLUENCE ESTIMATES ARE AS FOLLOWS:

PEAK FLOW RATE (CFS) = 13.18 Tc (MIN.) = 6.21  
 TOTAL AREA (ACRES) = 3.4  
 LONGEST FLOWPATH FROM NODE 235.00 TO NODE 230.00 = 483.00 FEET.

\*\*\*\*\*  
 FLOW PROCESS FROM NODE 260.00 TO NODE 265.00 IS CODE = 31  
 -----

>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<<  
 >>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<<

=====

ELEVATION DATA: UPSTREAM (FEET) = 34.50 DOWNSTREAM (FEET) = 20.00  
 FLOW LENGTH (FEET) = 205.50 MANNING'S N = 0.013  
 DEPTH OF FLOW IN 15.0 INCH PIPE IS 10.2 INCHES  
 PIPE-FLOW VELOCITY (FEET/SEC.) = 14.77  
 ESTIMATED PIPE DIAMETER (INCH) = 15.00 NUMBER OF PIPES = 1



```

PIPE-FLOW(CFS) =      13.18
PIPE TRAVEL TIME(MIN.) = 0.23   Tc(MIN.) = 6.44
LONGEST FLOWPATH FROM NODE 235.00 TO NODE 265.00 = 688.50 FEET.

*****
FLOW PROCESS FROM NODE 275.00 TO NODE 265.00 IS CODE = 81
-----
>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<
=====
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.127
*USER SPECIFIED(SUBAREA):
USER-SPECIFIED RUNOFF COEFFICIENT = .4500
S.C.S. CURVE NUMBER (AMC II) = 0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.8853
SUBAREA AREA(ACRES) = 0.26   SUBAREA RUNOFF(CFS) = 0.48
TOTAL AREA(ACRES) = 3.7   TOTAL RUNOFF(CFS) = 13.44
TC(MIN.) = 6.44
=====
END OF STUDY SUMMARY:
TOTAL AREA(ACRES) = 3.7   TC(MIN.) = 6.44
PEAK FLOW RATE(CFS) = 13.44
=====
END OF RATIONAL METHOD ANALYSIS

```

## Proposed Mitigated Condition

\*\*\*\*\*

RATIONAL METHOD HYDROLOGY COMPUTER PROGRAM PACKAGE  
Reference: SAN DIEGO COUNTY FLOOD CONTROL DISTRICT  
2003,1985,1981 HYDROLOGY MANUAL  
(c) Copyright 1982-2016 Advanced Engineering Software (aes)  
Ver. 23.0 Release Date: 07/01/2016 License ID 1452

Analysis prepared by:

Pasco Laret Suiter & Associates  
119 Aberdeen Drive  
Cardiff, California 92007  
858-259-8212

\*\*\*\*\* DESCRIPTION OF STUDY \*\*\*\*\*  
\* 3272 PALM AND HOLLISTER \*  
\* PROPOSED CONDITION MITIGATED \*  
\* 100-YR \*  
\*\*\*\*\*

FILE NAME: 3272PD00.DAT  
TIME/DATE OF STUDY: 11:32 04/04/2023

-----  
USER SPECIFIED HYDROLOGY AND HYDRAULIC MODEL INFORMATION:  
-----

USER SPECIFIED STORM EVENT (YEAR) = 100.00  
SPECIFIED MINIMUM PIPE SIZE (INCH) = 4.00  
SPECIFIED PERCENT OF GRADIENTS (DECIMAL) TO USE FOR FRICTION SLOPE = 0.90  
RAINFALL-INTENSITY ADJUSTMENT FACTOR = 1.000

\*USER SPECIFIED:  
NUMBER OF [TIME, INTENSITY] DATA PAIRS = 9

- 1) 5.000; 4.400
- 2) 10.000; 3.450
- 3) 15.000; 2.900
- 4) 20.000; 2.500
- 5) 25.000; 2.200
- 6) 30.000; 2.000
- 7) 40.000; 1.700
- 8) 50.000; 1.500
- 9) 60.000; 1.300

SAN DIEGO HYDROLOGY MANUAL "C"-VALUES USED FOR RATIONAL METHOD

NOTE: ONLY PEAK CONFLUENCE VALUES CONSIDERED

\*USER-DEFINED STREET-SECTIONS FOR COUPLED PIPEFLOW AND STREETFLOW MODEL\*

NO.	HALF- CROWN TO		STREET-CROSSFALL:		CURB HEIGHT (FT)	GUTTER-GEOMETRIES:			MANNING FACTOR (n)
	WIDTH (FT)	CROSSFALL (FT)	IN- / SIDE	OUT- / SIDE/ WAY		WIDTH (FT)	LIP (FT)	HIKE (FT)	
1	12.0	7.0	0.020	0.020/0.020	0.50	1.50	0.0100	0.125	0.0180

GLOBAL STREET FLOW-DEPTH CONSTRAINTS:

- 1. Relative Flow-Depth = 0.00 FEET  
as (Maximum Allowable Street Flow Depth) - (Top-of-Curb)
- 2. (Depth)\*(Velocity) Constraint = 6.0 (FT\*FT/S)

\*SIZE PIPE WITH A FLOW CAPACITY GREATER THAN  
OR EQUAL TO THE UPSTREAM TRIBUTARY PIPE.\*

\*\*\*\*\*

FLOW PROCESS FROM NODE 100.00 TO NODE 105.00 IS CODE = 21

-----  
>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<<  
=====

\*USER SPECIFIED (SUBAREA) :  
USER-SPECIFIED RUNOFF COEFFICIENT = .9500

```

S.C.S. CURVE NUMBER (AMC II) = 0
INITIAL SUBAREA FLOW-LENGTH(FEET) = 46.00
UPSTREAM ELEVATION(FEET) = 46.50
DOWNSTREAM ELEVATION(FEET) = 45.50
ELEVATION DIFFERENCE(FEET) = 1.00
URBAN SUBAREA OVERLAND TIME OF FLOW(MIN.) = 1.414
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.400
NOTE: RAINFALL INTENSITY IS BASED ON Tc = 5-MINUTE.
SUBAREA RUNOFF(CFS) = 0.88
TOTAL AREA(ACRES) = 0.21 TOTAL RUNOFF(CFS) = 0.88

*****
FLOW PROCESS FROM NODE 100.00 TO NODE 105.00 IS CODE = 22
-----
>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<
=====
*USER SPECIFIED(SUBAREA):
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) = 0
USER SPECIFIED Tc(MIN.) = 5.000
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.400
SUBAREA RUNOFF(CFS) = 0.88
TOTAL AREA(ACRES) = 0.21 TOTAL RUNOFF(CFS) = 0.88

*****
FLOW PROCESS FROM NODE 105.00 TO NODE 110.00 IS CODE = 31
-----
>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) = 41.50 DOWNSTREAM(FEET) = 41.00
FLOW LENGTH(FEET) = 45.30 MANNING'S N = 0.013
DEPTH OF FLOW IN 9.0 INCH PIPE IS 4.7 INCHES
PIPE-FLOW VELOCITY(FEET/SEC.) = 3.79
ESTIMATED PIPE DIAMETER(INCH) = 9.00 NUMBER OF PIPES = 1
PIPE-FLOW(CFS) = 0.88
PIPE TRAVEL TIME(MIN.) = 0.20 Tc(MIN.) = 5.20
LONGEST FLOWPATH FROM NODE 100.00 TO NODE 110.00 = 91.30 FEET.

*****
FLOW PROCESS FROM NODE 115.00 TO NODE 110.00 IS CODE = 81
-----
>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<
=====
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.362
*USER SPECIFIED(SUBAREA):
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) = 0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.9500
SUBAREA AREA(ACRES) = 0.25 SUBAREA RUNOFF(CFS) = 1.04
TOTAL AREA(ACRES) = 0.5 TOTAL RUNOFF(CFS) = 1.91
TC(MIN.) = 5.20

*****
FLOW PROCESS FROM NODE 110.00 TO NODE 112.00 IS CODE = 31
-----
>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) = 41.00 DOWNSTREAM(FEET) = 40.00
FLOW LENGTH(FEET) = 26.90 MANNING'S N = 0.013
DEPTH OF FLOW IN 9.0 INCH PIPE IS 5.2 INCHES
PIPE-FLOW VELOCITY(FEET/SEC.) = 7.24
ESTIMATED PIPE DIAMETER(INCH) = 9.00 NUMBER OF PIPES = 1
PIPE-FLOW(CFS) = 1.91

```

```

PIPE TRAVEL TIME(MIN.) = 0.06    Tc(MIN.) = 5.26
LONGEST FLOWPATH FROM NODE 100.00 TO NODE 112.00 = 118.20 FEET.
*****
FLOW PROCESS FROM NODE 120.00 TO NODE 112.00 IS CODE = 81
-----
>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<
=====
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.350
*USER SPECIFIED(SUBAREA):
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) = 0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.9500
SUBAREA AREA(ACRES) = 0.56    SUBAREA RUNOFF(CFS) = 2.31
TOTAL AREA(ACRES) = 1.0    TOTAL RUNOFF(CFS) = 4.22
TC(MIN.) = 5.26
*****
FLOW PROCESS FROM NODE 112.00 TO NODE 125.00 IS CODE = 31
-----
>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) = 39.00    DOWNSTREAM(FEET) = 38.00
FLOW LENGTH(FEET) = 89.30    MANNING'S N = 0.013
DEPTH OF FLOW IN 15.0 INCH PIPE IS 8.8 INCHES
PIPE-FLOW VELOCITY(FEET/SEC.) = 5.62
ESTIMATED PIPE DIAMETER(INCH) = 15.00    NUMBER OF PIPES = 1
PIPE-FLOW(CFS) = 4.22
PIPE TRAVEL TIME(MIN.) = 0.26    Tc(MIN.) = 5.53
LONGEST FLOWPATH FROM NODE 100.00 TO NODE 125.00 = 207.50 FEET.
*****
FLOW PROCESS FROM NODE 125.00 TO NODE 125.00 IS CODE = 1
-----
>>>>DESIGNATE INDEPENDENT STREAM FOR CONFLUENCE<<<<
=====
TOTAL NUMBER OF STREAMS = 2
CONFLUENCE VALUES USED FOR INDEPENDENT STREAM 1 ARE:
TIME OF CONCENTRATION(MIN.) = 5.53
RAINFALL INTENSITY(INCH/HR) = 4.30
TOTAL STREAM AREA(ACRES) = 1.02
PEAK FLOW RATE(CFS) AT CONFLUENCE = 4.22
*****
FLOW PROCESS FROM NODE 130.00 TO NODE 135.00 IS CODE = 21
-----
>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<
=====
*USER SPECIFIED(SUBAREA):
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) = 0
INITIAL SUBAREA FLOW-LENGTH(FEET) = 63.00
UPSTREAM ELEVATION(FEET) = 45.70
DOWNSTREAM ELEVATION(FEET) = 45.50
ELEVATION DIFFERENCE(FEET) = 0.20
URBAN SUBAREA OVERLAND TIME OF FLOW(MIN.) = 2.405
WARNING: INITIAL SUBAREA FLOW PATH LENGTH IS GREATER THAN
         THE MAXIMUM OVERLAND FLOW LENGTH = 50.00
         (Reference: Table 3-1B of Hydrology Manual)
         THE MAXIMUM OVERLAND FLOW LENGTH IS USED IN Tc CALCULATION!
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.400
NOTE: RAINFALL INTENSITY IS BASED ON Tc = 5-MINUTE.
SUBAREA RUNOFF(CFS) = 0.21
TOTAL AREA(ACRES) = 0.05    TOTAL RUNOFF(CFS) = 0.21

```

```

*****
FLOW PROCESS FROM NODE      130.00 TO NODE      135.00 IS CODE =  22
-----
>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<
=====
*USER SPECIFIED(SUBAREA) :
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) =  0
USER SPECIFIED Tc(MIN.) =  5.000
  100 YEAR RAINFALL INTENSITY(INCH/HOUR) =  4.400
SUBAREA RUNOFF(CFS) =  0.21
TOTAL AREA(ACRES) =  0.05  TOTAL RUNOFF(CFS) =  0.21
*****
FLOW PROCESS FROM NODE      135.00 TO NODE      140.00 IS CODE =  62
-----
>>>>COMPUTE STREET FLOW TRAVEL TIME THRU SUBAREA<<<<
>>>>(STREET TABLE SECTION #  1 USED)<<<<
=====
UPSTREAM ELEVATION(FEET) =  45.50  DOWNSTREAM ELEVATION(FEET) =  44.50
STREET LENGTH(FEET) =  86.00  CURB HEIGHT(INCHES) =  6.0
STREET HALFWIDTH(FEET) =  12.00

DISTANCE FROM CROWN TO CROSSFALL GRADEBREAK(FEET) =  7.00
INSIDE STREET CROSSFALL(DECIMAL) =  0.020
OUTSIDE STREET CROSSFALL(DECIMAL) =  0.020

SPECIFIED NUMBER OF HALFSTREETS CARRYING RUNOFF =  1
STREET PARKWAY CROSSFALL(DECIMAL) =  0.020
Manning's FRICTION FACTOR for Streetflow Section(curbs-to-curbs) =  0.0180
Manning's FRICTION FACTOR for Back-of-Walk Flow Section =  0.0200

  **TRAVEL TIME COMPUTED USING ESTIMATED FLOW(CFS) =  1.34
  STREETFLOW MODEL RESULTS USING ESTIMATED FLOW:
  STREET FLOW DEPTH(FEET) =  0.27
  HALFSTREET FLOOD WIDTH(FEET) =  8.14
  AVERAGE FLOW VELOCITY(FEET/SEC.) =  1.79
  PRODUCT OF DEPTH&VELOCITY(FT*FT/SEC.) =  0.48
STREET FLOW TRAVEL TIME(MIN.) =  0.80  Tc(MIN.) =  5.80
  100 YEAR RAINFALL INTENSITY(INCH/HOUR) =  4.248
*USER SPECIFIED(SUBAREA) :
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) =  0
AREA-AVERAGE RUNOFF COEFFICIENT =  0.950
SUBAREA AREA(ACRES) =  0.56  SUBAREA RUNOFF(CFS) =  2.26
TOTAL AREA(ACRES) =  0.6  PEAK FLOW RATE(CFS) =  2.46

END OF SUBAREA STREET FLOW HYDRAULICS:
DEPTH(FEET) =  0.32  HALFSTREET FLOOD WIDTH(FEET) =  10.55
FLOW VELOCITY(FEET/SEC.) =  2.05  DEPTH*VELOCITY(FT*FT/SEC.) =  0.65
LONGEST FLOWPATH FROM NODE      130.00 TO NODE      140.00 =  149.00 FEET.
*****
FLOW PROCESS FROM NODE      140.00 TO NODE      145.00 IS CODE =  31
-----
>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) =  40.50  DOWNSTREAM(FEET) =  38.00
FLOW LENGTH(FEET) =  45.10  MANNING'S N =  0.013
DEPTH OF FLOW IN  9.0 INCH PIPE IS  5.4 INCHES
PIPE-FLOW VELOCITY(FEET/SEC.) =  8.96
ESTIMATED PIPE DIAMETER(INCH) =  9.00  NUMBER OF PIPES =  1
PIPE-FLOW(CFS) =  2.46

```

```

PIPE TRAVEL TIME (MIN.) = 0.08    Tc (MIN.) = 5.89
LONGEST FLOWPATH FROM NODE 130.00 TO NODE 145.00 = 194.10 FEET.
*****
FLOW PROCESS FROM NODE 145.00 TO NODE 125.00 IS CODE = 1
-----
>>>>DESIGNATE INDEPENDENT STREAM FOR CONFLUENCE<<<<
>>>>AND COMPUTE VARIOUS CONFLUENCED STREAM VALUES<<<<
=====
TOTAL NUMBER OF STREAMS = 2
CONFLUENCE VALUES USED FOR INDEPENDENT STREAM 2 ARE:
TIME OF CONCENTRATION (MIN.) = 5.89
RAINFALL INTENSITY (INCH/HR) = 4.23
TOTAL STREAM AREA (ACRES) = 0.61
PEAK FLOW RATE (CFS) AT CONFLUENCE = 2.46

** CONFLUENCE DATA **
STREAM    RUNOFF      Tc      INTENSITY      AREA
NUMBER    (CFS)        (MIN.)  (INCH/HOUR)    (ACRE)
  1         4.22         5.53      4.300          1.02
  2         2.46         5.89      4.232          0.61

RAINFALL INTENSITY AND TIME OF CONCENTRATION RATIO
CONFLUENCE FORMULA USED FOR 2 STREAMS.

** PEAK FLOW RATE TABLE **
STREAM    RUNOFF      Tc      INTENSITY
NUMBER    (CFS)        (MIN.)  (INCH/HOUR)
  1         6.53         5.53      4.300
  2         6.61         5.89      4.232

COMPUTED CONFLUENCE ESTIMATES ARE AS FOLLOWS:
PEAK FLOW RATE (CFS) = 6.61    Tc (MIN.) = 5.89
TOTAL AREA (ACRES) = 1.6
LONGEST FLOWPATH FROM NODE 100.00 TO NODE 125.00 = 207.50 FEET.
*****
FLOW PROCESS FROM NODE 145.00 TO NODE 125.00 IS CODE = 7
-----
>>>>USER SPECIFIED HYDROLOGY INFORMATION AT NODE<<<<
=====
USER-SPECIFIED VALUES ARE AS FOLLOWS:
TC (MIN) = 15.59    RAIN INTENSITY (INCH/HOUR) = 2.85
TOTAL AREA (ACRES) = 1.60    TOTAL RUNOFF (CFS) = 1.20
*****
FLOW PROCESS FROM NODE 145.00 TO NODE 150.00 IS CODE = 31
-----
>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<
=====
ELEVATION DATA: UPSTREAM (FEET) = 38.00    DOWNSTREAM (FEET) = 23.00
FLOW LENGTH (FEET) = 294.00    MANNING'S N = 0.013
DEPTH OF FLOW IN 6.0 INCH PIPE IS 4.9 INCHES
PIPE-FLOW VELOCITY (FEET/SEC.) = 6.99
ESTIMATED PIPE DIAMETER (INCH) = 6.00    NUMBER OF PIPES = 1
PIPE-FLOW (CFS) = 1.20
PIPE TRAVEL TIME (MIN.) = 0.70    Tc (MIN.) = 16.29
LONGEST FLOWPATH FROM NODE 100.00 TO NODE 150.00 = 501.50 FEET.
*****
FLOW PROCESS FROM NODE 150.00 TO NODE 150.00 IS CODE = 1
-----
>>>>DESIGNATE INDEPENDENT STREAM FOR CONFLUENCE<<<<
=====

```

```

TOTAL NUMBER OF STREAMS = 2
CONFLUENCE VALUES USED FOR INDEPENDENT STREAM 1 ARE:
TIME OF CONCENTRATION(MIN.) = 16.29
RAINFALL INTENSITY(INCH/HR) = 2.80
TOTAL STREAM AREA(ACRES) = 1.60
PEAK FLOW RATE(CFS) AT CONFLUENCE = 1.20

*****
FLOW PROCESS FROM NODE 155.00 TO NODE 150.00 IS CODE = 7
-----
>>>>USER SPECIFIED HYDROLOGY INFORMATION AT NODE<<<<
=====
USER-SPECIFIED VALUES ARE AS FOLLOWS:
TC(MIN) = 6.33 RAIN INTENSITY(INCH/HOUR) = 4.15
TOTAL AREA(ACRES) = 0.28 TOTAL RUNOFF(CFS) = 0.52

*****
FLOW PROCESS FROM NODE 150.00 TO NODE 150.00 IS CODE = 1
-----
>>>>DESIGNATE INDEPENDENT STREAM FOR CONFLUENCE<<<<
>>>>AND COMPUTE VARIOUS CONFLUENCED STREAM VALUES<<<<
=====
TOTAL NUMBER OF STREAMS = 2
CONFLUENCE VALUES USED FOR INDEPENDENT STREAM 2 ARE:
TIME OF CONCENTRATION(MIN.) = 6.33
RAINFALL INTENSITY(INCH/HR) = 4.15
TOTAL STREAM AREA(ACRES) = 0.28
PEAK FLOW RATE(CFS) AT CONFLUENCE = 0.52

** CONFLUENCE DATA **
STREAM RUNOFF Tc INTENSITY AREA
NUMBER (CFS) (MIN.) (INCH/HOUR) (ACRE)
1 1.20 16.29 2.797 1.60
2 0.52 6.33 4.147 0.28

RAINFALL INTENSITY AND TIME OF CONCENTRATION RATIO
CONFLUENCE FORMULA USED FOR 2 STREAMS.

** PEAK FLOW RATE TABLE **
STREAM RUNOFF Tc INTENSITY
NUMBER (CFS) (MIN.) (INCH/HOUR)
1 0.99 6.33 4.147
2 1.55 16.29 2.797

COMPUTED CONFLUENCE ESTIMATES ARE AS FOLLOWS:
PEAK FLOW RATE(CFS) = 1.55 Tc(MIN.) = 16.29
TOTAL AREA(ACRES) = 1.9
LONGEST FLOWPATH FROM NODE 100.00 TO NODE 150.00 = 501.50 FEET.

*****
FLOW PROCESS FROM NODE 200.00 TO NODE 205.00 IS CODE = 21
-----
>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<
=====
*USER SPECIFIED(SUBAREA) :
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) = 0
INITIAL SUBAREA FLOW-LENGTH(FEET) = 45.00
UPSTREAM ELEVATION(FEET) = 45.70
DOWNSTREAM ELEVATION(FEET) = 45.00
ELEVATION DIFFERENCE(FEET) = 0.70
URBAN SUBAREA OVERLAND TIME OF FLOW(MIN.) = 1.563
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.400
NOTE: RAINFALL INTENSITY IS BASED ON Tc = 5-MINUTE.
SUBAREA RUNOFF(CFS) = 0.42

```



```

TOTAL AREA (ACRES) =      0.10   TOTAL RUNOFF (CFS) =      0.42
*****
FLOW PROCESS FROM NODE    200.00 TO NODE    205.00 IS CODE =  22
-----
>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<
=====
*USER SPECIFIED (SUBAREA) :
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) =    0
USER SPECIFIED Tc (MIN.) =    5.000
  100 YEAR RAINFALL INTENSITY (INCH/HOUR) =  4.400
SUBAREA RUNOFF (CFS) =      0.42
TOTAL AREA (ACRES) =      0.10   TOTAL RUNOFF (CFS) =      0.42
*****
FLOW PROCESS FROM NODE    210.00 TO NODE    205.00 IS CODE =  81
-----
>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<
=====
  100 YEAR RAINFALL INTENSITY (INCH/HOUR) =  4.400
*USER SPECIFIED (SUBAREA) :
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) =    0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.9500
SUBAREA AREA (ACRES) =    0.39   SUBAREA RUNOFF (CFS) =    1.63
TOTAL AREA (ACRES) =      0.5   TOTAL RUNOFF (CFS) =    2.05
TC (MIN.) =    5.00
*****
FLOW PROCESS FROM NODE    205.00 TO NODE    215.00 IS CODE =  31
-----
>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<
=====
ELEVATION DATA: UPSTREAM (FEET) =    40.30   DOWNSTREAM (FEET) =    39.70
FLOW LENGTH (FEET) =    77.00   MANNING'S N =    0.013
DEPTH OF FLOW IN 12.0 INCH PIPE IS  7.3 INCHES
PIPE-FLOW VELOCITY (FEET/SEC.) =    4.09
ESTIMATED PIPE DIAMETER (INCH) =  12.00   NUMBER OF PIPES =    1
PIPE-FLOW (CFS) =      2.05
PIPE TRAVEL TIME (MIN.) =    0.31   Tc (MIN.) =    5.31
LONGEST FLOWPATH FROM NODE    200.00 TO NODE    215.00 =    122.00 FEET.
*****
FLOW PROCESS FROM NODE    215.00 TO NODE    215.00 IS CODE =  81
-----
>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<
=====
  100 YEAR RAINFALL INTENSITY (INCH/HOUR) =  4.340
*USER SPECIFIED (SUBAREA) :
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) =    0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.9500
SUBAREA AREA (ACRES) =    0.11   SUBAREA RUNOFF (CFS) =    0.45
TOTAL AREA (ACRES) =      0.6   TOTAL RUNOFF (CFS) =    2.47
TC (MIN.) =    5.31
*****
FLOW PROCESS FROM NODE    215.00 TO NODE    220.00 IS CODE =  31
-----
>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<
=====
ELEVATION DATA: UPSTREAM (FEET) =    39.70   DOWNSTREAM (FEET) =    39.10

```

```

FLOW LENGTH(FEET) = 76.70 MANNING'S N = 0.013
DEPTH OF FLOW IN 12.0 INCH PIPE IS 8.3 INCHES
PIPE-FLOW VELOCITY(FEET/SEC.) = 4.26
ESTIMATED PIPE DIAMETER(INCH) = 12.00 NUMBER OF PIPES = 1
PIPE-FLOW(CFS) = 2.47
PIPE TRAVEL TIME(MIN.) = 0.30 Tc(MIN.) = 5.61
LONGEST FLOWPATH FROM NODE 200.00 TO NODE 220.00 = 198.70 FEET.
*****
FLOW PROCESS FROM NODE 220.00 TO NODE 220.00 IS CODE = 81
-----
>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<
=====
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.283
*USER SPECIFIED(SUBAREA):
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) = 0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.9500
SUBAREA AREA(ACRES) = 0.38 SUBAREA RUNOFF(CFS) = 1.55
TOTAL AREA(ACRES) = 1.0 TOTAL RUNOFF(CFS) = 3.99
TC(MIN.) = 5.61
*****
FLOW PROCESS FROM NODE 220.00 TO NODE 222.00 IS CODE = 31
-----
>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) = 39.10 DOWNSTREAM(FEET) = 38.00
FLOW LENGTH(FEET) = 114.50 MANNING'S N = 0.013
DEPTH OF FLOW IN 15.0 INCH PIPE IS 8.9 INCHES
PIPE-FLOW VELOCITY(FEET/SEC.) = 5.24
ESTIMATED PIPE DIAMETER(INCH) = 15.00 NUMBER OF PIPES = 1
PIPE-FLOW(CFS) = 3.99
PIPE TRAVEL TIME(MIN.) = 0.36 Tc(MIN.) = 5.98
LONGEST FLOWPATH FROM NODE 200.00 TO NODE 222.00 = 313.20 FEET.
*****
FLOW PROCESS FROM NODE 225.00 TO NODE 222.00 IS CODE = 81
-----
>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<
=====
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.214
*USER SPECIFIED(SUBAREA):
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) = 0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.9500
SUBAREA AREA(ACRES) = 0.71 SUBAREA RUNOFF(CFS) = 2.84
TOTAL AREA(ACRES) = 1.7 TOTAL RUNOFF(CFS) = 6.77
TC(MIN.) = 5.98
*****
FLOW PROCESS FROM NODE 270.00 TO NODE 222.00 IS CODE = 81
-----
>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<
=====
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.214
*USER SPECIFIED(SUBAREA):
USER-SPECIFIED RUNOFF COEFFICIENT = .5000
S.C.S. CURVE NUMBER (AMC II) = 0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.8940
SUBAREA AREA(ACRES) = 0.24 SUBAREA RUNOFF(CFS) = 0.51
TOTAL AREA(ACRES) = 1.9 TOTAL RUNOFF(CFS) = 7.27
TC(MIN.) = 5.98

```

```

*****
FLOW PROCESS FROM NODE      222.00 TO NODE      230.00 IS CODE =  31
-----
>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) =    37.00  DOWNSTREAM(FEET) =    34.50
FLOW LENGTH(FEET) =    45.80  MANNING'S N =  0.013
DEPTH OF FLOW IN 12.0 INCH PIPE IS  9.1 INCHES
PIPE-FLOW VELOCITY(FEET/SEC.) =  11.41
ESTIMATED PIPE DIAMETER(INCH) =  12.00  NUMBER OF PIPES =  1
PIPE-FLOW(CFS) =    7.27
PIPE TRAVEL TIME(MIN.) =  0.07  Tc(MIN.) =  6.05
LONGEST FLOWPATH FROM NODE  200.00 TO NODE  230.00 =  359.00 FEET.
*****
FLOW PROCESS FROM NODE      230.00 TO NODE      230.00 IS CODE =  1
-----
>>>>DESIGNATE INDEPENDENT STREAM FOR CONFLUENCE<<<<<
=====
TOTAL NUMBER OF STREAMS =  2
CONFLUENCE VALUES USED FOR INDEPENDENT STREAM  1 ARE:
TIME OF CONCENTRATION(MIN.) =  6.05
RAINFALL INTENSITY(INCH/HR) =  4.20
TOTAL STREAM AREA(ACRES) =  1.93
PEAK FLOW RATE(CFS) AT CONFLUENCE =  7.27
*****
FLOW PROCESS FROM NODE      235.00 TO NODE      240.00 IS CODE =  21
-----
>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<<
=====
*USER SPECIFIED(SUBAREA):
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) =  0
INITIAL SUBAREA FLOW-LENGTH(FEET) =  165.00
UPSTREAM ELEVATION(FEET) =  44.50
DOWNSTREAM ELEVATION(FEET) =  42.00
ELEVATION DIFFERENCE(FEET) =  2.50
URBAN SUBAREA OVERLAND TIME OF FLOW(MIN.) =  1.897
WARNING: INITIAL SUBAREA FLOW PATH LENGTH IS GREATER THAN
         THE MAXIMUM OVERLAND FLOW LENGTH =  65.15
         (Reference: Table 3-1B of Hydrology Manual)
         THE MAXIMUM OVERLAND FLOW LENGTH IS USED IN Tc CALCULATION!
100 YEAR RAINFALL INTENSITY(INCH/HOUR) =  4.400
NOTE: RAINFALL INTENSITY IS BASED ON Tc = 5-MINUTE.
SUBAREA RUNOFF(CFS) =  1.42
TOTAL AREA(ACRES) =  0.34  TOTAL RUNOFF(CFS) =  1.42
*****
FLOW PROCESS FROM NODE      235.00 TO NODE      240.00 IS CODE =  22
-----
>>>>RATIONAL METHOD INITIAL SUBAREA ANALYSIS<<<<<
=====
*USER SPECIFIED(SUBAREA):
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) =  0
USER SPECIFIED Tc(MIN.) =  5.000
100 YEAR RAINFALL INTENSITY(INCH/HOUR) =  4.400
SUBAREA RUNOFF(CFS) =  1.42
TOTAL AREA(ACRES) =  0.34  TOTAL RUNOFF(CFS) =  1.42
*****
FLOW PROCESS FROM NODE      240.00 TO NODE      245.00 IS CODE =  31
-----

```

```

>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) = 38.00 DOWNSTREAM(FEET) = 37.60
FLOW LENGTH(FEET) = 39.60 MANNING'S N = 0.013
DEPTH OF FLOW IN 9.0 INCH PIPE IS 6.7 INCHES
PIPE-FLOW VELOCITY(FEET/SEC.) = 4.04
ESTIMATED PIPE DIAMETER(INCH) = 9.00 NUMBER OF PIPES = 1
PIPE-FLOW(CFS) = 1.42
PIPE TRAVEL TIME(MIN.) = 0.16 Tc(MIN.) = 5.16
LONGEST FLOWPATH FROM NODE 235.00 TO NODE 245.00 = 204.60 FEET.

*****
FLOW PROCESS FROM NODE 250.00 TO NODE 245.00 IS CODE = 81
-----
>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<
=====
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.369
*USER SPECIFIED(SUBAREA):
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) = 0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.9500
SUBAREA AREA(ACRES) = 0.31 SUBAREA RUNOFF(CFS) = 1.29
TOTAL AREA(ACRES) = 0.6 TOTAL RUNOFF(CFS) = 2.70
TC(MIN.) = 5.16

*****
FLOW PROCESS FROM NODE 245.00 TO NODE 247.00 IS CODE = 31
-----
>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) = 37.60 DOWNSTREAM(FEET) = 35.90
FLOW LENGTH(FEET) = 217.90 MANNING'S N = 0.013
DEPTH OF FLOW IN 12.0 INCH PIPE IS 8.9 INCHES
PIPE-FLOW VELOCITY(FEET/SEC.) = 4.31
ESTIMATED PIPE DIAMETER(INCH) = 12.00 NUMBER OF PIPES = 1
PIPE-FLOW(CFS) = 2.70
PIPE TRAVEL TIME(MIN.) = 0.84 Tc(MIN.) = 6.01
LONGEST FLOWPATH FROM NODE 235.00 TO NODE 247.00 = 422.50 FEET.

*****
FLOW PROCESS FROM NODE 255.00 TO NODE 247.00 IS CODE = 81
-----
>>>>ADDITION OF SUBAREA TO MAINLINE PEAK FLOW<<<<
=====
100 YEAR RAINFALL INTENSITY(INCH/HOUR) = 4.209
*USER SPECIFIED(SUBAREA):
USER-SPECIFIED RUNOFF COEFFICIENT = .9500
S.C.S. CURVE NUMBER (AMC II) = 0
AREA-AVERAGE RUNOFF COEFFICIENT = 0.9500
SUBAREA AREA(ACRES) = 0.84 SUBAREA RUNOFF(CFS) = 3.36
TOTAL AREA(ACRES) = 1.5 TOTAL RUNOFF(CFS) = 5.96
TC(MIN.) = 6.01

*****
FLOW PROCESS FROM NODE 247.00 TO NODE 260.00 IS CODE = 31
-----
>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) = 34.90 DOWNSTREAM(FEET) = 34.50
FLOW LENGTH(FEET) = 60.50 MANNING'S N = 0.013
DEPTH OF FLOW IN 18.0 INCH PIPE IS 11.5 INCHES
PIPE-FLOW VELOCITY(FEET/SEC.) = 5.01

```

```

ESTIMATED PIPE DIAMETER(INCH) = 18.00    NUMBER OF PIPES = 1
PIPE-FLOW(CFS) = 5.96
PIPE TRAVEL TIME(MIN.) = 0.20    Tc(MIN.) = 6.21
LONGEST FLOWPATH FROM NODE 235.00 TO NODE 260.00 = 483.00 FEET.
*****
FLOW PROCESS FROM NODE 260.00 TO NODE 230.00 IS CODE = 1
-----
>>>>DESIGNATE INDEPENDENT STREAM FOR CONFLUENCE<<<<<
>>>>AND COMPUTE VARIOUS CONFLUENCED STREAM VALUES<<<<<
=====
TOTAL NUMBER OF STREAMS = 2
CONFLUENCE VALUES USED FOR INDEPENDENT STREAM 2 ARE:
TIME OF CONCENTRATION(MIN.) = 6.21
RAINFALL INTENSITY(INCH/HR) = 4.17
TOTAL STREAM AREA(ACRES) = 1.49
PEAK FLOW RATE(CFS) AT CONFLUENCE = 5.96

** CONFLUENCE DATA **
STREAM      RUNOFF      Tc      INTENSITY      AREA
NUMBER      (CFS)      (MIN.)  (INCH/HOUR)    (ACRE)
1           7.27      6.05    4.201          1.93
2           5.96      6.21    4.171          1.49

RAINFALL INTENSITY AND TIME OF CONCENTRATION RATIO
CONFLUENCE FORMULA USED FOR 2 STREAMS.

** PEAK FLOW RATE TABLE **
STREAM      RUNOFF      Tc      INTENSITY
NUMBER      (CFS)      (MIN.)  (INCH/HOUR)
1           13.07     6.05    4.201
2           13.18     6.21    4.171

COMPUTED CONFLUENCE ESTIMATES ARE AS FOLLOWS:
PEAK FLOW RATE(CFS) = 13.18    Tc(MIN.) = 6.21
TOTAL AREA(ACRES) = 3.4
LONGEST FLOWPATH FROM NODE 235.00 TO NODE 230.00 = 483.00 FEET.
*****
FLOW PROCESS FROM NODE 260.00 TO NODE 230.00 IS CODE = 7
-----
>>>>USER SPECIFIED HYDROLOGY INFORMATION AT NODE<<<<<
=====
USER-SPECIFIED VALUES ARE AS FOLLOWS:
TC(MIN) = 13.61    RAIN INTENSITY(INCH/HOUR) = 3.05
TOTAL AREA(ACRES) = 3.40    TOTAL RUNOFF(CFS) = 2.89
*****
FLOW PROCESS FROM NODE 260.00 TO NODE 265.00 IS CODE = 31
-----
>>>>COMPUTE PIPE-FLOW TRAVEL TIME THRU SUBAREA<<<<<
>>>>USING COMPUTER-ESTIMATED PIPESIZE (NON-PRESSURE FLOW)<<<<<
=====
ELEVATION DATA: UPSTREAM(FEET) = 34.50    DOWNSTREAM(FEET) = 20.00
FLOW LENGTH(FEET) = 205.50    MANNING'S N = 0.013
DEPTH OF FLOW IN 9.0 INCH PIPE IS 5.5 INCHES
PIPE-FLOW VELOCITY(FEET/SEC.) = 10.19
ESTIMATED PIPE DIAMETER(INCH) = 9.00    NUMBER OF PIPES = 1
PIPE-FLOW(CFS) = 2.89
PIPE TRAVEL TIME(MIN.) = 0.34    Tc(MIN.) = 13.95
LONGEST FLOWPATH FROM NODE 235.00 TO NODE 265.00 = 688.50 FEET.
*****
FLOW PROCESS FROM NODE 265.00 TO NODE 265.00 IS CODE = 1
-----

```

```

>>>>DESIGNATE INDEPENDENT STREAM FOR CONFLUENCE<<<<
=====
TOTAL NUMBER OF STREAMS = 2
CONFLUENCE VALUES USED FOR INDEPENDENT STREAM 1 ARE:
TIME OF CONCENTRATION(MIN.) = 13.95
RAINFALL INTENSITY(INCH/HR) = 3.02
TOTAL STREAM AREA(ACRES) = 3.40
PEAK FLOW RATE(CFS) AT CONFLUENCE = 2.89

*****
FLOW PROCESS FROM NODE 275.00 TO NODE 265.00 IS CODE = 7
-----
>>>>USER SPECIFIED HYDROLOGY INFORMATION AT NODE<<<<
=====
USER-SPECIFIED VALUES ARE AS FOLLOWS:
TC(MIN) = 6.44 RAIN INTENSITY(INCH/HOUR) = 4.13
TOTAL AREA(ACRES) = 0.26 TOTAL RUNOFF(CFS) = 0.48

*****
FLOW PROCESS FROM NODE 275.00 TO NODE 275.00 IS CODE = 1
-----
>>>>DESIGNATE INDEPENDENT STREAM FOR CONFLUENCE<<<<
>>>>AND COMPUTE VARIOUS CONFLUENCED STREAM VALUES<<<<
=====
TOTAL NUMBER OF STREAMS = 2
CONFLUENCE VALUES USED FOR INDEPENDENT STREAM 2 ARE:
TIME OF CONCENTRATION(MIN.) = 6.44
RAINFALL INTENSITY(INCH/HR) = 4.13
TOTAL STREAM AREA(ACRES) = 0.26
PEAK FLOW RATE(CFS) AT CONFLUENCE = 0.48

** CONFLUENCE DATA **
STREAM RUNOFF Tc INTENSITY AREA
NUMBER (CFS) (MIN.) (INCH/HOUR) (ACRE)
1 2.89 13.95 3.016 3.40
2 0.48 6.44 4.126 0.26

RAINFALL INTENSITY AND TIME OF CONCENTRATION RATIO
CONFLUENCE FORMULA USED FOR 2 STREAMS.

** PEAK FLOW RATE TABLE **
STREAM RUNOFF Tc INTENSITY
NUMBER (CFS) (MIN.) (INCH/HOUR)
1 1.81 6.44 4.126
2 3.24 13.95 3.016


COMPUTED CONFLUENCE ESTIMATES ARE AS FOLLOWS:
PEAK FLOW RATE(CFS) = 3.24 Tc(MIN.) = 13.95
TOTAL AREA(ACRES) = 3.7
LONGEST FLOWPATH FROM NODE 235.00 TO NODE 275.00 = 688.50 FEET.
=====
END OF STUDY SUMMARY:
TOTAL AREA(ACRES) = 3.7 TC(MIN.) = 13.95
PEAK FLOW RATE(CFS) = 3.24
=====
END OF RATIONAL METHOD ANALYSIS

```




**Appendix 3**  
**Detention Output**







DMA-1 to VAULT-1





VAULT-1 100-YR



DMA 2 to VAULT-2



VAULT-2 100-YR



**Routing Diagram for 3272**

Prepared by Pasco Laret Suiter & Assoc, Printed 4/3/2023  
HydroCAD® 10.20-2f s/n 10097 © 2022 HydroCAD Software Solutions LLC



### Summary for Link 1L: DMA-1 to VAULT-1


Inflow = 6.64 cfs @ 4.10 hrs, Volume= 0.327 af  
Primary = 6.64 cfs @ 4.10 hrs, Volume= 0.327 af, Atten= 0%, Lag= 0.0 min  
Routed to Pond 1P : VAULT-1 100-YR

Primary outflow = Inflow, Time Span= 0.00-96.00 hrs, dt= 0.01 hrs

DISCHARGE Imported from Vault-1 Rathydro.csv

### Link 1L: DMA-1 to VAULT-1

Hydrograph



**Summary for Pond 1P: VAULT-1 100-YR**

Inflow = 6.64 cfs @ 4.10 hrs, Volume= 0.327 af  
 Outflow = 1.21 cfs @ 4.26 hrs, Volume= 0.327 af, Atten= 82%, Lag= 9.7 min  
 Discarded = 0.00 cfs @ 0.11 hrs, Volume= 0.026 af  
 Primary = 1.20 cfs @ 4.26 hrs, Volume= 0.300 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-96.00 hrs, dt= 0.01 hrs  
 Peak Elev= 105.28' @ 4.26 hrs Surf.Area= 1,100 sf Storage= 6,767 cf

Plug-Flow detention time= 210.8 min calculated for 0.326 af (100% of inflow)  
 Center-of-Mass det. time= 211.2 min ( 423.9 - 212.7 )

Volume	Invert	Avail.Storage	Storage Description			
#1	97.83'	7,192 cf	<b>Custom Stage Data (Conic) Listed below (Recalc)</b>			
Elevation (feet)	Surf.Area (sq-ft)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	
97.83	1,100	0.0	0	0	1,100	
100.00	1,100	40.0	955	955	1,355	
101.00	1,100	100.0	1,100	2,055	1,473	
102.00	1,100	100.0	1,100	3,155	1,590	
103.00	1,100	100.0	1,100	4,255	1,708	
104.00	1,100	100.0	1,100	5,355	1,825	
105.37	1,100	100.0	1,507	6,862	1,986	
105.67	1,100	100.0	330	7,192	2,022	


Device	Routing	Invert	Outlet Devices
#1	Primary	100.00'	<b>24.00" Round Culvert</b> L= 10.0' RCP, groove end projecting, Ke= 0.200 Inlet / Outlet Invert= 100.00' / 99.90' S= 0.0100 '/' Cc= 0.900 n= 0.013, Flow Area= 3.14 sf
#2	Device 1	100.00'	<b>4.50" Vert. Orifice</b> C= 0.600 Limited to weir flow at low heads
#3	Device 1	105.37'	<b>Custom Weir, Cv= 2.62 (C= 3.28)</b> Head (feet) 0.00 0.30 0.30 Width (feet) 14.00 14.00 0.00
#4	Discarded	97.83'	<b>0.180 in/hr Exfiltration over Surface area below 100.00'</b>

**Discarded OutFlow** Max=0.00 cfs @ 0.11 hrs HW=97.92' (Free Discharge)  
 ↑**4=Exfiltration** (Exfiltration Controls 0.00 cfs)

**Primary OutFlow** Max=1.20 cfs @ 4.26 hrs HW=105.28' (Free Discharge)  
 ↑**1=Culvert** (Passes 1.20 cfs of 39.13 cfs potential flow)  
 ↑**2=Orifice** (Orifice Controls 1.20 cfs @ 10.87 fps)  
 ↑**3=Custom Weir** ( Controls 0.00 cfs)

### Pond 1P: VAULT-1 100-YR

Hydrograph



### Summary for Link 2L: DMA 2 to VAULT-2


Inflow = 13.18 cfs @ 4.10 hrs, Volume= 0.694 af  
Primary = 13.18 cfs @ 4.10 hrs, Volume= 0.694 af, Atten= 0%, Lag= 0.0 min  
Routed to Pond 2P : VAULT-2 100-YR

Primary outflow = Inflow, Time Span= 0.00-96.00 hrs, dt= 0.01 hrs

DISCHARGE Imported from Vault-2 RatHydro\_adj.csv

### Link 2L: DMA 2 to VAULT-2

Hydrograph



**Summary for Pond 2P: VAULT-2 100-YR**

Inflow = 13.18 cfs @ 4.10 hrs, Volume= 0.694 af  
 Outflow = 2.90 cfs @ 4.22 hrs, Volume= 0.694 af, Atten= 78%, Lag= 7.4 min  
 Discarded = 0.01 cfs @ 0.09 hrs, Volume= 0.050 af  
 Primary = 2.89 cfs @ 4.22 hrs, Volume= 0.644 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-96.00 hrs, dt= 0.01 hrs  
 Peak Elev= 105.18' @ 4.22 hrs Surf.Area= 2,300 sf Storage= 13,682 cf

Plug-Flow detention time= 176.7 min calculated for 0.694 af (100% of inflow)  
 Center-of-Mass det. time= 177.1 min ( 389.9 - 212.8 )

Volume	Invert	Avail.Storage	Storage Description			
#1	98.08'	14,807 cf	<b>Custom Stage Data (Conic) Listed below (Recalc)</b>			
Elevation (feet)	Surf.Area (sq-ft)	Voids (%)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	
98.08	2,300	0.0	0	0	2,300	
100.00	2,300	40.0	1,766	1,766	2,626	
101.00	2,300	100.0	2,300	4,066	2,796	
102.00	2,300	100.0	2,300	6,366	2,966	
103.00	2,300	100.0	2,300	8,666	3,136	
104.00	2,300	100.0	2,300	10,966	3,306	
105.17	2,300	100.0	2,691	13,657	3,505	
105.67	2,300	100.0	1,150	14,807	3,590	


Device	Routing	Invert	Outlet Devices	
#1	Primary	100.00'	<b>24.00" Round Culvert</b> L= 10.0' RCP, groove end projecting, Ke= 0.200 Inlet / Outlet Invert= 100.00' / 99.90' S= 0.0100 '/ Cc= 0.900 n= 0.013, Flow Area= 3.14 sf	
#2	Device 1	100.00'	<b>7.00" Vert. Orifice</b> C= 0.600 Limited to weir flow at low heads	
#3	Device 1	105.17'	<b>Custom Weir, Cv= 2.62 (C= 3.28)</b> Head (feet) 0.00 0.50 0.50 Width (feet) 13.00 13.00 0.00	
#4	Discarded	98.08'	<b>0.180 in/hr Exfiltration over Surface area below 100.00'</b>	

**Discarded OutFlow** Max=0.01 cfs @ 0.09 hrs HW=98.16' (Free Discharge)  
 ↑4=Exfiltration (Exfiltration Controls 0.01 cfs)

**Primary OutFlow** Max=2.89 cfs @ 4.22 hrs HW=105.18' (Free Discharge)  
 ↑1=Culvert (Passes 2.89 cfs of 38.66 cfs potential flow)  
 ↑2=Orifice (Orifice Controls 2.85 cfs @ 10.65 fps)  
 ↑3=Custom Weir (Weir Controls 0.05 cfs @ 0.34 fps)

### Pond 2P: VAULT-2 100-YR

Hydrograph





---





## **Appendix 4**

### **100-Year HEC-RAS Output**

---



**LEGEND:**

-  HEC-RAS CROSS-SECTION
-  PROPOSED GRADING
-  EFFECTIVE 100-YEAR FLOODPLAIN
-  EFFECTIVE FLOODWAY



HEC-RAS WORK MAP





HEC-RAS River: RIVER-1 Reach: Reach-1 Profile: 100-Year

Reach	River Sta	Profile	Plan	Q Total	Min Ch El	W.S. Elev	Crit W.S.	E.G. Elev	E.G. Slope	Vel Chnl	Flow Area	Top Width	Froude # Chl
				(cfs)	(ft)	(ft)	(ft)	(ft)	(ft/ft)	(ft/s)	(sq ft)	(ft)	
Reach-1	116	100-Year	Exist Cond	22000.00	17.09	31.22		31.42	0.002518	3.98	6680.49	2129.71	0.24
Reach-1	116	100-Year	Prop Cond	22000.00	17.09	31.23		31.42	0.002504	3.97	6694.10	2131.57	0.23
Reach-1	115	100-Year	Exist Cond	22000.00	15.70	30.45		30.61	0.001965	3.67	7841.84	2332.63	0.21
Reach-1	115	100-Year	Prop Cond	22000.00	15.70	30.46		30.62	0.001947	3.66	7854.36	2325.15	0.21
Reach-1	114	100-Year	Exist Cond	22000.00	14.40	30.14	25.55	30.20	0.000711	2.54	11167.88	2241.24	0.13
Reach-1	114	100-Year	Prop Cond	22000.00	14.40	30.14	25.55	30.21	0.000739	2.59	10988.04	2204.50	0.13
Reach-1	113.5	100-Year	Exist Cond	22000.00	14.00	30.00	24.95	30.06	0.000561	2.42	11597.53	1998.52	0.12
Reach-1	113.5	100-Year	Prop Cond	22000.00	14.00	30.00	24.94	30.06	0.000564	2.43	11549.72	1982.84	0.12
Reach-1	113.1	100-Year	Exist Cond	22000.00	13.80	29.92		29.96	0.000343	1.80	14867.52	2494.45	0.09
Reach-1	113.1	100-Year	Prop Cond	22000.00	13.80	29.92		29.96	0.000347	1.81	14750.65	2465.36	0.09
Reach-1	113	100-Year	Exist Cond	22000.00	13.00	29.87		29.90	0.000162	1.30	18645.40	2605.11	0.07
Reach-1	113	100-Year	Prop Cond	22000.00	13.00	29.87		29.90	0.000161	1.29	18603.13	2586.23	0.07
Reach-1	112	100-Year	Exist Cond	22000.00	18.00	28.91	26.04	29.76	0.008928	7.63	3107.82	465.08	0.47
Reach-1	112	100-Year	Prop Cond	22000.00	18.00	28.91	26.04	29.76	0.008928	7.63	3107.82	465.08	0.47



1) Prop Cond 2) Exist Cond  
RS = 116




1) Prop Cond 2) Exist Cond  
RS = 115



1) Prop Cond 2) Exist Cond  
RS = 114





1) Prop Cond 2) Exist Cond  
RS = 112

