



THE CITY OF SAN DIEGO

ADDENDUM TO MITIGATED NEGATIVE DECLARATION

WBS No. B-22015
Addendum to MND No. 255100
SCH No. 2011091045

SUBJECT: Via de la Valle Pipeline Replacement Project: The project proposes replacement of approximately 3,235 linear feet (LF) of existing water main, installation of approximately 2,730 LF of 16-inch water main; abandonment of approximately 406 LF of 24-inch water main; abandonment of approximately 3,840 LF of 4-inch water pipe currently servicing the San Diego Surf Sports Park; and installation of approximately 35 LF of new 4-inch water pipe. The project would replace associated water service connections, fire hydrants, valves, water meters, and curbs within the project alignment. The project is located within an approximately 1.1-mile span of Via de la Valle, a paved public street that bounds Via de la Valle Community Planning Area (CPA) and the North City Future Urbanizing Area CPA (Council District 1).

I. SUMMARY OF ORIGINAL PROJECT

A Citywide Pipelines Projects Mitigated Negative Declaration (MND) No. 255100 was prepared by the City of San Diego Development Services Department (DSD) and was adopted by the City Council on November 30, 2011 (Resolution No. 307122). The Citywide Pipelines Projects MND provides for the inclusion of subsequent pipeline projects that are located within the public right-of-way (ROW) and would not result in any direct impacts to sensitive biological resources. Pursuant to the City of San Diego Municipal Code Section 128.0306 and Section 15164(c) of State CEQA Guidelines addenda to environmental documents are not required to be circulated for public review.

II. SUMMARY OF PROPOSED PROJECT

The project would entail replacement of approximately 3,235 (LF) (0.61 miles) of existing 24-inch diameter cement mortar lined and coated steel (CMLCS) water mains with new 16-inch-diameter water mains; installation of approximately 2,730 LF (0.52 miles) of new 16-inch diameter water main; abandonment of approximately 406 LF of 24-inch diameter CMLCS & asphalt concrete (AC) water main; abandonment of approximately 3,840 LF of 4-inch diameter PVC water pipe currently servicing the San Diego Surf Sports Park located southeast of intersection of Via de la Valle and El Camino Real; and installation of approximately 35 LF of new 4-inch diameter PVC pipe to reconnect the abandoned PVC pipe to the new 16-inch diameter water main. The project would replace associated water-service connections, fire hydrants, valves, water meters, and curbs within the project

alignment. Most of the existing segment of water main associated with the project occurs in the disturbed eastbound shoulder of Via de la Valle; this would be abandoned, and the replacement water main would be located beneath the paved road surface.

Construction methods identified in the MND that will be implemented in this project include:

- **Open Trench:** The open trench method of construction will be used for manhole replacement, installation of manholes, and installation of new sewer cleanouts. Trenches are typically 5x5 feet wide and are dug with excavators and similar large construction equipment.
- **Abandonment:** Pipeline abandonment activities would be similar to rehabilitation methods in that no surface/subsurface disturbance would occur. This process may involve slurry or grout material injected into the abandoned lines via manhole access. The top portion of the manhole is then typically removed, and the remaining space is backfilled and paved over.
- **Potholing:** Potholing would be used to verify utility crossings. These “potholes” are made by using vacuum-type equipment to open up small holes in the street or pavement.

The contractor would comply with all applicable requirements described in the latest edition of the Standard Specifications for Public Works Construction (“GREENBOOK”) and the latest edition of the City of San Diego Standard Specifications for Public Works Construction (“WHITEBOOK”). A traffic control plan would be prepared and implemented in accordance with the California Manual on Uniform Traffic Control Devices (CA MUTCD). With respect to storm water, all projects would be reviewed for compliance with the most recent version of the City’s Storm Water Standards Manual and Municipal Separate Storm Sewer System (MS4) Permit.

III. ENVIRONMENTAL SETTING

The project is located within an approximately 1.1-mile span of Via de la Valle, a paved public street that forms part of the boundary between the Via de la Valle Community Planning Area (CPA) and the North City Future Urbanizing Area CPA (Council District 1). The western terminus of the project is a point approximately 215 feet east of the intersection of Via de la Valle and San Andres Drive, adjacent to the Del Mar Shopping Center and near the San Dieguito River Park ranger station. The eastern terminus of the project is approximately 300 feet east of the intersection of Via de la Valle and De la Valle Place, near a driveway to a small commercial development north of Via de la Valle. This eastern terminus is also near the future intersection of Via de la Valle and the planned realignment of El Camino Real. North of the project-related span of Via de la Valle is a mixture of commercial development, steep undeveloped hillsides, and a single-family residential development. South of the project-related span of Via de la Valle is a mixture of commercial development, the San Dieguito River Park, the Del Mar Horse Park, and the San Diego Surf Sports Park. The western portion of the alignment is adjacent to the City Multiple Habitat Preservation Area (MHPA) associated with the San Dieguito River Park. See Attachment A, Via de la Valle MHPA, and Attachment B, Via de la Valle Water Map.

IV. ENVIRONMENTAL DETERMINATION

The City previously prepared and certified the Citywide Pipelines MND No. 255100/SCH No. 2011091045. Based on all available information in light of the entire record, the analysis in this Addendum, and pursuant to Section 15162 of the State CEQA Guidelines, the City has determined the following:

- There are no substantial changes proposed in the project which will require major revisions of the previous environmental document due to the involvement of new significant environmental effects or a substantial increase in the severity of previously identified significant effects;
- Substantial changes have not occurred with respect to the circumstances under which the project is undertaken which will require major revisions of the previous environmental document due to the involvement of new significant environmental effects or a substantial increase in the severity of previously identified significant effects; or
- There is no new information of substantial importance, which was not known and could not have been known with the exercise of reasonable diligence at the time the previous environmental document was certified as complete or was adopted, shows any of the following:
 - a. The project will have one or more significant effects not discussed in the previous environmental document;
 - b. Significant effects previously examined will be substantially more severe than shown in the previous environmental document;
 - c. Mitigation measures or alternatives previously found not to be feasible would in fact be feasible, and would substantially reduce one or more significant effects of the project, but the project proponents decline to adopt the mitigation measure or alternative; or
 - d. Mitigation measures or alternatives which are considerably different from those analyzed in the previous environmental document would substantially reduce one or more significant effects on the environment, but the project proponents decline to adopt the mitigation measure or alternative.

Based upon a review of the current project, none of the situations described in Sections 15162 and 15164 of the State CEQA Guidelines apply. No changes in circumstances have occurred, and no new information of substantial importance has manifested, which would result in new significant or substantially increased adverse impacts as a result of the project. Therefore, this Addendum has been prepared in accordance with Section 15164 of the CEQA State Guidelines. Public review of this Addendum is not required per CEQA.

V. IMPACT ANALYSIS

The following includes the project-specific environmental review pursuant to CEQA. The analysis in this document evaluates the adequacy of the MND relative to the project. As indicated in Table 1, the MND identifies the project would have the potential for significant impacts and mitigation measures would ensure impacts would remain less than significant.

Table 1: Impact Assessment Summary

Environmental Issues	Citywide Pipelines MND Significance	Proposed Project Significance	Proposed Project Mitigation
Aesthetics	LTSM	LTS	No
Agriculture and Forestry Resources	NI	LTS	No
Air Quality	LTS	LTS	No
Biological Resources	LTSM	LTS	No
Cultural Resources	LTSM	LTSM	Yes
Geology/Soils	LTS	LTS	No
Greenhouse Gas Emissions	LTS	LTS	No
Hazards and Hazardous Materials	LTS	LTS	No
Hydrology/Water Quality	NI	NI	No
Land Use/Planning	LTSM	LTS	No
Mineral Resources	NI	NI	No
Noise	LTS	LTS	No
Population/Housing	NI	NI	No
Public Services	NI	NI	No
Recreation	NI	NI	No
Transportation/Traffic	LTS	LTS	No
Utilities/Service Systems	LTS	LTS	No
Mandatory Findings Significance	LTSM	LTSM	Yes

NI = No Impact; LTS = Less than Significant; LTSM = Less than Significant with Mitigation

Based on the following analysis and information, there is no evidence that the project would require a major change to the Mitigated Negative Declaration. The project would not result in any new significant impact, nor would a substantial increase in the severity of impacts from that described in the Mitigated Negative Declaration result.

Aesthetics

Citywide Pipelines Project MND

The Citywide Pipelines Project MND concluded that near-term or future projects may involve work that could affect street trees, historic buildings, or a state scenic highway. Street improvements, if located within a historic district, would be required to comply with mitigation measures to reduce impacts to scenic resources to below a level of significance.

Project

The project would not impact any historical structures and is not located within a historic district or within or adjacent to a state scenic highway. No impact to aesthetic resources would occur, and no mitigation is required.

Biological Resources/Land Use (MSCP)

Citywide Pipelines MND

The Citywide Pipelines MND concluded that projects occurring within 100 feet of the City's MHPA preserve area are required to implement relevant measures from the Multiple Species Conservation Program (MSCP). These measures include displaying the MHPA boundaries on design drawings and considering other requirements in the project design and specifications; implementing the project outside the breeding seasons for the covered bird species coastal California gnatcatcher, least Bell's vireo, and southwest willow flycatcher, or conducting pre-construction surveys for these species and incorporating avoidance and minimization measures if the species are detected; and requiring biological resources monitoring during construction. The MND concluded that implementing the MSCP requirements specified in the MND would reduce the project's potential land use impacts to a less-than-significant level.

Via de le Valle Project

The project is adjacent to and within 100 feet of the MHPA preserve area associated with the San Dieguito River Park, so the project would be required to implement the land use mitigation measures identified in the MND, as listed below in Section VI.

Cultural Resources

Citywide Pipelines Project MND

Historical – Built Environment

The Citywide Pipelines Project MND concluded that pipeline projects located within the public ROW and City easements could result in significant environmental impacts relating to historical resources, and mitigation to reduce impacts to historical resources to below a level of significance were included in the MND. Associated street improvements, if located within a historic district, would be required to comply with the mitigation measures incorporated in the MND.

Archaeological Resources

The Citywide Pipelines MND concluded that future pipeline projects located within the public right-of-way and city easements could result in significant environmental impacts relating to archaeological resources and included mitigation to reduce impacts to archaeological resources to below a level of significance. To reduce potential project impacts on archaeological resources to below a level of significance, excavation within previously undisturbed soil, for either new trench alignments or for replacement of pipelines within the same trench alignment occurring at a deeper depth than the previously existing pipeline, would be monitored by a qualified archaeologist or archaeological monitor and Native American monitor. Any significant archaeological resources encountered would be recovered and curated in accordance with the Mitigation, Monitoring, and Reporting Program (MMRP) detailed in Section VI.

Paleontological Resources

The Citywide Pipelines Project MND concluded that pipeline projects may include work underlain by sensitive fossil-bearing formations that could result in significant environmental impacts relating to paleontological resources. Excavation within previously undisturbed formations at a moderate or high sensitivity at a depth of 10 or more feet and in geologic formations that are known to be sensitive for the presence of fossils would be monitored by a qualified paleontologist or paleontological monitor. Mitigation was incorporated into the MND to reduce impacts to paleontological resources to below a level of significance.

Via de le Valle Project

Historical – Built Environment

The project would not impact any historical structures and is not located within a historic district or within or adjacent to a state scenic highway. No impact to historical resources (built environment) would occur.

Archaeological Resources

Dudek prepared a Cultural Resources Inventory Report for the project in September 2024. The report presented the results of a cultural resources records search, pedestrian survey, outreach to Native American tribal representatives, and assessment of potential impacts from constructing and operating the project. The report identified several previously recorded archaeological resources in the vicinity of the project, including resources that were recorded in 1929 and mapped beneath the existing roadway surface. This type of potential impact was anticipated in the MND. Because the project has the potential to encounter subsurface archaeological resources, the City will implement the historic resources mitigation measures identified in the MND to reduce potential impacts to less-than-significant levels, listed in detail below in Section V. All excavation within previously undisturbed soil would be monitored by a qualified archaeologist or archaeological monitor and Native American monitor. Any significant archaeological resources encountered would be recovered and curated in accordance with the detailed program established in the MMRP.

Paleontological Resources

The project alignment is underlain by the Pleistocene Bay Point Formation and occurs adjacent to the Eocene Torrey Sandstone Formation.¹ The Bay Point Formation is considered by the City to have high sensitivity for fossil presence, having “produced a large and diverse amount of well-preserved marine invertebrate and vertebrate fossils.” The Torrey Sandstone Formation is considered to have low paleontological sensitivity outside of Black Mountain Ranch and the Carmel Valley.² Because the project will entail excavation within a formation that is sensitive for its potential to feature paleontological resources, the City will implement the paleontological resources monitoring in accordance with San Diego Municipal Code Section 142.0151 and the City of San Diego Land Development Manual, General Grading Guidelines for Paleontological Resources. Monitoring would reduce potential impacts to less-than-significant levels, as listed in detail in Attachment C.

VI. MITIGATION, MONITORING, AND REPORTING PROGRAM (MMRP) INCORPORATED INTO THE PROJECT

Land Use (MSCP Conditions for Projects Within 100 Feet of the MHPA)

I. Prior to Permit Issuance

- A. Prior to issuance of any construction permit, the DSD Environmental Designee (ED) shall verify the Applicant has accurately represented the project's design in the Construction Documents (CDs) that are in conformance with the associated discretionary permit conditions and Exhibit "A", and also the City's Multi-Species Conservation Program (MSCP) Land Use Adjacency Guidelines for the Multiple Habitat Planning Area (MHPA), including identifying adjacency as the potential for direct/indirect impacts where applicable. In addition, all CDs where applicable shall show the following:
- 1. Land Development/Grading/ Boundaries** – MHPA boundaries on-site and adjacent properties shall be delineated on the CDs. The ED shall ensure that all grading is included within the development footprint, specifically manufactured slopes, disturbance, and development within or adjacent to the MHPA.
 - 2. Drainage/Toxins** – All new and proposed parking lots and developed areas in and adjacent to the MHPA shall be designed so they do not drain directly into the MHPA, all developed and paved areas must prevent the release of toxins, chemicals, petroleum products, exotic plant materials prior to release by incorporating the use of filtration devices, planted swales and/or planted detention/desiltation basins, or other approved permanent methods that are designed to minimize negative impacts, such as excessive water and toxins into the ecosystems of the MHPA.
 - 3. Staging/storage, equipment maintenance, and trash** – All areas for staging, storage of equipment and materials, trash, equipment maintenance, and other construction-related activities are within the development footprint. Provide a note on the plans that states: "All construction-related activity that may have the potential for leakage or intrusion shall be

¹ San Diego Natural History Museum. Paleontological Resource Assessment, Via de la Valle Erosion Control Maintenance, City of San Diego. September 2016.

² City of San Diego. Draft General Plan Final Programmatic Environmental Impact Report, Paleontological Resources Section. September 2007.

monitored by the Qualified Biologist/Owners Representative to ensure there is no impact to the MHPA. "

4. Barriers – All new development within or adjacent to the MHPA shall provide fencing or other City approved barriers along the MHPA boundaries to direct public access to appropriate locations, to reduce domestic animal predation, and to direct wildlife to appropriate corridor crossing. Permanent barriers may include but are not limited to, fencing (6-foot black vinyl coated chain link or equivalent), walls, rocks/boulders, vegetated buffers, and signage for access, litter, and educational purposes.

5. Lighting – All building, site, and landscape lighting adjacent to the MHPA shall be directed away from the preserve using proper placement and adequate shielding to protect sensitive habitat. Where necessary, light from traffic or other incompatible uses, shall be shielded from the MHPA through the utilization of including, but not limited to, earth berms, fences, and/or plant material.

6. Invasive Plants – Plant species within 100 feet of the MHPA shall comply with the Landscape Regulations (LDC142.0400 and per table 142-04F, Revegetation and Irrigation Requirements) and be non-invasive. Landscape plans shall include a note that states: "The ongoing maintenance requirements of the property owner shall prohibit the use of any plantings that are invasive, per City Regulations, Standards, guidelines, etc., within 100 feet of the MHPA."

7. Brush Management – All new development adjacent to the MHPA is set back from the MHPA to provide the required Brush Management Zone (BMZ) 1 area (LDC Sec. 142.0412) within the development area and outside of the MHPA. BMZ 2 may be located within the MHPA and the BMZ 2 management shall be the responsibility of a HOA or other private entity.

8. Noise- Due to the site's location adjacent to or within the MHPA, construction noise that exceeds the maximum levels allowed shall be avoided, during the breeding seasons for protected avian species such as: coastal California gnatcatcher (3/ 1-8/15); least Bell's vireo (3/15-9/15); and southwestern willow flycatcher (5/1-8/30). If construction is proposed during the breeding season for the species, U.S. Fish and Wildlife Service protocol surveys shall be required in order to determine species presence/absence. When applicable, adequate noise reduction measures shall be incorporated. Upon project submittal the ED shall determine which of the following project-specific avian protocol surveys shall be required.

Coastal California Gnatcatcher

No clearing, grubbing, grading, or other construction activities shall occur between March 1 and August 15, the breeding season of the coastal California gnatcatcher, until the following requirements have been met to the satisfaction of the City Manager:

- A. A qualified biologist (possessing a valid Endangered Species Act Section 10(a)(1)(A) recovery permit) shall survey those habitat areas adjacent to the MHPA that would be subject to construction noise levels exceeding 60 decibels (dB[A]) hourly average for the presence of the coastal California gnatcatcher. Surveys for the coastal California gnatcatcher shall be conducted pursuant to the protocol survey guidelines established by the U.S. Fish and Wildlife Service within the breeding season prior to the commencement of any construction. If gnatcatchers are present, then the following must be met:

- i) Between March 1 and August 15, no clearing, grubbing, or grading of occupied gnatcatcher habitat shall be permitted. Areas restricted from such activities shall be staked or fenced under the supervision of a qualified biologist; and
- ii) Between March 1 and August 15, no construction activities shall occur within any portion of the site where construction activities would result in noise levels exceeding 60 dB(A) hourly average at the edge of occupied gnatcatcher habitat. An analysis showing that noise generated by construction activities would not exceed 60 dB(A) hourly average at the edge of occupied habitat must be completed by a qualified acoustician (possessing a current noise engineer license or registration with monitoring noise level experience with listed animal species) and approved by the City Manager at least 2 weeks prior to the commencement of construction activities. Prior to the commencement of construction activities during the breeding season, areas restricted from such activities shall be staked or fenced under the supervision of a qualified biologist; or
- iii) At least 2 weeks prior to the commencement of construction activities, under the direction of a qualified acoustician, noise attenuation measures (e.g., berms, walls) shall be implemented to ensure that noise levels resulting from construction activities will not exceed 60 dB(A) hourly average at the edge of habitat occupied by the coastal California gnatcatcher. Concurrent with the commencement of construction activities and the construction of necessary noise attenuation facilities, noise monitoring* shall be conducted at the edge of the occupied habitat area to ensure that noise levels do not exceed 60 dB(A) hourly average. If the noise attenuation techniques implemented are determined to be inadequate by the qualified acoustician or biologist, then the associated construction activities shall cease until such time that adequate noise attenuation is achieved or until the end of the breeding season (August 16).

* Construction noise monitoring shall continue to be monitored at least twice weekly on varying days, or more frequently depending on the construction activity, to verify that noise levels at the edge of occupied habitat are maintained below 60 dB(A) hourly average or to the ambient noise level if it already exceeds 60 dB(A) hourly average. If not, other measures shall be implemented in consultation with the biologist and the City Manager, as necessary, to reduce noise levels to below 60 dB(A) hourly average or to the ambient noise level if it already exceeds 60 dB(A) hourly average. Such measures may include but are not limited to, limitations on the placement of construction equipment and the simultaneous use of equipment.

- B. If coastal California gnatcatchers are not detected during the protocol survey, the qualified biologist shall submit substantial evidence to the city manager and applicable resource agencies that demonstrates whether or not mitigation measures such as noise walls are necessary between March 1 and August 15 as follows:
 - i) If this evidence indicates the potential is high for coastal California gnatcatcher to be present based on historical records or site conditions, then condition A.iii shall be adhered to as specified above.
 - ii) If this evidence concludes that no impacts to this species are anticipated, no mitigation measures would be necessary.

Least Bell's Vireo

No clearing, grubbing, grading, or other construction activities shall occur between March 15 and September 15, the breeding season of the least Bell's vireo, until the following requirements have been met to the satisfaction of the city manager:

- A. A qualified biologist (possessing a valid Endangered Species Act Section 10(a)(1)(a) recovery permit) shall survey those wetland areas that would be subject to construction noise levels exceeding 60 dB(A) hourly average for the presence of the least Bell's vireo. Surveys for this species shall be conducted pursuant to the protocol survey guidelines established by the U.S. Fish and Wildlife Service within the breeding season prior to the commencement of construction. If the least Bell's vireo is present, then the following conditions must be met:
- i) Between March 15 and September 15, no clearing, grubbing, or grading of occupied least bell's vireo habitat shall be permitted. areas restricted from such activities shall be staked or fenced under the supervision of a qualified biologist; and
 - ii) Between March 15 and September 15, no construction activities shall occur within any portion of the site where construction activities would result in noise levels exceeding 60 dB(A) hourly average at the edge of occupied least Bell's vireo or habitat. An analysis showing that noise generated by construction activities would not exceed 60 dB(A) hourly average at the edge of occupied habitat must be completed by a qualified acoustician (possessing a current noise engineer license or registration with monitoring noise level experience with listed animal species) and approved by the City Manager at least 2 weeks prior to the commencement of construction activities. Prior to the commencement of any construction activities during the breeding season, areas restricted from such activities shall be staked or fenced under the supervision of a qualified biologist; or
 - iii) At least 2 weeks prior to the commencement of construction activities, under the direction of a qualified acoustician, noise attenuation measures (e.g., berms, walls) shall be implemented to ensure that noise levels resulting from construction activities will not exceed 60 dB(A) hourly average at the edge of habitat occupied by the least Bell's vireo. concurrent with the commencement of construction activities and the construction of necessary noise attenuation facilities, noise monitoring* shall be conducted at the edge of the occupied habitat area to ensure that noise levels do not exceed 60 dB(A) hourly average. If the noise attenuation techniques implemented are determined to be inadequate by the qualified acoustician or biologist, then the associated construction activities shall cease until such time that adequate noise attenuation is achieved or until the end of the breeding season (September 16).

* Construction noise monitoring shall continue at least twice weekly on varying days, or more frequently depending on the construction activity, to verify that noise levels at the edge of occupied habitat are maintained below 60 dB(A) hourly average or to the ambient noise level if it already exceeds 60 dB(A) hourly average. If not, other measures shall be implemented in consultation with the biologist and the City Manager, as necessary, to reduce noise levels to below 60 dB(A) hourly average or to the ambient noise level if it already exceeds 60 dB(A) hourly average. Such measures may include but are not limited to, limitations on the placement of construction equipment and the simultaneous use of equipment.

- B. If least Bell's vireo are not detected during the protocol survey, the qualified biologist shall submit substantial evidence to the City Manager and applicable resource agencies that demonstrates whether or not mitigation measures such as noise walls are necessary between March 15 and September 15 as follows:

- i) If this evidence indicates the potential is high for least Bell's vireo to be present based on historical records or site conditions, then condition A.iii shall be adhered to as specified above.
- ii) If this evidence concludes that no impacts to this species are anticipated, no mitigation measures would be necessary.

Southwestern Willow Flycatcher

Prior to the first preconstruction meeting, the City Manager (or appointed designee) shall verify that the following project requirements regarding the southwestern willow flycatcher are shown on the construction plans:

No clearing, grubbing, grading, or other construction activities shall occur between May 1 and September 1, the breeding season of the southwestern willow flycatcher, until the following requirements have been met to the satisfaction of the city manager:

- A. A qualified biologist (possessing a valid Endangered Species Act Section 10(a)(1)(a) recovery permit) shall survey those wetland areas that would be subject to construction noise levels exceeding 60 dB(A) hourly average for the presence of the southwestern willow flycatcher. surveys for this species shall be conducted pursuant to the protocol survey guidelines established by the U.S. Fish and Wildlife Service within the breeding season prior to the commencement of any construction. if the southwestern willow flycatcher is present, then the following conditions must be met:
 - i) Between May 1 and September 1, no clearing, grubbing, or grading of occupied southwestern willow flycatcher habitat shall be permitted. Areas restricted from such activities shall be staked or fenced under the supervision of a qualified biologist; and
 - ii) Between May 1 and September 1, no construction activities shall occur within any portion of the site where construction activities would result in noise levels exceeding 60 dB(A) hourly average at the edge of occupied southwestern willow flycatcher habitat. An analysis showing that noise generated by construction activities would not exceed 60 dB(A) hourly average at the edge of occupied habitat must be completed by a qualified acoustician (possessing a current noise engineer license or registration with monitoring noise level experience with listed animal species) and approved by the City Manager at least 2 weeks prior to the commencement of construction activities. Prior to the commencement of construction activities during the breeding season, areas restricted from such activities shall be staked or fenced under the supervision of a qualified biologist; or at least 2 weeks prior to the commencement of construction activities, under the direction of a qualified acoustician, noise attenuation measures (e.g., berms, walls) shall be implemented to ensure that noise levels resulting from construction activities will not exceed 60 dB(A) hourly average at the edge of habitat occupied by the southwestern willow flycatcher. Concurrent with the commencement of construction activities and the construction of necessary noise attenuation facilities, noise monitoring* shall be conducted at the edge of the occupied habit at area to ensure that noise levels do not exceed 60 dB(A) hourly average. If the noise attenuation techniques implemented are determined to be inadequate by the qualified acoustician or biologist, then the associated construction activities shall cease until such time that adequate noise attenuation is achieved or until the end of the breeding season (September 1).

* Construction noise monitoring shall continue to be monitored at least twice weekly on varying days, or more frequently depending on the construction activity, to verify that noise levels at the edge of occupied habitat are maintained below 60 dB(A) hourly average or to the ambient noise level if it already exceeds 60 dB(A) hourly average. If not, other measures shall be implemented in consultation with the biologist and the City Manager, as necessary, to reduce noise levels to below 60 dB(A) hourly average or to the ambient noise level if it already exceeds 60 dB(A) hourly average. Such measures may include but are not limited to, limitations on the placement of construction equipment and the simultaneous use of equipment.

- B. If southwestern willow flycatcher are not detected during the protocol survey, the qualified biologist shall submit substantial evidence to the city manager and applicable resource agencies which demonstrates whether or not mitigation measures such as noise walls are necessary between May 1 and September 1 as follows:
 - I. If this evidence indicates the potential is high for southwestern willow flycatcher to be present based on historical records or site conditions, then condition A.ii shall be adhered to as specified above.
 - II. If this evidence concludes that no impacts to this species are anticipated, no mitigation measures would be necessary.

II. Prior to Start of Construction

A. Preconstruction Meeting

The Qualified Biologist/Owner's Representative shall incorporate all MHPA construction-related requirements into the project's Biological Monitoring Exhibit (BME). The Qualified Biologist/Owner's Representative is responsible for arranging and performing a focused pre-con with all contractors, subcontractors, and all workers involved in grading or other construction activities to discuss the sensitive nature of the adjacent sensitive biological resources.

III. During Construction

- A. The Qualified Biologist/Owner's Representative, shall verify that all construction-related activities taking place adjacent to the MHPA are consistent with the CDs, the MSCP/MHPA Land Use Adjacency Guidelines. The Qualified Biologist/Owner's Representative shall monitor and ensure that:

1. Land Development /Grading Boundaries - The MHPA boundary and the limits of grading shall be clearly delineated by a survey crew prior to brushing, clearing, or grading. Limits shall be defined with an orange construction fence and a siltation fence (can be combined) under the supervision of the Qualified Biologist/Owners Representative who shall provide a letter of verification to RE/MMC that all limits were marked as required. Within or adjacent to the MHPA, all manufactured slopes associated with site development shall be included within the development footprint.

2. Drainage/Toxics - No Direct drainage into the MHPA shall occur during or after construction until filtration devices, swales and/or detention/desiltation basins that drain into the MHPA are functioning properly during construction, and that permanent maintenance after construction is addressed. These systems should be maintained approximately once a year, or as often a needed, to ensure proper functioning. Maintenance should include dredging out sediments if needed, removing exotic plant materials, and

adding chemical-neutralizing compounds (e.g. clay compounds) when necessary and appropriate.

3. Staging/storage, equipment maintenance, and trash - Identify all areas for staging, storage of equipment and materials, trash, equipment maintenance, and other construction-related activities on the monitoring exhibits and verify that they are within the development footprint. Comply with the applicable notes on the plans.

4. Barriers - New development adjacent to the MHPA provides city-approved barriers along the MHPA boundaries

5. Lighting - Periodic night inspections are performed to verify that all lighting adjacent to the MHPA is directed away from preserve areas and that appropriate placement and shielding is used.

6. Invasives - No invasive plant species are used adjacent (within 100 feet) to the MHPA.

7. Brush Management – BMZ 1 is within the development footprint and outside of the MHPA, and that maintenance responsibility for the BMZ 2 located within the MHPA is identified as the responsibility of an HOA or other private entity.

8. Noise - For any area of the site that is adjacent to the MHPA, construction noise that exceeds the maximum levels allowed, shall be avoided, during the breeding seasons, for protected avian species such as coastal California gnatcatcher (3/1-8/15); least Bell's vireo (3/15-9/15); and southwestern willow flycatcher (5/1-8/30). If construction is proposed during the breeding season for the species, U.S. Fish and Wildlife Service protocol surveys will be required in order to determine species presence/absence. When applicable, adequate noise reduction measures shall be incorporated.

IV. Post-Construction

A. Preparation and Submittal of Monitoring Report

The Qualified Biologist/Owners Representative shall submit a final biological monitoring report to the RE/MMC within 30 days of the completion of construction that requires monitoring. The report shall incorporate the results of the MMRP/MSCP requirements per the construction documents and the BME to the satisfaction of RE/MMC.

Cultural Resources (Archaeology)

I. Prior to Permit Issuance or Bid Opening/Bid Award

A. Entitlements Plan Check

1. Prior to permit issuance or Bid Opening/Bid Award, whichever is applicable, a qualified City staff member shall verify that the requirements for Archaeological Monitoring and Native American monitoring have been noted on the applicable construction documents through the plan check process.

B. Letters of Qualification have been submitted to ADD

1. Prior to Bid Award, the applicant shall submit a letter of verification to Mitigation Monitoring Coordination (MMC) identifying the Principal Investigator (PI) for the project and the names of all persons involved in the archaeological monitoring program, as defined in the City of San Diego Historical Resources Guidelines (HRG). If applicable, individuals involved in the archaeological monitoring program must have completed the 40-hour HAZWOPER training with certification documentation.

2. MMC will provide a letter to the applicant confirming the qualifications of the PI and that all persons involved in the archaeological monitoring of the project meet the qualifications established in the HRG.
3. Prior to the start of work, the applicant must obtain written approval from MMC for any personnel changes associated with the monitoring program.

II. Prior to Start of Construction

A. Verification of Records Search

1. The PI shall provide verification to MMC that a site-specific records search (1/4 mile radius) has been completed. Verification includes but is not limited to, a copy of a confirmation letter from South Coastal Information Center or, if the search was in-house, a letter of verification from the PI stating that the search was completed.
2. The letter shall introduce any pertinent information concerning expectations and probabilities of discovery during trenching and/or grading activities.
3. The PI may submit a detailed letter to MMC requesting a reduction to the ¼ mile radius.

B. PI Shall Attend Precon Meetings

1. Prior to beginning any work that requires monitoring; the Applicant shall arrange a Precon Meeting that shall include the PI, Native American consultant/monitor (where Native American resources may be impacted), Construction Manager (CM) and/or Grading Contractor, Resident Engineer (RE), Building Inspector (BI), if appropriate, and MMC. The qualified Archaeologist and Native American Monitor shall attend any grading/excavation-related Precon Meetings to make comments and/or suggestions concerning the Archaeological Monitoring program with the Construction Manager and/or Grading Contractor.
 - a. If the PI is unable to attend the Precon Meeting, the Applicant shall schedule a focused Precon Meeting with MMC, the PI, RE, CM or BI, if appropriate, prior to the start of any work that requires monitoring.
2. Acknowledgement of Responsibility for Curation (CIP or Other Public Projects)
The applicant shall submit a letter to MMC acknowledging their responsibility for the cost of curation associated with all phases of the archaeological monitoring program.
3. Identify Areas to be Monitored
 - a. Prior to the start of any work that requires monitoring, the PI shall submit an Archaeological Monitoring Exhibit (AME) (with verification that the AME has been reviewed and approved by the Native American consultant/monitor when Native American resources may be impacted) based on the appropriate construction documents (reduced to 11x17) to MMC identifying the areas to be monitored including the delineation of grading/excavation limits.
 - b. The AME shall be based on the results of a site-specific records search as well as information regarding the age of existing pipelines, laterals and associated appurtenances and/or any known soil conditions (native or formation).
 - c. MMC shall notify the PI that the AME has been approved.
4. When Monitoring Will Occur
 - a. Prior to the start of any work, the PI shall also submit a construction schedule to MMC through the RE indicating when and where monitoring will occur.
 - b. The PI may submit a detailed letter to MMC prior to the start of work or during construction requesting a modification to the monitoring program. This request

shall be based on relevant information such as a review of final construction documents that indicate conditions such as the age of the existing pipe to be replaced, depth of excavation and/or site graded to bedrock, etc., which may reduce or increase the potential for resources to be present.

5. Approval of AME and Construction Schedule
After approval of the AME by MMC, the PI shall submit to MMC written authorization of the AME and Construction Schedule from the CM.

III. During Construction

- A. Monitor Shall be Present During Grading/Excavation/Trenching
 1. The Archaeological Monitor shall be present full-time during all soil disturbing and grading/excavation/trenching activities, which could result in impacts to archaeological resources as identified on the AME. **The Construction Manager is responsible for notifying the RE, PI, and MMC of changes to any construction activities such as in the case of a potential safety concern within the area being monitored. In certain circumstances, OSHA safety requirements may necessitate modification of the AME.**
 2. The Native American consultant/monitor shall determine the extent of their presence during soil disturbing and grading/excavation/trenching activities based on the AME and provide that information to the PI and MMC. If prehistoric resources are encountered during the Native American consultant/monitor's absence, work shall stop, and the Discovery Notification Process detailed in Section III.B-C and IV.A-D shall commence.
 3. The PI may submit a detailed letter to MMC during construction requesting a modification to the monitoring program when a field condition such as modern disturbance post-dating the previous grading/trenching activities, presence of fossil formations, or when native soils are encountered that may reduce or increase the potential for resources to be present.
 4. The archaeological and Native American consultant/monitor shall document field activity via the Consultant Site Visit Record (CSVSR). The CSVSR's shall be faxed by the CM to the RE the first day of monitoring, the last day of monitoring, monthly (**Notification of Monitoring Completion**), and in the case of ANY discoveries. The RE shall forward copies to MMC.
- B. Discovery Notification Process
 1. In the event of a discovery, the Archaeological Monitor shall direct the contractor to temporarily divert all soil-disturbing activities, including but not limited to digging, trenching, excavating or grading activities in the area of discovery and in the area reasonably suspected to overlay adjacent resources and immediately notify the RE or BI, as appropriate.
 2. The Monitor shall immediately notify the PI (unless the Monitor is the PI) of the discovery.
 3. The PI shall immediately notify MMC by phone of the discovery, and shall also submit written documentation to MMC within 24 hours by fax or email with photos of the resource in context, if possible.
 4. No soil shall be exported off-site until a determination can be made regarding the significance of the resource specifically if Native American resources are encountered.

C. Determination of Significance

1. The PI and Native American consultant/monitor, where Native American resources are discovered shall evaluate the significance of the resource. If Human Remains are involved, follow protocol in Section IV below.

- a. The PI shall immediately notify MMC by phone to discuss significance determination and shall also submit a letter to MMC indicating whether additional mitigation is required.
- b. If the resource is significant, the PI shall submit an Archaeological Data Recovery Program (ADRP) and obtain written approval of the program from MMC, CM and RE. ADRP and any mitigation must be approved by MMC, RE and/or CM before ground-disturbing activities in the area of discovery will be allowed to resume.

Note: If a unique archaeological site is also an historical resource as defined in CEQA Section 15064.5, then the limits on the amount(s) that a project applicant may be required to pay to cover mitigation costs as indicated in CEQA Section 21083.2 shall not apply.

(1). Note: For pipeline trenching and other linear projects in the public Right-of-Way, the PI shall implement the Discovery Process for Pipeline Trenching projects identified below under "D."

- c. If the resource is not significant, the PI shall submit a letter to MMC indicating that artifacts will be collected, curated, and documented in the Final Monitoring Report. The letter shall also indicate that no further work is required.

(1). Note: For Pipeline Trenching and other linear projects in the public Right-of-Way, if the deposit is limited in size, both in length and depth; the information value is limited and is not associated with any other resource; and there are no unique features/artifacts associated with the deposit, the discovery should be considered not significant.

(2). Note, for Pipeline Trenching and other linear projects in the public Right-of-Way, if significance can not be determined, the Final Monitoring Report and Site Record (DPR Form 523A/B) shall identify the discovery as Potentially Significant.

D. Discovery Process for Significant Resources - Pipeline Trenching and other Linear Projects in the Public Right-of-Way

The following procedure constitutes adequate mitigation of a significant discovery encountered during pipeline trenching activities or for other linear project types within the Public Right-of-Way including but not limited to excavation for jacking pits, receiving pits, laterals, and manholes to reduce impacts to below a level of significance:

1. Procedures for documentation, curation and reporting

- a. One hundred percent of the artifacts within the trench alignment and width shall be documented in situ, including photographic records, plan view of the trench and profiles of side walls, recovered, photographed after cleaning and analyzed and curated. The remainder of the deposit within the limits of excavation (trench walls) shall be left intact.
- b. The PI shall prepare a Draft Monitoring Report and submit it to MMC via the RE as indicated in Section VI-A.
- c. The PI shall be responsible for recording (on the appropriate State of California Department of Park and Recreation forms-DPR 523 A/B) the resource(s) encountered during the Archaeological Monitoring Program in accordance with

the City's Historical Resources Guidelines. The DPR forms shall be submitted to the South Coastal Information Center for either a Primary Record or SDI Number and included in the Final Monitoring Report.

- d. The Final Monitoring Report shall include a recommendation for monitoring any future work in the vicinity of the resource.

IV. **Discovery of Human Remains**

If human remains are discovered, work shall halt in that area and no soil shall be exported off-site until a determination can be made regarding the provenance of the human remains; and the following procedures as set forth in CEQA Section 15064.5(e), the California Public Resources Code (Sec. 5097.98) and State Health and Safety Code (Sec. 7050.5) shall be undertaken:

- A. Notification
 1. Archaeological Monitor shall notify the RE or BI as appropriate, MMC, and the PI, if the Monitor is not qualified as a PI. MMC will notify the appropriate Senior Planner in the Environmental Analysis Section (EAS) of the Development Services Department to assist with the discovery notification process.
 2. The PI shall notify the Medical Examiner after consultation with the RE, either in person or via telephone.
- B. Isolate discovery site
 1. Work shall be directed away from the location of the discovery and any nearby area reasonably suspected to overlay adjacent human remains until a determination can be made by the Medical Examiner in consultation with the PI concerning the provenience of the remains.
 2. The Medical Examiner, in consultation with the PI, will determine the need for a field examination to determine the provenience.
 3. If a field examination is not warranted, the Medical Examiner will determine with input from the PI, if the remains are or are most likely to be of Native American origin.
- C. If Human Remains **ARE** determined to be Native American
 1. The Medical Examiner will notify the Native American Heritage Commission (NAHC) within 24 hours. By law, **ONLY** the Medical Examiner can make this call.
 2. NAHC will immediately identify the person or persons determined to be the Most Likely Descendent (MLD) and provide contact information.
 3. The MLD will contact the PI within 24 hours or sooner after the Medical Examiner has completed coordination, to begin the consultation process in accordance with CEQA Section 15064.5(e), the California Public Resources and Health & Safety Codes.
 4. The MLD will have 48 hours to make recommendations to the property owner or representative for the treatment or disposition with proper dignity of the human remains and associated grave goods.
 5. Disposition of Native American Human Remains will be determined between the MLD and the PI, and, if:
 - a. The NAHC is unable to identify the MLD, OR the MLD failed to make a recommendation within 48 hours after being notified by the Commission, OR;
 - b. The landowner or authorized representative rejects the recommendation of the MLD and mediation in accordance with PRC 5097.94 (k) by the NAHC fails to provide measures acceptable to the landowner, THEN

- c. To protect these sites, the landowner shall do one or more of the following:
 - (1) Record the site with the NAHC;
 - (2) Record an open space or conservation easement; or
 - (3) Record a document with the County.
 - d. Upon the discovery of multiple Native American human remains during a ground-disturbing land development activity, the landowner may agree that additional conferral with descendants is necessary to consider culturally appropriate treatment of multiple Native American human remains. Culturally appropriate treatment of such a discovery may be ascertained from a review of the site utilizing cultural and archaeological standards. Where the parties are unable to agree on the appropriate treatment measures the human remains and items associated and buried with Native American human remains shall be reinterred with appropriate dignity, pursuant to Section 5.c., above.
- D. If Human Remains are **NOT** Native American
- 1. The PI shall contact the Medical Examiner and notify them of the historic era context of the burial.
 - 2. The Medical Examiner will determine the appropriate course of action with the PI and City staff (PRC 5097.98).
 - 3. If the remains are of historic origin, they shall be appropriately removed and conveyed to the San Diego Museum of Man for analysis. The decision for the internment of the human remains shall be made in consultation with MMC, EAS, the applicant/landowner, any known descendant group, and the San Diego Museum of Man.

V. Night and/or Weekend Work

- A. If night and/or weekend work is included in the contract
- 1. When night and/or weekend work is included in the contract package, the extent and timing shall be presented and discussed at the Precon meeting.
 - 2. The following procedures shall be followed.
 - a. No Discoveries
In the event that no discoveries were encountered during night and/or weekend work, the PI shall record the information on the CSVR and submit to MMC via fax by 8AM of the next business day.
 - b. Discoveries
All discoveries shall be processed and documented using the existing procedures detailed in Sections III - During Construction, and IV - Discovery of Human Remains. Discovery of human remains shall always be treated as a significant discovery.
 - c. Potentially Significant Discoveries
If the PI determines that a potentially significant discovery has been made, the procedures detailed under Section III - During Construction and IV-Discovery of Human Remains shall be followed.
 - d. The PI shall immediately contact the RE and MMC, or by 8 a.m. of the next business day to report and discuss the findings as indicated in Section III-B, unless other specific arrangements have been made.
- B. If night and/or weekend work becomes necessary during the course of construction

1. The Construction Manager shall notify the RE or BI, as appropriate, a minimum of 24 hours before the work is to begin.
2. The RE or BI, as appropriate, shall notify MMC immediately.
- C. All other procedures described above shall apply, as appropriate.

VI. Post Construction

A. Submittal of Draft Monitoring Report

1. The PI shall submit two copies of the Draft Monitoring Report (even if negative), prepared in accordance with the Historical Resources Guidelines (Appendix C/D) which describes the results, analysis, and conclusions of all phases of the Archaeological Monitoring Program (with appropriate graphics) to MMC via the RE for review and approval within 90 days following the completion of monitoring. **It should be noted that if the PI is unable to submit the Draft Monitoring Report within the allotted 90-day timeframe as a result of delays with analysis, special study results or other complex issues, a schedule shall be submitted to MMC establishing agreed due dates and the provision for submittal of monthly status reports until this measure can be met.**
 - a. For significant archaeological resources encountered during monitoring, the Archaeological Data Recovery Program or Pipeline Trenching Discovery Process shall be included in the Draft Monitoring Report.
 - b. Recording Sites with State of California Department of Parks and Recreation
The PI shall be responsible for recording (on the appropriate State of California Department of Park and Recreation forms-DPR 523 A/B) any significant or potentially significant resources encountered during the Archaeological Monitoring Program in accordance with the City's Historical Resources Guidelines, and submittal of such forms to the South Coastal Information Center with the Final Monitoring Report.
2. MMC shall return the Draft Monitoring Report to the PI via the RE for revision or, for preparation of the Final Report.
3. The PI shall submit a revised Draft Monitoring Report to MMC via the RE for approval.
4. MMC shall provide written verification to the PI of the approved report.
5. MMC shall notify the RE or BI, as appropriate, of receipt of all Draft Monitoring Report submittals and approvals.

B. Handling of Artifacts

1. The PI shall be responsible for ensuring that all cultural remains collected are cleaned and cataloged
2. The PI shall be responsible for ensuring that all artifacts are analyzed to identify function and chronology as they relate to the history of the area, that faunal material is identified as to species, and that specialty studies are completed, as appropriate.

C. Curation of Artifacts: Accession Agreement and Acceptance Verification

1. The PI shall be responsible for ensuring that all artifacts associated with the survey, testing and/or data recovery for this project are permanently curated with an appropriate institution. This shall be completed in consultation with MMC and the Native American representative, as applicable.
2. When applicable to the situation, the PI shall include written verification from the Native American consultant/monitor indicating that Native American resources were

treated in accordance with state law and/or applicable agreements. If the resources were reinterred, verification shall be provided to show what protective measures were taken to ensure no further disturbance occurs in accordance with Section IV – Discovery of Human Remains, Subsection C.

3. The PI shall submit the Accession Agreement and catalog record(s) to the RE or BI, as appropriate for donor signature, with a copy submitted to MMC.
 4. The RE or BI, as appropriate, shall obtain a signature on the Accession Agreement and shall return to PI with a copy submitted to MMC.
 5. The PI shall include the Acceptance Verification from the curation institution in the Final Monitoring Report submitted to the RE or BI and MMC.
- D. Final Monitoring Report(s)
1. The PI shall submit one copy of the approved Final Monitoring Report to the RE or BI, as appropriate, and one copy to MMC (even if negative), within 90 days after notification from MMC of the approved report.
 2. The RE shall, in no case, issue the Notice of Completion until receiving a copy of the approved Final Monitoring Report from MMC which includes the Acceptance Verification from the curation institution.

The above Mitigation Monitoring and Reporting Program may require additional fees and/or deposits to be collected prior to the issuance of building permits, certificates of occupancy and/or final maps to ensure the successful completion of the monitoring program.

VII. IMPACT SIGNIFICANCE

The MND identified that all impacts would be mitigated to below a level of significance through mitigation. This Addendum also identifies that all significant project impacts would be mitigated to below a level of significance, consistent with the previously certified MND.

VIII. CERTIFICATION

Copies of the addendum, the adopted MND, the MMRP, and associated project-specific technical appendices, if any, may be accessed on the City's CEQA webpage at <https://www.sandiego.gov/ceqa/final>.



Jamie Kennedy, Senior Planner
Engineering and Capital Projects Department


October 30, 2024
Date of Final Report

Analyst: JMKennedy

Attachments:



- A. Via de la Valle MHPA
- B. Via de la Valle Pre Design Water Map
- C. General Grading Guidelines for Paleontological Resources
- D. Mitigated Negative Declaration No. 255100/SCH No. 2011091045

Attachment A




SOURCE: SANGIS 2023






DETAIL 'A'



DETAIL 'B'



DETAIL 'C'

PRELIMINARY ENGINEERING SECTION
PROJECT MANAGER: NADER NACHAVIAN
DATE: _____

PROJECT ENGINEER: VIRGINIA OSKOU
DESIGN SECTION
PROJECT MANAGER: ALEJANDRA GONZALEZ
DATE: _____

PUD PROGRAM MANAGEMENT SECTION
PROJECT MANAGER: JEROME POTENCIANO
DATE: _____

LEGEND

- REPLACE 24" WATER MAIN WITH 16" WATER MAIN
- NEW 16" WATER MAIN
- NEW 12" WATER MAIN
- RECONNECT THE EXISTING WATER SERVICE TO THE NEW 16" WATER MAIN
- FUTURE NEW 16" WATER MAIN
- WATER MAIN TO BE ABANDONED
- EXISTING WATER MAIN
- EXISTING WATER VALVE
- EXISTING WATER PUMP
- ▼ EXISTING REDUCER
- ▲ EXISTING PRESSURE REDUCING STATION
- ⊗ EXISTING CLOSED GATE VALVE
- - - PRESSURE ZONE BOUNDARY
- FS EXISTING FIRE SERVICE
- EXISTING FIRE HYDRANT
- - - EXISTING STORM DRAIN

SCALE: 1" = 150'

VIA DE LA VALLE PIPELINE PREDESIGN WATER MAP

Attachment C

The following is the standard monitoring requirement that shall be placed on grading plans and implemented when required pursuant to LDC section 142.0151:

I. Prior to Permit Issuance

Entitlements Plan Check

Prior to issuance of any construction permits, including but not limited to, the first Grading Permit, Demolition Plans/Permits and Building Plans/Permits or a Notice to Proceed for Subdivisions, but prior to the first preconstruction meeting, whichever is applicable, the City Engineer (CE) and/or Building Inspector (BI) shall verify that the requirements for Paleontological Monitoring have been noted on the appropriate construction documents.

1. The applicant shall submit a letter of verification to Resident Engineer (RE) and/or Building Inspector (BI) identifying the qualified Principal Investigator (PI) for the project and the names of all persons involved in the paleontological monitoring program. A qualified PI is defined as a person with a Ph.D. or M.S. or equivalent in paleontology or closely related field (e.g., sedimentary or stratigraphic geology, evolutionary biology, etc.) with demonstrated knowledge of southern California paleontology and geology, and documented experience in professional paleontological procedures and techniques.

2. II. Prior to Start of Construction

A. Verification of Records Search

1. The PI shall provide verification to RE and/or BI that a site specific records search has been completed. Verification includes, but is not limited to a copy of a confirmation letter from the San Diego Natural History Museum, or another relevant institution that maintains paleontological collections recovered from sites within the City of San Diego.
2. The letter shall introduce any pertinent information concerning expectations and probabilities of discovery during trenching and/or grading activities.

B. PI Shall Attend Preconstruction Meetings

1. Prior to beginning any work that requires monitoring, the Applicant shall arrange a Preconstruction Meeting that shall include the PI, Construction Manager (CM) and/or Grading Contractor, RE, and BI, as appropriate. The qualified paleontologist (PI) shall attend any grading/excavation related Preconstruction Meetings to make comments and/or suggestions concerning the Paleontological Monitoring program with the Construction Manager and/or Grading Contractor.

- a. If the PI is unable to attend the Preconstruction Meeting, the Applicant shall schedule a focused Preconstruction Meeting with the PI, RE, CM or BI, if appropriate, prior to the start of any work that requires monitoring.
2. Identify Areas to be Monitored

Prior to the start of any work that requires monitoring, the PI shall submit a Paleontological Monitoring Exhibit (PME) based on the appropriate construction documents (reduced to 11x17) to RE and/or BI identifying the areas to be monitored including the delineation of grading/excavation limits. The PME shall be based on the results of a site specific records search as well as information regarding existing known geologic conditions (e.g., geologic deposits as listed in the Paleontological Monitoring Determination Matrix below).
3. When Monitoring Will Occur
 - a. Prior to the start of any work, the PI shall also submit a construction schedule to the RE and/or BI indicating when and where monitoring will occur.
 - b. The PI may submit a detailed letter to RE and/or BI prior to the start of work or during construction requesting a modification to the monitoring program. This request shall be based on relevant information such as review of final construction documents and geotechnical reports which indicate conditions such as depth of excavation and/or thickness of artificial fill overlying bedrock, presence or absence of fossils , etc., which may reduce or increase the potential for resources to be present.

III. During Construction

- A. Monitor Shall be Present During Grading/Excavation/Trenching
 1. The paleontological monitor shall be present full-time during grading/excavation/trenching activities as identified on the PME that could result in impacts to formations with high and moderate resource sensitivity. **The Construction Manager is responsible for notifying the PI, RE and/or BI of changes to any construction activities such as in the case of a potential safety concern within the area being monitored. In certain circumstances OSHA safety requirements may necessitate modification of the PME.**
 2. The PI may submit a detailed letter to RE and/or BI during construction requesting a modification to the monitoring program when a field condition such as trenching activities that do not encounter previously undisturbed and paleontologically sensitive geologic deposits as previously assumed, and/or when unique/unusual fossils are encountered, which may reduce or increase the potential for paleontological resources to be present.

3. The paleontological monitor shall document field activity via the Consultant Site Visit Record (CSV). The CSV's shall be emailed by the CM to the RE and/or BI the first day of monitoring, the last day of monitoring, monthly (**Notification of Monitoring Completion**), and in the case of ANY discoveries.

B. Discovery Notification Process

1. In the event of a discovery, the paleontological monitor shall direct the contractor to temporarily divert trenching activities in the area of discovery and notify the RE and/or BI. The contractor shall also process a construction change for administrative purposes to formalize the documentation and recovery program, including modification to Mitigation Monitoring and Compliance (MMC).
2. The paleontological monitor shall notify the PI (unless paleontological monitor is the PI) of the discovery.
3. The PI shall notify MMC of the discovery, and shall submit documentation to MMC within 24 hours by email with photos of the resource in context.

C. Recovery of Fossils

If a paleontological resource is encountered:

1. The paleontological monitor shall salvage unearthed fossil remains, including simple excavation of exposed specimens or, if necessary as determined by the PI, plaster-jacketing of large and/or fragile specimens or more elaborate quarry excavations of richly fossiliferous deposits.
2. The paleontological monitor shall record stratigraphic and geologic data to provide a context for the recovered fossil remains, including a detailed description of all paleontological localities within the project site, as well as the lithology of fossil-bearing strata within the measured stratigraphic section, and photographic documentation of the geologic setting.

V. Post Construction

A. Preparation and Submittal of Draft Paleontological Monitoring Report

1. The PI shall submit two copies of the Draft Paleontological Monitoring Report (even if negative), prepared to the satisfaction of the Development Services Department. The Draft Paleontological Monitoring Report shall describe the methods, results, and conclusions of all phases of the Paleontological Monitoring Program (with appropriate graphics) to MMC for review and approval within 90 days following the completion of monitoring,

- a. For significant or potentially significant paleontological resources encountered during monitoring, as identified by the PI, the Paleontological Recovery Program shall be included in the Draft Monitoring Report.
 - b. The PI shall be responsible for recording (on the appropriate forms) any significant or potentially significant fossil resources encountered during the Paleontological Monitoring Program in accordance with the City's Paleontological Guidelines (revised November 2017), and submittal of such forms to the San Diego Natural History Museum and MMC with the Draft Paleontological Monitoring Report.
2. MMC shall return the Draft Paleontological Monitoring Report to the PI for revision or, for preparation of the Final Report.
 3. The PI shall submit revised Draft Paleontological Monitoring Report to MMC for approval.
 4. MMC shall provide written verification to the PI of the approved Draft Paleontological Monitoring Report.
 5. MMC shall notify the RE and/or BI, of receipt of all Draft Paleontological Monitoring Report submittals and approvals.
- B. Handling of Recovered Fossils
1. The PI shall ensure that all fossils collected are cleaned to the point of curation (e.g., removal of extraneous sediment, repair of broken specimens, and consolidation of fragile/brittle specimens) and catalogued as part of the Paleontological Monitoring Program.
 2. The PI shall ensure that all fossils are analyzed to identify stratigraphic provenance, geochronology, and taphonomic context of the source geologic deposit; that faunal material is taxonomically identified; and that curation has been completed, as appropriate.
- C. Curation of Fossil Remains: Deed of Gift and Acceptance Verification
1. The PI shall be responsible for ensuring that all fossils associated with the paleontological monitoring program for this project are permanently curated with an accredited institution that maintains paleontological collections (such as the San Diego Natural History Museum).
 2. The PI shall include an acceptance verification from the curation institution in the Final Paleontological Monitoring Report submitted to the RE and/or BI, and MMC.

D. Final Paleontological Monitoring Report(s)

1. The PI shall submit two copies of the Final Paleontological Monitoring Report to MMC (even if negative), within 90 days after notification from MMC that the Final Paleontological Monitoring Report has been approved.
2. The RE and/or BI shall, in no case, issue the Notice of Completion until receiving a copy of the approved Final Paleontological Monitoring Report from MMC, which includes the Acceptance Verification from the curation institution.

Paleontological Monitoring Determination Matrix

Geological Deposit/Formation/Rock Unit	Potential Fossil Localities	Sensitivity Rating
Alluvium (Qsw, Qal, or Qls)	All communities where this unit occurs	Low
Ardath Shale (Ta)	All communities where this unit occurs	High
Bay Point/Marine Terrace (Qbp) ¹	All communities where unit occurs	High
Cabrillo Formation (Kcs)	All communities where unit occurs	Moderate
Delmar Formation (Td)	All communities where unit occurs	High
Friars Formation (Tf)	All communities where unit occurs	High
Granite/Plutonic (Kg)	All communities where unit occurs	Zero
Lindavista Formation (Qln, Qlb) ²	A. Mira Mesa/Tierrasanta B. All other areas	A. High B. Moderate
Lusardi Formation (Kl)	Black Mountain Ranch/Lusardi Canyon Poway/Rancho Santa Fe B. All other areas	A. High B. Moderate
Mission Valley Formation (Tmv)	All communities where unit occurs	High
Mt. Soledad Formation (Tm, Tmss, Tmsc)	A. Rose Canyon B. All other areas where this unit occurs	A. High B. Moderate
Otay Formation (To)	All communities where unit occurs	High
Point Loma Formation (Kp)	All communities where unit occurs	High
Pomerado Conglomerate (Tp)	A. Scripps Ranch/Tierrasanta B. All other areas	High
River /Stream Terrace Deposits (Qt)	A. South Eastern/Chollas Valley/Fairbanks Ranch/Skyline/Paradise Hills/Otay Mesa, Nestor/San Ysidro B. All other areas	A. Moderate B. Low
San Diego Formation (Qsd)	All communities where this unit occurs.	High
Santiago Peak Volcanics (Jsp) A. Metasedimentary B. Metavolcanic	A. Black Mountain Ranch/La Jolla Valley, Fairbanks Ranch/Mira Mesa/Peñasquitos B. All other areas	A. Moderate B. Zero
Scripps Formation (Tsd)	All communities where this unit occurs	High
Stadium Conglomerate (Tst)	All communities where this unit occurs	High
Sweetwater Formation	All communities where this unit occurs	High
Torrey Sandstone (Tf)	A. Black Mountain Ranch/Carmel Valley B. All other areas	A. High B. Low