



PDP SWQMP

PRIORITY DEVELOPMENT PROJECT (PDP) STORM WATER QUALITY MANAGEMENT PLAN (SWQMP)

Project Name Nakano

Assessor's Parcel Number(s) 624-071-02

Permit Application Number City of Chula Vista TM#PCS21-000 City of San Diego
PTS#647766

Drawing Numbers _____

CIVIL ENGINEER NAME: Chelisa Pack ; PE # 71026



Chelisa A. Pack

Wet Signature and Stamp

PREPARED FOR: Applicant Name: TriPointe Homes
Address: 13400 Sabre Springs Parkway, Suite 200
San Diego, CA 92128
Telephone # 858.794.2500

PREPARED BY: Company Name: Project Design Consultants
Address: 701 B Street, Suite 800
San Diego, CA, 92101
Telephone # 619-235-6471

DATE: January 9, 2023

Approved By: City of Chula Vista
(print Name & Sign)

Date: _____

P:\4409\Engr\Reports-4409.02-Nakano\Entitlement\SWQMP
Job# 4409.02

PDP SWQMP Template Date: March 2019

Page intentionally left blank for double-sided printing

TABLE OF CONTENTS

The checklist on this page summarized the table and attachments to be included with this PDP SWQMP Submittal. Tables & attachments with boxes already checked (✓) are required for all Projects

- Acronym Sheet**
- Certification Page**
- Submittal Record**
- Project Vicinity Map**
- Attach a copy of the Intake Form: Storm Water Requirements Applicability Checklist**
- HMP Exemption Exhibit (if Applicable)**
- FORM I-3B Site Information Checklist for PDPs**
- FORM I-4: Source Control BMP Checklist for All Development Projects**
- FORM I-5: Site Design BMP Checklist for All Development Projects**
- FORM I-6: Summary of PDP Structural BMPs**
- ATTACHEMNT 1: Backup for PDP Pollutant Control BMPs**
 - Attachment 1A: DMA Exhibit
 - Attachment 1B: Tabular Summary of DMAs and Design Capture Volume Calculations
 - Attachment 1C: FORM I-7 Harvest and Use Feasibility Screening (when applicable)
 - Attachment 1D: Infiltration Information Attachment 1E: Pollutant Control BMP Design Worksheets / Calculations for each DMA and Structural BMP Worksheets from Appendix B, as applicable
- ATTACHMENT 2: Backup for PDP Hydromodification Control Measures**
 - Attachment 2A: Hydromodification Management Exhibit
 - Attachment 2B: Management of Critical Coarse Sediment Yield Areas
 - Attachment 2C: Geomorphic Assessment of Receiving Channels
 - Attachment 2D: Flow Control Facility Design; Overflow Design Summary for each structural BMP
- ATTACHMENT 3: Structural BMP Maintenance Plan**
- ATTACHMENT 4: Copy of Plan Sheets Showing Permanent Storm Water BMPs**
- ATTACHMENT 5: Project's Drainage Report**
- ATTACHMENT 6: Project's Geotechnical and Groundwater Investigation Report**

ACRONYMS

APN	Assessor's Parcel Number
BMP	Best Management Practice
HMP	Hydromodification Management Plan
HSG	Hydrologic Soil Group
MS4	Municipal Separate Storm Sewer System
N/A	Not Applicable
NRCS	Natural Resources Conservation Service
PDP	Priority Development Project
PE	Professional Engineer
SC	Source Control
SD	Site Design
SDRWQCB	San Diego Regional Water Quality Control Board
SIC	Standard Industrial Classification
SWQMP	Storm Water Quality Management Plan

Nakano

Project Name/ _____

Certification Page

Project Name: Nakano

Permit Application Number: _____

I hereby declare that I am the Engineer in Responsible Charge of design of storm water best management practices (BMPs) for this project, and that I have exercised responsible charge over the design of the BMPs as defined in Section 6703 of the Business and Professions Code, and that the design is consistent with the PDP requirements of the City of Chula Vista BMP Design Manual, which is based on the requirements of the San Diego Regional Water Quality Control Board Order No. R9-2013-0001 as amended by R9-2015-0001 and R9-2015-0100 (MS4 Permit).

I have read and understand that the City Engineer has adopted minimum requirements for managing urban runoff, including storm water, from land development activities, as described in the BMP Design Manual. I certify that this PDP SWQMP has been completed to the best of my ability and accurately reflects the project being proposed and the applicable BMPs proposed to minimize the potentially negative impacts of this project's land development activities on water quality. I understand and acknowledge that the plan check review of this PDP SWQMP by the City Engineer is confined to a review and does not relieve me, as the Engineer in Responsible Charge of design of storm water BMPs for this project, of my responsibilities for project design.

Chelisa A. Pack

1/9/2023

Engineer of Work's Signature

Date

71026

6/30/23

PE #


Expiration Date

Chelisa Pack

Print Name

Project Design Consultants

Company




Project Name/ _____

SUBMITTAL RECORD

Use this Table to keep a record of submittals of this PDP SWQMP. Each time the PDP SWQMP is re-submitted, provide the date and status of the project. In column 4 summarize the changes that have been made or indicate if response to plancheck comments is included. When applicable, insert response to plancheck comments behind this page.

Submittal Number	Date	Project Status	Summary of Changes
1		<input checked="" type="checkbox"/> Preliminary Design / Planning/ CEQA <input type="checkbox"/> Final Design	Initial Submittal
2		<input checked="" type="checkbox"/> Preliminary Design / Planning/ CEQA <input type="checkbox"/> Final Design	2nd Submittal- Revised Site Plan to add secondary access & avoid Caltrans drainage easement
3		<input checked="" type="checkbox"/> Preliminary Design / Planning/ CEQA <input type="checkbox"/> Final Design	
4		<input checked="" type="checkbox"/> Preliminary Design / Planning/ CEQA <input type="checkbox"/> Final Design	
5	1/9/23	Preliminary Design	5th Submittal - Updated to include additional City of SD-formatted version of infiltration feasibility letter in Att 1D

Project Vicinity Map





Storm Water Requirements Applicability Checklist for All Permit Applications

Intake Form

March 2019 Update

Project Information

Project Address: North of the intersection of Denney Rd & Regatta Lane, Chula Vista, CA 92154	Project Application #
Project Name: Nakano	APN(s) 624-071-01
Brief Description of Work Proposed: Construction of 157 residential units, two biofiltration basins and a park lookout to Otay River.	

The project is (select one):

- New Development Total Impervious Area 566445 ft²
- Redevelopment Total new and/or replaced Impervious Area _____ ft²
(Redevelopment is the creation and/or replacement of impervious surface on an already developed site).
- Others _____

Name of Person Completing this Form: Chelisa Pack (Agent on behalf of Pardee Homes)

Role: Property Owner Contractor Architect Engineer Other _____

Email: chelisap@projectdesign.com Phone: (619) 881-2575

Signature: Date Completed: 9/9/2020

Answer each section below, starting with Section 1 and progressing through each section. Additional information for determining the requirements is found in the Chula Vista BMP Design Manual available on the City's website at <http://www.chulavistaca.gov/departments/public-works/services/storm-water-pollution-prevention/documents-and-reports>.

SECTION 1: Storm Water BMP Requirements

<p>Does the project consist of one or both of the following:</p> <ul style="list-style-type: none"> • Repair or improvements to an existing building or structure that don't alter the size such as: tenant improvements, interior remodeling, electrical work, fire alarm, fire sprinkler system, HVAC work, Gas, plumbing, etc. • Routine maintenance activities such as: roof or exterior structure surface replacement; resurfacing existing roadways and parking lots including dig outs, slurry seal, overlay and restriping; repair damaged sidewalks or pedestrian ramps on existing roads without expanding the impervious footprint; routine replacement of damaged pavement, trenching and resurfacing associated with utility work (i.e. sewer, water, gas or electrical laterals, etc.) and pot holing or geotechnical investigation borings. 	<input type="checkbox"/> Yes	<p>Project is NOT Subject to Permanent Storm Water BMP requirements.</p> <p>BUT IS subject to Construction BMP requirements. Review & sign "Construction Storm Water BMP Certification Statement" on page 2.</p>
	<input checked="" type="checkbox"/> No	<p>Continue to Section 2, page 3.</p>

Construction Storm Water BMP Certification Statement

The following stormwater quality protection measures are required by City Chula Vista Municipal Code Chapter 14.20 and the City's Jurisdictional Runoff Management Program.

1. All applicable construction BMPs and non-stormwater discharge BMPs shall be installed and maintained for the duration of the project in accordance with the Appendix K "Construction BMP Standards" of the Chula Vista BMP Design Manual.
2. Erosion control BMPs shall be implemented for all portions of the project area in which no work has been done or is planned to be done over a period of 14 or more days. All onsite drainage pathways that convey concentrated flows shall be stabilized to prevent erosion.
3. Run-on from areas outside the project area shall be diverted around work areas to the extent feasible. Run-on that cannot be diverted shall be managed using appropriate erosion and sediment control BMPs.
4. Sediment control BMPs shall be implemented, including providing fiber rolls, gravel bags, or other equally effective BMPs around the perimeter of the project to prevent transport of soil and sediment offsite. Any sediment tracked onto offsite paved areas shall be removed via sweeping at least daily.
5. Trash and other construction wastes shall be placed in a designated area at least daily and shall be disposed of in accordance with applicable requirements.
6. Materials shall be stored to avoid being transported in storm water runoff and non-storm water discharges. Concrete washout shall be directed to a washout area and shall not be washed out to the ground.
7. Stockpiles and other sources of pollutants shall be covered when the chance of rain within the next 48 hours is at least 50%.

I certify that the stormwater quality protection measures listed above will be implemented at the project described on Intake Form. I understand that failure to implement these measures may result in monetary penalties or other enforcement actions. This certification is signed under penalty of perjury and does not require notarization.

Name: _____ Title: _____

Signature: _____ Date: _____

Section 2: Determine if Project is a Standard Project or Priority Development Project

Is the project in any of the following categories, (a) through (j)?

(a) New development that **creates 10,000 square feet** or more of impervious surfaces (collectively over the entire project site). This includes commercial, industrial, residential, mixed-use, and public development projects on public or private land. Yes No

(b) Redevelopment project that **creates and/or replaces 5,000 square feet** or more of impervious surface (collectively over the entire project site on an existing site of 10,000 square feet or more of impervious surfaces). This includes commercial, industrial, residential, mixed-use, and public development projects on public or private land. Yes No

(c) New development or redevelopment projects that **creates and/or replaces a combined total of 5,000 square feet** or more of impervious surface (collectively over the entire project site) and support one or more of the following uses: Yes No

(i) **Restaurant.** This category is defined as a facility that sells prepared foods and drinks for consumption, including stationary lunch counters and refreshment stands selling prepared foods and drinks for immediate consumption (Standard Industrial Classification Code 5812).

(ii) **Hillside development projects.** This category includes development on any natural slope that is twenty-five percent or greater.

(iii) **Parking Lots.** This category is defined as a land area or facility for the temporary parking or storage of motor vehicles used personally, for business, or for commerce.

(iv) **Streets, roads, highways, freeways, and driveways.** This category is defined as any paved impervious surface used for the transportation of automobiles, trucks, motorcycles, and other vehicles.

(d) New development or redevelopment project that **creates and/or replaces 2,500 square feet** or more of impervious surface (collectively over the entire project site), discharging directly to an Environmentally Sensitive Area (ESA). "Discharging directly to" includes flow that is conveyed overland a distance of 200 feet or less from the project to the ESA, or conveyed in a pipe or open channel any distance as an isolated flow from the project to the ESA (i.e. not commingled with flows from adjacent lands). Yes No

(e) New development or redevelopment project that creates and/or replaces a combined total of 5,000 square feet or more of impervious surface, that support one or more of the following used: Yes No

(i) Automotive repair shops. This category is defined as a facility that is categorized in any one of the following Standard Industrial Classification (SIC) codes: 5013, 5014, 5541, 7532-7534, or 7536-7539.

(ii) Retail gasoline outlets. This category includes retail gasoline outlets that meet the meet one of the following criteria: (a) 5,000 square feet or more or (b) a projected Average Daily Traffic (ADT) of 100 or more vehicles per day.

(f) New development or redevelopment that result in the disturbance of **one or more acres** of land and are expected to generate pollutants post construction. This does not include projects creating less than 5,000 sf of impervious surface and where added landscaping does not require regular use of pesticides and fertilizers, such as slope stabilization using native plants. Calculation of the square footage of impervious surface need not include linear pathways that are for infrequent vehicle use, such as emergency maintenance access or bicycle pedestrian use, if they are built with pervious surfaces or if they sheet flow to surrounding pervious surfaces. Yes No

The project is (select one):

- If "No" is checked for every category in Section 2, **Project is "Standard Development Project"**. Site design and source control BMP requirements apply. **Complete and submit Standard SWQMP** (refer to Chapter 4 & Appendix E of the BMP Design Manual for guidance). Continue to Section 4.
- If "Yes" is checked for ANY category in Section 2, **Project is "Priority Development Project (PDP)"**. Complete below, if applicable, and continue to Section 3.

Complete for PDP Redevelopment Projects ONLY:

The total existing (pre-project) impervious area at the project site is: _____ ft² (A)

The total proposed newly created or replaced impervious area is _____ ft² (B)

Percent impervious surface created or replaced (B/A)*100: _____%

The percent impervious surface created or replaced is (select one based on the above calculation):

- less than or equal to fifty percent (50%) – **only new impervious areas are considered a PDP**
OR
- greater than fifty percent (50%) – **the entire project site is considered a PDP**
- Continue to Section 3**

Section 3: Determine if project is PDP Exempt

1. Does the project ONLY include new or retrofit sidewalk, bicycle lane or trails that:

- Are designed and constructed to direct storm water runoff to adjacent vegetated areas, or other non-erodible permeable areas? Or;
- Are designed and constructed to be hydraulically disconnected from paved streets or roads? Or;
- Are designed and constructed with permeable pavements or surfaces in accordance with USEPA Green Streets guidance?

Yes. Project is PDP Exempt.

No. Next question

Complete and submit **Standard SWQMP**
(refer to Chapter 4 of the BMP Design Manual
for guidance). **Continue to Section 4.**

2. Does the project ONLY include retrofitting or redevelopment of existing paved alleys, streets or roads designed and constructed in accordance with the Green Streets standards?

Yes.
Project is PDP Exempt.

Complete and submit Standard SWQMP (refer
to Chapter 4 of the BMP Design Manual for
guidance). **Continue to Section 4.**

No.
Project is PDP.

Site design, source control and structural
pollutant control BMPs apply. Complete
and submit PDP SWQMP (refer to
Chapters 4, 5 & 6 of the BMP Design
Manual for guidance). **Continue to
Section 4.**

SECTION 4: Construction Storm Water BMP Requirements:

All construction sites are required to implement construction BMPs in accordance with the performance standards in the BMP Design Manual. Some sites are additionally required to obtain coverage under the State Construction General Permit (CGP), which is administered by the State Water Resource Control Board.

1. Does the project include Building/Grading/Construction permits proposing less than 5,000 square feet of ground disturbance and has less than 5-foot elevation change over the entire project area?

Yes; review & sign Construction Storm Water Certification Statement, skip questions 2-4 No; next question

2. Does the project propose construction or demolition activity, including but not limited to, clearing grading, grubbing, excavation, or other activity that results in ground disturbance of less than one acre and more than 5,000 square feet?

Yes. complete & submit Construction Storm Water Pollution Control Plan (CSWPCP), skip questions 3-4 No; next question

3. Does the project results in disturbance of an acre or more of total land area and are considered regular maintenance projects performed to maintain original line and grade, hydraulic capacity, or original purpose of the facility? (Projects such as sewer/storm drain/utility replacement)

Yes. complete & submit Construction Storm Water Pollution Control Plan (CSWPCP), skip question 4 No; next question

4. Is the project proposing land disturbance greater than or equal to one acre OR the project is part of a larger common plan of development disturbing 1 acre or more?

Yes; Storm Water Pollution Prevention Plan (SWPPP) is required. Refer to online CASQA or Caltrans Template. Visit the SWRCB web site at http://www.waterboards.ca.gov/water_issues/programs/stormwater/construction.shtml.

Note: for Projects that result in disturbance of one to five acres of total land area and can demonstrate that there will be no adverse water quality impacts by applying for a Construction Rainfall Erosivity Waiver, may be allowed to submit a CSWPCP in lieu of a SWPPP.

Project Name/_____

HMP Exemption Exhibit

Attach this Exhibit (if Applicable) that shows direct storm water runoff discharge from the project site to HMP exempt area. Include project area, applicable underground storm drains line and/or concrete lined channels, outfall information and exempt waterbody. Reference applicable drawing number(s). **Exhibit must be provided on 11"x17" or larger paper.**

Nakano

Project Name: _____

Site Information Checklist		Form I-3B
Project Summary Information		
Project Name	Nakano	
Project Address	North of the intersection of Dennerly Rd & Regatta Lane, Chula Vista, CA 92154	
Assessor's Parcel Number(s) (APN(s))	624-071-02	
Permit Application Number		
Project Watershed	<input checked="" type="checkbox"/> San Diego Bay	
Hydrologic Subarea name with Numeric Identifier up to two decimal places	Select One: <input type="checkbox"/> Pueblo San Diego 908 <input type="checkbox"/> Sweetwater 909 <input checked="" type="checkbox"/> Otay 910	
Project Area (total area of Assessor's Parcel(s) associated with the project or total area of the right-of-way)	<u>23.77</u> Acres (<u>1,035,418</u> Square Feet)	
Area to be Disturbed by the Project (Project Footprint)	<u>20.30</u> Acres (<u>884,389</u> Square Feet)	
Project Proposed Impervious Area (subset of Project Footprint)	<u>13.00</u> Acres (<u>566,445</u> Square Feet)	
Project Proposed Pervious Area (subset of Project Footprint)	<u>4.45</u> Acres (<u>198,057</u> Square Feet)	
Note: Proposed Impervious Area + Proposed Pervious Area = Area to be Disturbed by the Project. This may be less than the Parcel Area.		
The proposed increase or decrease in impervious area in the proposed condition as compared to the pre-project condition	<u>64</u> %	

Form I-3B Page 3 of 10	
Description of Existing Site Condition and Drainage Patterns	
<p>Current Status of the Site (select all that apply):</p> <ul style="list-style-type: none"> <input type="checkbox"/> Existing development <input checked="" type="checkbox"/> Previously graded but not built out <input type="checkbox"/> Demolition completed without new construction <input type="checkbox"/> Agricultural or other non-impervious use <input checked="" type="checkbox"/> Vacant, undeveloped/natural <p>Description / Additional Information:</p> <p>Presently the site is undeveloped, mostly vacant and natural other than small utilities facilities.</p>	
<p>Existing Land Cover Includes (select all that apply):</p> <ul style="list-style-type: none"> <input checked="" type="checkbox"/> Vegetative Cover <input type="checkbox"/> Non-Vegetated Pervious Areas <input type="checkbox"/> Impervious Areas <p>Description / Additional Information:</p> <p>Presently the site is undeveloped and natural with grassland, hillside, utilities facilities and a small dirt path traversing the property.</p>	
<p>Underlying Soil belongs to Hydrologic Soil Group (select all that apply):</p> <ul style="list-style-type: none"> <input type="checkbox"/> NRCS Type A <input type="checkbox"/> NRCS Type B <input checked="" type="checkbox"/> NRCS Type C <input checked="" type="checkbox"/> NRCS Type D 	
<p>Approximate Depth to Groundwater (GW):</p> <ul style="list-style-type: none"> <input type="checkbox"/> GW Depth < 5 feet <input type="checkbox"/> 5 feet < GW Depth < 10 feet <input type="checkbox"/> 10 feet < GW Depth < 20 feet <input checked="" type="checkbox"/> GW Depth > 20 feet 	
<p>Existing Natural Hydrologic Features (select all that apply):</p> <ul style="list-style-type: none"> <input checked="" type="checkbox"/> Watercourses <input type="checkbox"/> Seeps <input type="checkbox"/> Springs <input type="checkbox"/> Wetlands <input type="checkbox"/> None <p>Description / Additional Information:</p> <p>Runon from the south flows north along the eastern edge of the project in an existing natural channel which is within a CDFW jurisdictional area.</p>	

Project Name: _____

Form I-3B Page 3 of 10

Description of Existing Site Drainage Patterns

How is storm water runoff conveyed from the site? At a minimum, this description should answer:

1. whether existing drainage conveyance is natural or urban;
2. Is runoff from offsite conveyed through the site? if yes, quantify all offsite drainage areas, design flows, and locations where offsite flows enter the project site, and summarize how such flows are conveyed through the site;
3. Provide details regarding existing project site drainage conveyance network, including any existing storm drains, concrete channels, swales, detention facilities, storm water treatment facilities, natural or constructed channels; and
4. Identify all discharge locations from the existing project site along with a summary of conveyance system size and capacity for each of the discharge locations. Provide summary of the pre-project drainage areas and design flows to each of the existing runoff discharge locations.

Describe existing site drainage patterns:

1. The existing drainage conveyance is mostly natural with minimal drainage improvements.
2. There are about 10.1 acres of runoff areas draining onto the site from upstream areas from Kaiser Permanente and flows to the northeast of project site through natural conveyance to the northerly property line. Most of this portion of the runoff from the north flows through the site and also along the western edge of the project site. A pipe will convey most of the runoff flows through the site and out the center outfall of the proposed conditions. A low flow splitter will be utilized to maintain flow in the natural conveyance along the east portion of the project.
3. There are currently minimal drainage improvements within the project boundary.
4. The majority of the project drains to the north towards Otay River. The onsite portion sheet flows across the property to the north which eventually flows to Otay River. A clear natural channel is not defined though.

Refer to the project drainage study for additional information.

Form I-3B Page 4 of 10

Description of Proposed Site Development and Drainage Patterns

Project Description / Proposed Land Use and/or Activities:
The Nakano project proposes a total of 61 detached condominiums, 84 duplexes, and 70 multi-family dwelling units. Two biofiltration basins will be installed, one in the northwest corner of the site and center east side of the project as well as a detention vault and modular wetland unit for water quality treatment. Two mini parks will be constructed in the center north and northwest locations of the project.

List/describe proposed impervious features of the project (e.g., buildings, roadways, parking lots, courtyards, athletic courts, other impervious features):
The impervious features of the project consist of building roofs, driveways, streets, concrete sidewalks, and other miscellaneous improvements.

List/describe proposed pervious features of the project (e.g., landscape areas):
The pervious features of the project consist of landscaping areas, two biofiltration basins and a proposed park.

Does the project include grading and changes to site topography?
 Yes
 No

Description / Additional Information:
The site will be mass graded to build the residential units, but the proposed grading maintains similar slope to existing condition.



Project Name: _____

Form I-3B Page 5 of 10

Does the project include changes to site drainage (e.g., installation of new storm water conveyance systems)?

- Yes
- No

If yes, provide details regarding the proposed project site drainage conveyance network, including storm drains, concrete channels, swales, detention facilities, storm water treatment facilities, natural or constructed channels, and the method for conveying offsite flows through or around the proposed project site. Identify all discharge locations from the proposed project site along with a summary of the conveyance system size and capacity for each of the discharge locations. Provide a summary of pre- and post-project drainage areas and design flows to each of the runoff discharge locations. Reference the drainage study for detailed calculations.

Describe proposed site drainage patterns:

The project site will include a storm drain system consisting of roof drains, inlets, pipes, brow ditches, and water quality features/detention basin.
The proposed drainage improvements include private storm drain improvements serving the private development lots. The site generally maintains the natural drainage, flowing to the north.

Project Name: _____

Form I-3B Page 6 of 10

Identify whether any of the following features, activities, and/or pollutant source areas will be present (select all that apply):

- On-site storm drain inlets
- Interior floor drains and elevator shaft sump pumps
- Interior parking garages
- Need for future indoor & structural pest control
- Landscape/Outdoor Pesticide Use
- Pools, spas, ponds, decorative fountains, and other water features
- Food service
- Refuse areas
- Industrial processes
- Outdoor storage of equipment or materials
- Vehicle and Equipment Cleaning
- Vehicle/Equipment Repair and Maintenance
- Fuel Dispensing Areas
- Loading Docks
- Fire Sprinkler Test Water
- Miscellaneous Drain or Wash Water
- Plazas, sidewalks, and parking lots

Description / Additional Information:

The project will have features typical of proposed land uses including parks, residential units with landscaped areas, sidewalks and onsite storm drain inlets.

Project Name: _____

Form I-3B Page 7 of 10

Identification and Narrative of Receiving Water and Pollutants of Concern

Describe flow path of storm water from the project site discharge location(s), through urban storm conveyance systems as applicable, to receiving creeks, rivers, and lagoons as applicable, and ultimate discharge to the Pacific Ocean (or bay, lagoon, lake or reservoir, as applicable):

The majority of the project drains to the north and sheet flows towards Otay River. There is no storm drain conveyance system or facilities onsite. Otay River then flows to the San Diego Bay.

List any 303(d) impaired water bodies within the path of storm water from the project site to the Pacific Ocean (or bay, lagoon, lake or reservoir, as applicable), identify the pollutant(s)/stressor(s) causing impairment, and identify any TMDLs and/or Highest Priority Pollutants from the WQIP for the impaired water bodies:

303(d) Impaired Water Body	Pollutant(s)/Stressor(s)	TMDLs / WQIP Highest Priority Pollutant
San Diego Bay	Mercury, PAHs, PCBs	Mercury, PAHs, PCBs

Identification of Project Site Pollutants*

*Identification of project site pollutants is only required if flow-thru treatment BMPs are implemented onsite in lieu of retention or biofiltration BMPs (note the project must also participate in an alternative compliance program unless prior lawful approval to meet earlier PDP requirements is demonstrated)

Identify pollutants expected from the project site based on all proposed use(s) of the site (see BMP Design Manual Appendix B.6):

Pollutant	Not Applicable to the Project Site	Expected from the Project Site	Also a Receiving Water Pollutant of Concern
Sediment	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Nutrients	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Heavy Metals	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Organic Compounds	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Trash & Debris	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Oxygen Demanding Substances	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Oil & Grease	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Bacteria & Viruses	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Pesticides	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>



Form I-3B Page 8 of 10

Hydromodification Management Requirements

Do hydromodification management requirements apply (see Section 1.6)?

- Yes, hydromodification management flow control structural BMPs required.
- No, the project will discharge runoff directly to existing underground storm drains discharging directly to water storage reservoirs, lakes, enclosed embayments, or the Pacific Ocean.
- No, the project will discharge runoff directly to conveyance channels whose bed and bank are concrete-lined all the way from the point of discharge to water storage reservoirs, lakes, enclosed embayments, or the Pacific Ocean.
- No, the project will discharge runoff directly to an area identified as appropriate for an exemption by the WMAA for the watershed in which the project resides.

Description / Additional Information (to be provided if a 'No' answer has been selected above):

Note: If “No” answer has been selected the SWQMP must include an exhibit that shows the storm water conveyance system from the project site to an exempt water body. The exhibit should include details about the conveyance system and the outfall to the exempt water body.

Critical Coarse Sediment Yield Areas*

***This Section only required if hydromodification management requirements apply**

Based on Section 6.2 and Appendix H does CCSYA exist on the project footprint or in the upstream area draining through the project footprint?

- Yes
- No

Description / Additional Information:

Yes, a small portion of CCSYAs exist on the project footprint. One CCSYA area is draining onto the project will be mitigated by using the avoidance metric per Section H.2.1 of the City of Chula Vista BMP Design Manual. The disturbed onsite CCSYA Area of 6,441 SF is less than 5% of the area draining to POC 2 (172,005 SF). The CCSYA area is 3.7% of the area draining to the POC.

The second CCSYA area is a hillslope area and will be bypassed and flow into a drainage ditch to the northeast corner of the project. The drainage ditch will convey bed sediment from the hillslope to the downstream waters by maintaining a peak velocity of greater than 3 ft/s for the 2-year, 24 hour runoff event per Section H.3.1. Continued below.



Project Name: _____

Form I-3B Page 9 of 10

Flow Control for Post-Project Runoff*
***This Section only required if hydromodification management requirements apply**

List and describe point(s) of compliance (POCs) for flow control for hydromodification management (see Section 6.3.1). For each POC, provide a POC identification name or number correlating to the project's HMP Exhibit and a receiving channel identification name or number correlating to the project HMP Exhibit.

POC 1 is located in the northwest portion of the project site.

POC 2 is located in the center north area of the project site.

Has a geomorphic assessment been performed for the receiving channel(s)?

- No, the low flow threshold is 0.1Q2 (default low flow threshold)
- Yes, the result is the low flow threshold is 0.1Q2
- Yes, the result is the low flow threshold is 0.3Q2
- Yes, the result is the low flow threshold is 0.5Q2

If a geomorphic assessment has been performed, provide title, date, and preparer:

Discussion / Additional Information: (optional)



Project Name: _____

Form I-3B Page 10 of 10

Other Site Requirements and Constraints

When applicable, list other site requirements or constraints that will influence storm water management design, such as zoning requirements including setbacks and open space, or local codes governing minimum street width, sidewalk construction, allowable pavement types, and drainage requirements.

Optional Additional Information or Continuation of Previous Sections As Needed

This space provided for additional information or continuation of information from previous sections as needed.

Project Name: _____

Source Control BMP Checklist for All Development Projects		Form I-4	
<p>All development projects must implement source control BMPs. Refer to Chapter 4 and Appendix E of the BMP Design Manual for information to implement BMPs shown in this checklist.</p> <p>Note: All selected BMPs must be shown on the site/construction plans.</p> <p>Answer each category below pursuant to the following:</p> <ul style="list-style-type: none"> • "Yes" means the project will implement the source control BMP as described in Chapter 4 and/or Appendix E of the BMP Design Manual. Discussion / justification is not required. • "No" means the BMP is applicable to the project but it is not feasible to implement. Discussion / justification must be provided. • "N/A" means the BMP is not applicable at the project site because the project does not include the feature that is addressed by the BMP (e.g., the project has no outdoor materials storage areas). Discussion / justification may be provided. 			
Source Control Requirement	Applied?		
4.2.1 Prevention of Illicit Discharges into the MS4	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Discussion / justification if 4.2.1 not implemented:			
4.2.2 Storm Drain Stenciling or Signage	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Discussion / justification if 4.2.2 not implemented:			
4.2.3 Protect Outdoor Materials Storage Areas from Rainfall, Run-On, Runoff, and Wind Dispersal	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A
Discussion / justification if 4.2.3 not implemented: No outdoor material storage areas planned.			
4.2.4 Protect Materials Stored in Outdoor Work Areas from Rainfall, Run-On, Runoff, and Wind Dispersal	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A
Discussion / justification if 4.2.4 not implemented:			
4.2.5 Protect Trash Storage Areas from Rainfall, Run-On, Runoff, and Wind Dispersal	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
Discussion / justification if 4.2.5 not implemented: Trash storage areas will be located indoors and/or trash receptacles with lids will be used.			

Project Name: _____

Source Control BMP Checklist for All Development Projects		Form I-4 (Page 2 of 2)	
4.2.6 Additional BMPs Based on Potential Sources of Runoff Pollutants (must answer for each source listed below)	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
SC-A Onsite storm drain inlets	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
SC-B Interior floor drains and elevator shaft sump pumps	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A
SC-C Interior parking garages	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A
SC-D1 Need for future indoor & structural pest control	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A
SD-D2 Landscape/outdoor pesticide use	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
SC-E Pools, spas, ponds, decorative fountains, and other water features	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A
SC-F Food Service	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A
SC-G Refuse areas	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
SC-H Industrial processes	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A
SC-I Outdoor storage of equipment or materials	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A
SC-J Vehicle and equipment cleaning	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A
SC-K Vehicle/equipment repair and maintenance	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A
SC-L Fuel dispensing areas	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A
SC-M Loading docks	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A
SC-N Fire sprinkler test water	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
SC-O Miscellaneous drain or wash water	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
SC-P Plazas, sidewalks, and parking lots	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
SC-Q: Large Trash Generating Facilities	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A
SC-R: Animal Facilities	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A
SC-S: Plant Nurseries and Garden Centers	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A
SC-T: Automotive Facilities	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A
Discussion / justification if 4.2.6 not implemented. Justification must be provided for all "No" answers shown above.			

Project Name.: _____

Site Design BMP Checklist for All Development Projects		Form I-5	
<p>All development projects must implement site design BMPs where applicable and feasible. See Chapter 4 and Appendix E of the manual for information to implement site design BMPs shown in this checklist. Note: All selected BMPs must be shown on the site/construction plans.</p> <p>Answer each category below pursuant to the following.</p> <ul style="list-style-type: none"> • "Yes" means the project will implement the site design BMP as described in Chapter 4 and/or Appendix E of the manual. Discussion / justification is not required. • "No" means the BMP is applicable to the project but it is not feasible to implement. Discussion / justification must be provided. • "N/A" means the BMP is not applicable at the project site because the project does not include the feature that is addressed by the BMP (e.g., the project site has no existing natural areas to conserve). Discussion / justification may be provided. 			
Site Design Requirement	Applied?		
4.3.1 Maintain Natural Drainage Pathways and Hydrologic Features	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
4.3.2 Conserve Natural Areas, Soils, and Vegetation	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
4.3.3 Minimize Impervious Area	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
4.3.4 Minimize Soil Compaction	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
4.3.5 Impervious Area Dispersion	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A

Nakano

Project Name/Address/N _____

Site Design BMP Checklist for All Development Projects		Form I-5	
Site Design Requirement	Applied?		
4.3.6 Runoff Collection	<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input checked="" type="checkbox"/> N/A
4.3.7 Landscaping with Native or Drought Tolerant Species	<input checked="" type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> N/A
4.3.8 Harvesting and Using Precipitation	<input type="checkbox"/> Yes	<input checked="" type="checkbox"/> No	<input type="checkbox"/> N/A
Discussion / justification for all "No" answers shown above: Harvest and Reuse not feasible per calculations in Form I-7.			

Project Name: _____

Summary of PDP Structural BMPs	Form I-6
PDP Structural BMPs	
<p>All PDPs must implement structural BMPs for storm water pollutant control (see Chapter 5 of the manual). Selection of PDP structural BMPs for storm water pollutant control must be based on the selection process described in Chapter 5. PDPs subject to hydromodification management requirements must also implement structural BMPs for flow control for hydromodification management (see Chapter 6 of the manual). Both storm water pollutant control and flow control for hydromodification management can be achieved within the same structural BMP(s).</p> <p>PDP structural BMPs must be verified by City at the completion of construction. This may include requiring the project owner or project owner's representative to certify construction of the structural BMPs (see Section 1.12 of the manual). PDP structural BMPs must be maintained into perpetuity (see Section 7 of the manual).</p> <p>Use this form to provide narrative description of the general strategy for structural BMP implementation at the project site in the box below. Then complete the PDP structural BMP summary information sheet (page 3 of this form) for each structural BMP within the project (copy the BMP summary information page as many times as needed to provide summary information for each individual structural BMP).</p>	
<p>Describe the general strategy for structural BMP implementation at the site. This information must describe how the steps for selecting and designing storm water pollutant control BMPs presented in Section 5.1 of the manual were followed, and the results (type of BMPs selected). For projects requiring hydromodification flow control BMPs, indicate whether pollutant control and flow control BMPs are integrated or separate.</p> <p>The project geotechnical engineer has deemed the entire site to be a no-infiltration site for stormwater purposes. Harvest and reuse calculations showed that stormwater reuse was deemed infeasible for this project site. Due to the "no infiltration" conditions, two biofiltration basins and a detention vault in a combination with a Modular Wetland Unit will be used for pollutant control and volume retention requirements. Some slopes to the western perimeter will be graded and drain directly off site without any imperviousness and will therefore be treated as self-mitigating. Refer to Attachment 1A for the identification of the areas.</p> <p>The biofiltration basins combined with the detention vault and the Modular Wetland Unit will individually meet pollutant treatment requirements for the drainage areas. The volume retention is analyzed for the entire site and will be met with a combination of biofiltration basins, and impervious dispersion of hardscape to landscape areas. These dispersion areas utilized for the volume retention credit are located within the non-contiguous sidewalks and adjacent landscaping strips along the Private Drives throughout the project. Refer to the DMA exhibit for further information. The dispersion to landscape area will be less than 10 feet, but it meets the criteria when the contributing flow path length of the impervious area / pervious area width is less than or equal to 2 and a maximum slope of 5% (See page B-48 of the 2021 City of Chula Vista BMP Design Manual)</p>	

Project Name: _____

Summary of PDP Structural BMPs	Form I-6
PDP Structural BMPs	
<p>All PDPs must implement structural BMPs for storm water pollutant control (see Chapter 5 of the manual). Selection of PDP structural BMPs for storm water pollutant control must be based on the selection process described in Chapter 5. PDPs subject to hydromodification management requirements must also implement structural BMPs for flow control for hydromodification management (see Chapter 6 of the manual). Both storm water pollutant control and flow control for hydromodification management can be achieved within the same structural BMP(s).</p> <p>PDP structural BMPs must be verified by City at the completion of construction. This may include requiring the project owner or project owner's representative to certify construction of the structural BMPs (see Section 1.12 of the manual). PDP structural BMPs must be maintained into perpetuity (see Section 7 of the manual).</p> <p>Use this form to provide narrative description of the general strategy for structural BMP implementation at the project site in the box below. Then complete the PDP structural BMP summary information sheet (page 3 of this form) for each structural BMP within the project (copy the BMP summary information page as many times as needed to provide summary information for each individual structural BMP).</p>	
<p>Describe the general strategy for structural BMP implementation at the site. This information must describe how the steps for selecting and designing storm water pollutant control BMPs presented in Section 5.1 of the manual were followed, and the results (type of BMPs selected). For projects requiring hydromodification flow control BMPs, indicate whether pollutant control and flow control BMPs are integrated or separate.</p> <p>The project geotechnical engineer has deemed the entire site to be a no-infiltration site for stormwater purposes. Harvest and reuse calculations showed that stormwater reuse was deemed infeasible for this project site. Due to the "no infiltration" conditions, two biofiltration basins and a detention vault in a combination with a Modular Wetland Unit will be used for pollutant control and volume retention requirements. Some slopes to the western perimeter will be graded and drain directly off site without any imperviousness and will therefore be treated as self-mitigating. Refer to Attachment 1A for the identification of the areas.</p> <p>The biofiltration basins combined with the detention vault and the Modular Wetland Unit will individually meet pollutant treatment requirements for the drainage areas. The volume retention is analyzed for the entire site and will be met with a combination of biofiltration basins, and impervious dispersion of hardscape to landscape areas. These dispersion areas utilized for the volume retention credit are located within the non-contiguous sidewalks and adjacent landscaping strips along the Private Drives throughout the project. Refer to the DMA exhibit for further information. The dispersion to landscape area will be less than 10 feet, but it meets the criteria when the contributing flow path length of the impervious area / pervious area width is less than or equal to 2 and a maximum slope of 5% (See page B-48 of the 2021 City of Chula Vista BMP Design Manual)</p>	

Project Name: _____

Summary of PDP Structural BMPs	Form I-6
PDP Structural BMPs	
<p>All PDPs must implement structural BMPs for storm water pollutant control (see Chapter 5 of the manual). Selection of PDP structural BMPs for storm water pollutant control must be based on the selection process described in Chapter 5. PDPs subject to hydromodification management requirements must also implement structural BMPs for flow control for hydromodification management (see Chapter 6 of the manual). Both storm water pollutant control and flow control for hydromodification management can be achieved within the same structural BMP(s).</p> <p>PDP structural BMPs must be verified by City at the completion of construction. This may include requiring the project owner or project owner's representative to certify construction of the structural BMPs (see Section 1.12 of the manual). PDP structural BMPs must be maintained into perpetuity (see Section 7 of the manual).</p> <p>Use this form to provide narrative description of the general strategy for structural BMP implementation at the project site in the box below. Then complete the PDP structural BMP summary information sheet (page 3 of this form) for each structural BMP within the project (copy the BMP summary information page as many times as needed to provide summary information for each individual structural BMP).</p>	
<p>Describe the general strategy for structural BMP implementation at the site. This information must describe how the steps for selecting and designing storm water pollutant control BMPs presented in Section 5.1 of the manual were followed, and the results (type of BMPs selected). For projects requiring hydromodification flow control BMPs, indicate whether pollutant control and flow control BMPs are integrated or separate.</p> <p>DMA 1 is the northwest portion of residential units that flows via the gutter system towards a reverse curb outlet and enters a lined biofiltration basin (BMP#1) in the northwest corner of the project site.</p> <p>DMA 3 collects a majority of the onsite project site of residential units and streets. This DMA will be treated by one planted-type modular wetland unit (BMP#3) downstream a detention vault which will detain 2.6DCV with a drawdown time less than 96 hrs. Because the unit is situated downstream of the vault, and the vault detains the water quality capture volume the modular wetland unit is sized based on a volume-basis in combination with the vault. Based on the Percent Capture method, capturing and treating 1.25DCV with a 24 hour drawdown is equivalent to a 2.6 DCV capture with a 96-hour drawdown. The "default" sizing methodology for proprietary biofiltration is 1.5 WQF, but in this case the project will size the BMP based on the percent capture method and the volume-based sizing methodology, to ensure that the vault and proprietary biofiltration downstream of the vault are both sized adequately.</p> <p>DMA 2 collects a portion of the center east project site area and is drained to a lined biofiltration basin (BMP#2).</p>	

Form I-6 Page 3 of 8 (Copy and attach as many as needed)	
Structural BMP ID No. 1	
Construction Plan Sheet No.	
Type of structural BMP: <input type="checkbox"/> Retention by harvest and use (e.g. HU-1, cistern) <input type="checkbox"/> Retention by infiltration basin (INF-1) <input type="checkbox"/> Retention by bioretention (INF-2) <input type="checkbox"/> Retention by permeable pavement (INF-3) <input type="checkbox"/> Partial retention by biofiltration with partial retention (PR-1) <input checked="" type="checkbox"/> Biofiltration (BF-1) <input type="checkbox"/> Flow-thru treatment control with prior lawful approval to meet earlier PDP requirements (provide BMP type/description in discussion section below) <input type="checkbox"/> Flow-thru treatment control included as pre-treatment/forebay for an onsite retention or biofiltration BMP (provide BMP type/description and indicate which onsite retention or biofiltration BMP it serves in discussion section below) <input type="checkbox"/> Flow-thru treatment control with alternative compliance (provide BMP type/description in discussion section below) <input type="checkbox"/> Detention pond or vault for hydromodification management <input type="checkbox"/> Other (describe in discussion section below)	
Purpose: <input type="checkbox"/> Pollutant control only <input type="checkbox"/> Hydromodification control only <input checked="" type="checkbox"/> Combined pollutant control and hydromodification control <input type="checkbox"/> Pre-treatment/forebay for another structural BMP <input type="checkbox"/> Other (describe in discussion section below)	
Who will certify construction of this BMP? Provide name and contact information for the party responsible to sign BMP verification forms if required by the City Engineer (See Section 1.12 of the manual)	Chelisa Pack, RCE 71026 Project Design Consultants 619.235.6471
Who will be the final owner of this BMP?	HOA
Who will maintain this BMP into perpetuity?	HOA
What is the funding mechanism for maintenance?	HOA

Project Name: _____

Form I-6 Page 4 of 8 *(Copy and attach as many as needed)*

Structural BMP ID No. 1

Construction Plan Sheet No.

Discussion (as needed, must include worksheets showing BMP sizing calculations in the SWQMP):

BMP#1 is a lined biofiltration basin with a bottom footprint of 3,608 SF. This basin consists of 12" of aggregate storage, 3" of ASTM No. 8 Stone, 18" biofiltration media, 3" of ASTM 33 fine aggregate sand and 3" mulch with 6" of ponding.

Project Name: _____

Structural BMP ID No. 2

Construction Plan Sheet No.

Discussion (as needed, must include worksheets showing BMP sizing calculations in the SWQMP):

BMP#2 is a lined biofiltration basin with a bottom footprint of 4,523 SF. This basin consists of 12" of aggregate storage, 3" of ASTM No. 8 Stone, 18" biofiltration media, 3" of ASTM 33 fine aggregate sand and 3" mulch with 6" of ponding.

Project Name: _____

Form I-6 Page 8 of 8 *(Copy and attach as many as needed)***Structural BMP ID No. 3****Construction Plan Sheet No.**

Discussion (as needed, must include worksheets showing BMP sizing calculations in the SWQMP):

BMP#3 is a compact biofiltration BF-3 type Modular Wetland Unit(planted 8-24 model) from the manufacturer Bioclean. This BMP will be downstream of a detention vault. The flow will enter the detention vault with a footprint of 12,736 SF and 5 feet tall. This vault has a capacity of 63,680 CF to detain the capture volume dictated by the drawdown time. The MWS unit model utilizes two orifices within the unit. Two 1.48" orifices within the MWS unit will build enough head in vault to treat the required volume through the unit. The MWS unit is sized based on volume to treat the detained flow out from the water quality capture volume in the upstream vault. In the hydromodification SWMM model an equivalent single 2.2" orifice was modeled to achieve the same flow out. See hydromodification study in Attachment 2. Additional cross sections and calculations can be found in Attachment 1e.

Project Name/_____

ATTACHMENT 1

Backup for PDP Pollutant Control BMPs

Indicate which Items are Included:


Attachment Sequence	Contents	Checklist
Attachment 1A	DMA Exhibit (Required) See DMA Exhibit Checklist.	<input type="checkbox"/> Included
Attachment 1B	Tabular Summary of DMAs Showing DMA ID matching DMA Exhibit, DMA Area, and DMA Type (Required)* *Provide table in this Attachment OR on DMA Exhibit in Attachment 1a	<input checked="" type="checkbox"/> Included on DMA Exhibit in Attachment 1A <input type="checkbox"/> Included as Attachment 1B, separate from DMA Exhibit
Attachment 1C	Form I-7, Harvest and Use Feasibility Screening Checklist (Required unless the entire project will use infiltration BMPs) Refer to Appendix B.3-1 of the BMP Design Manual to complete Form I-7.	<input checked="" type="checkbox"/> Included <input type="checkbox"/> Not included because the entire project will use infiltration BMPs
Attachment 1D	Infiltration Feasibility Information. Contents of Attachment 1D depend on the infiltration condition: <input checked="" type="checkbox"/> No Infiltration Condition: <input type="checkbox"/> Infiltration Feasibility Condition <input checked="" type="checkbox"/> Letter (<i>Note: must be stamped & signed by licensed geotechnical engineer</i>) <input type="checkbox"/> Form I-8A (optional) <input checked="" type="checkbox"/> Form I-8B (optional) <input type="checkbox"/> Partial Infiltration Condition: <input checked="" type="checkbox"/> Infiltration Feasibility Condition <input type="checkbox"/> Letter (<i>Note: must be stamped & signed by licensed geotechnical engineer</i>) <input type="checkbox"/> Form I-8A <input type="checkbox"/> Form I-8B <input type="checkbox"/> Full Infiltration Condition: <input type="checkbox"/> Form I-8A <input type="checkbox"/> Form I-8B <input type="checkbox"/> Worksheet C.4-3 <input type="checkbox"/> Form I-9 Refer to Appendices C and D of the BMP Design Manual for guidance.	<input checked="" type="checkbox"/> Included <input type="checkbox"/> Not included because the entire project will use harvest and use BMPs
Attachment 1E	Pollutant Control BMP Design Worksheets/ Calculations (Required) Refer to Appendices B and E of the BMP Design Manual for structural pollutant control BMP design guidelines	<input checked="" type="checkbox"/> Included

Use this checklist to ensure the required information has been included on the DMA Exhibit:

The DMA Exhibit must identify all the following:

- Underlying hydrologic soil group
- Approximate depth to groundwater
- Existing natural hydrologic features (watercourses, seeps, springs, wetlands)
- Critical coarse sediment yield areas to be protected
- Existing topography and impervious areas
- Existing and proposed site drainage network and connections to drainage offsite
- Proposed grading
- Proposed impervious features
- Proposed design features and surface treatments used to minimize imperviousness
- Drainage management area (DMA) boundaries, DMA ID numbers, and DMA areas (square footage or acreage), and DMA type (i.e., drains to BMP, self-retaining, or self-mitigating)
- Potential pollutant source areas and corresponding required source controls (see Chapter 4, Appendix E.1, and Form I-3B)
- Structural BMPs (identify location, type of BMP, and size/detail, and include cross-sections)

ATTACHMENT 1A,1B – DMA MAP



DENNERY VILLAGES 2/3
(RIVEREDGE TERRACE)

DMA SUMMARY				
DMA #	DMA TYPE	BMP TYPE	DRAINAGE AREA (Ac)	BMP Footprint (SF)
1	Drains to BMP	BF-1 LINED BIOFILTRATION	2.49	3608
2	Drains to BMP	BF-1 LINED BIOFILTRATION	4.01	4523
3	Drains to BMP	BF-3 COMPACT BIOFILTRATION & DETENTION VAULT	13.80	VAULT: 12736
4	SELF-MITIGATING	-	1.59	-

TABULAR SUMMARY OF IMPERVIOUS DISPERSION	
TOTAL IMPERVIOUS AREA (SF)	PERVIOUS AREA (SF)
13551	11151

SCALE: 1"=40'

PREPARED BY:

PROJECT DESIGN CONSULTANTS
 Planning | Landscape Architecture | Environmental | Engineering | Survey
 701 B Street, Suite 600 San Diego, CA 92101
 619.236.0471 Tel 619.234.0249 Fax

JOB # 4408.02
 CREATED: 3/11/20

CITY OF CHULA VISTA

NAKANO

DMA EXHIBIT
PROPOSED CONDITIONS
EXHIBIT B

P:\1449\Draw\Drawings\4408.02\Drawings\DWG\17794\17794_11135_Plan.dwg 1/2/2022 9:24:40 AM

Project Name: Nakano

Tabular Summary of DMAs							Worksheet B-1		
DMA Unique Identifier	Area (acres)	Impervious Area (acres)	% Imp	HSG	Area Weighted Runoff Coefficient	DCV (Cubic feet)	Treated by (BMP ID)	Pollutant Control Type	Drains to (POC ID)
1	2.49	1.72	69.2	C/D	0.69	3,108	1	BF-1	1
2	4.01	2.33	58.0	C			2	BF-1	2
3	13.80	8.95	64.8	C			3	BF-3	1
4	1.59	0	0	C		0	-	-	1/2
Summary of DMA Information (Must match Project description and SWQMP narrative)									
No. of DMAs	Total DMA Area (acres)	Total Impervious Area (acres)	% Impervious		Area Weighted Runoff Coefficient	DCV (Cubic feet)	Total Area Treated (acres)		No. of POCs
3*	20.30	13.00	64.0	C/D	0.63	24,074	20.30	BF-1&BF-3	2

Where: DMA = Drainage Management Area Imp = Imperviousness ID = identifier
HSG = Hydrologic Soil Group DCV= Design Capture Volume No. = Number
BMP = Best Management Practice POC = Point of Compliance

*Volume Retention for the site as a whole will be met with Biofiltration Basins and Impervious Dispersion.



**ATTACHMENT 1C – HARVEST & USE FEASIBILITY
CHECKLIST**

Project Name: _____

Harvest and Use Feasibility Screening		FORM I-7 (Worksheet B.3-1)
<p>1. Is there a demand for harvested water (check all that apply) at the project site that is reliably present during the wet season?</p> <p><input checked="" type="checkbox"/> Toilet and urinal flushing</p> <p><input checked="" type="checkbox"/> Landscape irrigation</p> <p><input type="checkbox"/> Other: _____</p>		
<p>2. If there is a demand; estimate the anticipated average wet season demand over a period of 36 hours. Guidance for planning level demand calculations for toilet/urinal flushing and landscape irrigation is provided in Section B.3.2.</p> <p>[Provide a summary of calculations here]</p> <div style="float: right; border: 1px solid black; padding: 2px;">Total Demand = 874 + 733 = 1607 CF</div> <p>Landscape Irrigation: Landscaping area = 4.45 ac Assume Mod. Water Use: 1470 g/ac/36 hours x 4.45 Ac. = 6541.5 gallons (CF/7.48 gallons) = 874 CF</p> <p>Expected Total Population: 157 x 2.5 = 393 36 hr Demand = 9.3 gal/res/day x 1.5 days/36 hr x 393 pop = 5482 gallons (CF/7.48 gal) = 733 CF</p>		
<p>3. Calculate the DCV using worksheet B-2.1.</p> <p>[Provide a result here]</p> <p>3 DMAs including Roof from residential units, at grade hardscape and landscape. See BMP Summary Worksheet. DMA = 24,074 CF</p>		
<p>3a. Is the 36-hour demand greater than or equal to the DCV?</p> <p style="text-align: center;">Yes / No ⇨</p> <p style="text-align: center;">↓</p>	<p>3b. Is the 36-hour demand greater than 0.25DCV but less than the full DCV?</p> <p style="text-align: center;">Yes / No ⇨</p> <p style="text-align: center;">↓</p> <p style="text-align: center;">0.25DCV= 6,019 CF</p>	<p>3c. Is the 36-hour demand less than 0.25DCV?</p> <p style="text-align: center;">Yes</p> <p style="text-align: center;">↓</p>
<p>Harvest and use appears to be feasible. Conduct more detailed evaluation and sizing calculations to confirm that DCV can be used at an adequate rate to meet drawdown criteria.</p>	<p>Harvest and use may be feasible. Conduct more detailed evaluation and sizing calculations to determine feasibility. Harvest and use may only be able to be used for a portion of the site, or (optionally) the storage may need to be upsized to meet long term capture targets while draining in longer than 36 hours.</p>	<p>Harvest and use is considered to be infeasible.</p>

Note: 36-hour demand calculations are for feasibility analysis only, once the feasibility analysis is complete the applicant may be allowed to use a different drawdown time provided they meet the 80 percent of average annual (long term) runoff volume performance standard.



ATTACHMENT 1D – INFILTRATION FEASIBILITY LETTER

Note: This attachment includes two infiltration feasibility letters. The first is formatted for the City of San Diego, and is included for review by the City of San Diego. The second is formatted for the City of Chula Vista, and is included for review by the City of Chula Vista.

City of San Diego Infiltration Feasibility Letter
(For Review by City of San Diego LDR-Engineering and LDR-Geology)



Project No. 07516-42-02
January 9, 2023

Tri Pointe Homes
13520 Evening Creek Drive North, Suite 300
San Diego, California 92128

Attention: Mr. Allen Kashani

Subject: STORMWATER MANAGEMENT RECOMMENDATIONS
NAKANO
SAN DIEGO, CALIFORNIA

Reference: *Update Geotechnical Investigation, Nakano Property, Chula Vista, California* prepared by
Geocon Incorporated dated September 18, 2020 (Project No. 07516-42-02).

Dear Mr. Kashani:

In response to City of San Diego review comments, we have prepared this report to provide stormwater management recommendations for the Nakano project. We previously performed an infiltration study on the property. A summary of our study and stormwater management recommendations are provided in Appendix C of the referenced report. The report was prepared in accordance with City of Chula Vista requirements. Provided herein are stormwater recommendations in accordance with the City of San Diego Stormwater Standards.

Based on the results of our study, full and partial infiltration is considered infeasible due to the presence undocumented fills, low infiltration characteristics, and existing nearby utilities. Basins should utilize a liner to prevent infiltration from causing adverse settlement, migrating to adjacent slopes, utilities, and foundations.

STORM WATER MANAGEMENT

We understand storm water management devices are being proposed in accordance with the current stormwater standards. If not properly constructed, there is a potential for distress to improvements and properties located hydrologically down gradient or adjacent to these devices. Factors such as the amount of water to be detained, its residence time, and soil permeability have an important effect on seepage transmission and the potential adverse impacts that may occur if the storm water management features are not properly designed and constructed. We have not performed a hydrogeological study at the site. If infiltration of storm water runoff occurs, downstream properties and improvements may be subjected

to seeps, springs, slope instability, raised groundwater, movement of foundations and slabs, or other undesirable impacts as a result of water infiltration.

Hydrologic Soil Group

The United States Department of Agriculture (USDA), Natural Resources Conservation Services, possesses general information regarding the existing soil conditions for areas within the United States. The USDA website also provides the Hydrologic Soil Group. Table 1 presents the descriptions of the hydrologic soil groups. In addition, the USDA website also provides an estimated saturated hydraulic conductivity for the existing soil.

**TABLE 1
HYDROLOGIC SOIL GROUP DEFINITIONS**

Soil Group	Soil Group Definition
A	Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.
B	Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.
C	Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.
D	Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

The property is underlain by undocumented fill, surficial deposits such as topsoil, colluvium and alluvium, Terrace Deposits, and the Mission Valley Formation. Table 2 presents the information from the USDA website for the subject property.

**TABLE 2
USDA WEB SOIL SURVEY – HYDROLOGIC SOIL GROUP**

Map Unit Name	Map Unit Symbol	Approximate Percentage of Property	Hydrologic Soil Group
Olivenhain cobbly loam, 9 to 30 percent slopes	OhE	5.0	D
Riverwash	Rm	18.5	D
Salinas clay loam, 0 to 2 percent slopes, warm MAAT, MLRA 19	SbA	76.6	C

Infiltration Testing

We performed two borehole infiltration tests at the locations shown on Figure 1. The tests were performed in 8-inch-diameter, drilled borings. Table 3 presents the results of the testing. The calculation sheets are provided herein.

We used the guidelines presented in the Riverside County Low Impact Development BMP Design Handbook. Based on this widely accepted guideline, the saturated hydraulic conductivity (Ksat) is equivalent to the infiltration rate. Therefore, the Ksat value determined from our testing is assumed to be the unfactored infiltration rate.

**TABLE 3
UNFACTORED, FIELD-SATURATED, INFILTRATION TEST RESULTS**

Test No.	Depth (inches)	Geologic Unit	Field Infiltration Rate, I (in/hr)	Factored* Field Infiltration Rate, I (in/hr)
A-1	68	Qt	0.004	0.002
A-2	92	Qt	0.082	0.041

* Factor of Safety of 2.0 for feasibility determination.

STORM WATER MANAGEMENT CONCLUSIONS

Soil Types

Undocumented Fill (Qpudf) – We encountered undocumented fill up to 18 feet thick at the north end of the property. The undocumented fill within structural improvement areas will be removed and replaced with compacted fill. Water that is allowed to migrate into the undocumented fill or compacted fill will cause settlement. Therefore, full and partial infiltration should be considered infeasible within fill.

Topsoil (Unmapped) – We encountered topsoil varying between 0.5 and 3 feet thick across the site. Topsoil within structural improvement areas will be removed and replaced with compacted fill. Water that is allowed to migrate into the topsoil will cause settlement. Therefore, full and partial infiltration should be considered infeasible within topsoil.

Colluvium (Qcol) – We encountered colluvium on the north-facing slopes at the south property boundary, varying between 0.5 and 5 feet thick. Colluvium within structural improvement areas will be removed and replaced with compacted fill. Water that is allowed to migrate into colluvium will cause settlement. Therefore, full and partial infiltration should be considered infeasible within areas underlain by colluvium.

Alluvium (Qal) – Alluvium is present in a drainage located at the southeast corner of the property. Alluvium was also encountered in Trench T-20 beneath undocumented fill at the north end of the site. Alluvium within structural improvement areas will be removed and replaced with compacted fill. Water that is allowed to migrate into alluvium will cause settlement. Therefore, full and partial infiltration should be considered infeasible within areas underlain by alluvium.

Terrace Deposits (Qt) – We encountered Terrace Deposits underlying most of the site below the artificial fill, topsoil, and alluvium. The Terrace Deposits are comprised of very dense, clayey, conglomerate. Infiltration into the Terrace Deposits is not feasible due to its low infiltration characteristics.

Mission Valley Formation (Tmv) – We encountered age Mission Valley in slopes along the southern portion of the site. Mission Valley Formation may also be present underlying the Terrace Deposits in the central portion of the site. Infiltration into the Mission Valley Formation is not feasible due to low infiltration characteristics.

Groundwater Elevation

Groundwater was not encountered in our borings or trenches to a depth explored. Infiltration should not impact groundwater.

Existing Utilities

Existing utilities are located on the north side of the property and along the west and east property margins. Infiltration near these utilities is considered infeasible. Otherwise, infiltration due to utility concerns would be feasible.

Soil or Groundwater Contamination

We are unaware of contaminated soil or groundwater on the property. Therefore, full and partial infiltration associated with this risk is considered feasible.

Slopes

There are no existing slopes that would be impacted by infiltration. There are proposed fill slopes where infiltration adjacent to the slopes is not feasible.

Infiltration Rates

Our test results indicated slow infiltration rates. The factored rates were 0.002 and 0.082 inches per hour. The infiltration rates are not high enough to support full or partial infiltration.

Storm Water Management Devices

Liners should be incorporated in the proposed basin. The liner should be impermeable (e.g. High-density polyethylene, HDPE, with a thickness of about 30 mil or equivalent Polyvinyl Chloride, PVC). Penetration of the liners should be properly sealed. The devices should also be installed in accordance with the manufacturer’s recommendations. Overflow protection devices should also be incorporated into the design and construction of the storm water management device.

Storm Water Standard Worksheets

The SWS requests the geotechnical engineer complete the *Categorization of Infiltration Feasibility Condition* (Worksheet C.4-1) worksheet information to help evaluate the potential for infiltration on the property. The attached Worksheet C.4-1 presents the completed information for the submittal process.

The regional storm water standards also have a worksheet (Worksheet Form D.5-1) that helps the project civil engineer estimate the factor of safety based on several factors. Table 4 describes the suitability assessment input parameters related to the geotechnical engineering aspects for the factor of safety determination.

**TABLE 4
SUITABILITY ASSESSMENT RELATED CONSIDERATIONS FOR INFILTRATION FACILITY
SAFETY FACTORS**

Consideration	High Concern – 3 Points	Medium Concern – 2 Points	Low Concern – 1 Point
Assessment Methods	Use of soil survey maps or simple texture analysis to estimate short-term infiltration rates. Use of well permeameter or borehole methods without accompanying continuous boring log. Relatively sparse testing with direct infiltration methods	Use of well permeameter or borehole methods with accompanying continuous boring log. Direct measurement of infiltration area with localized infiltration measurement methods (e.g., Infiltrometer). Moderate spatial resolution	Direct measurement with localized (i.e. small-scale) infiltration testing methods at relatively high resolution or use of extensive test pit infiltration measurement methods.
Predominant Soil Texture	Silty and clayey soils with significant fines	Loamy soils	Granular to slightly loamy soils
Site Soil Variability	Highly variable soils indicated from site assessment or unknown variability	Soil boring/test pits indicate moderately homogenous soils	Soil boring/test pits indicate relatively homogenous soils
Depth to Groundwater/ Impervious Layer	<5 feet below facility bottom	5-15 feet below facility bottom	>15 feet below facility bottom

Table 5 presents the estimated factor values for the evaluation of the factor of safety. This table only presents the suitability assessment safety factor (Part A) of the worksheet. The project civil engineer should evaluate the safety factor for design (Part B) and use the combined safety factor for the design infiltration rate.

**TABLE 5
FACTOR OF SAFETY WORKSHEET D.5-1 DESIGN VALUES¹**

Suitability Assessment Factor Category	Assigned Weight (w)	Factor Value (v)	Product (p = w x v)
Assessment Methods	0.25	2	0.50
Predominant Soil Texture	0.25	3	0.75
Site Soil Variability	0.25	2	0.50
Depth to Groundwater/Impervious Layer	0.25	1	0.25
Suitability Assessment Safety Factor, $S_A = \Sigma p$			2.0

¹ The project civil engineer should complete Worksheet D.5-1 using the data on this table. Additional information is required to evaluate the design factor of safety.

CONCLUSIONS

Our results indicate the site has relatively slow infiltration characteristics and should be considered as having a “no infiltration” condition. Because of the site conditions, it is our opinion that there is a potential for lateral water migration if infiltration were to be allowed. Undocumented and previously placed fill exists on the property and has a high potential for adverse settlement when wetted. It is our opinion that full or partial infiltration is infeasible on this site. Our evaluation included the soil and geologic conditions, estimated settlement and volume change of the underlying soil, slope stability, utility considerations, groundwater mounding, retaining walls, foundations and existing groundwater elevations.

If there are any questions regarding this correspondence, or if we may be of further service, please contact the undersigned at your convenience.

Very truly yours,



GEOCON INCORPORATED

Rodney C. Mikesell
GE 2533

RCM:arm

(e-mail) Addressee





GEOCON LEGEND

- Qudf.....UNDOCUMENTED FILL
- Qaf.....ARTIFICIAL FILL
- Qal.....ALLUVIUM
- Qt.....TERRACE DEPOSITS
(Dotted Where Buried)
- Tsd_{cg}.....SAN DIEGO FORMATION (Conglomerate)
- Tmv.....MISSION VALLEY FORMATION
-APPROX. LOCATION OF GEOLOGIC CONTACT
(Queried Where Uncertain)
- LD-2.....APPROX. LOCATION OF BORING
- T-24.....APPROX. LOCATION OF TRENCH
- A-2.....APPROX. LOCATION OF INFILTRATION TEST
- (5).....APPROX. DEPTH OF REMEDIAL GRADING (In Feet, MSL)
-APPROX. LOCATION OF GEOLOGIC CROSS SECTION

- @7' = 10-16"
- @15' = 16"
- @24' = 26"
- @29' = 21"
- @36' = 20"
- @58' = 11"

- @19' = 29"
- @30' = 11"
- @33' = 14"
- @39' = 16"
- @59' = 0-14"
- @61' = 10"
- @65' = 13"

GEOLOGIC MAP
NAKANO
CHULA VISTA, CALIFORNIA

GEOCON INCORPORATED GEOTECHNICAL ■ ENVIRONMENTAL ■ MATERIALS 6960 FLANDERS DRIVE ■ SAN DIEGO, CALIFORNIA 92121 ■ 2974 PHONE 658 558-6700 ■ FAX 658 558-6197	SCALE 1" = 60' PROJECT NO. 07516 - 42 - 02 SHEET 1 OF 1	DATE 02 - 09 - 2022 FIGURE 1
--	---	---------------------------------

Plotter: 02/10/2022 7:44AM | By: ALVIN LARILLON | File Location: W:_GEO\TECH\075000\075000\07516-42-02\0222-02-09\07516-42-02_Geo Map_30.dwg



Aardvark Permeameter Data Analysis

Project Name: Nakano
 Project Number: 07516-42-02
 Test Number: A-1

Date: 12/20/2019
 By: BRK


Borehole Diameter, d (in.): 8.00
 Borehole Depth, H (in.): 68.00
 Distance Between Reservoir & Top of Borehole (in.): 26.00
 Height APM Raised from Bottom (in.): 2.00
 Pressure Reducer Used: No

Ref. EL (feet, MSL): 102.0
 Bottom EL (feet, MSL): 96.3

Distance Between Reservoir and APM Float, D (in.): 84.75
 Head Height Measured, h (in.): 5.50

Reading	Time Elapsed (min)	Water Weight Consumed (lbs)	Water Volume Consumed (in ³)	Q (in ³ /min)
1	0.00	0.000	0.00	0.00
2	5.00	11.530	319.29	63.858
3	5.00	1.665	46.11	9.222
4	5.00	0.155	4.29	0.858
5	5.00	0.045	1.25	0.249
6	5.00	0.045	1.25	0.249
7	5.00	0.035	0.97	0.194
8	5.00	0.035	0.97	0.194
9	10.00	0.045	1.25	0.125
10	10.00	0.045	1.25	0.125
11	10.00	0.030	0.83	0.083
12	10.00	0.025	0.69	0.069
13	10.00	0.020	0.55	0.055
14	10.00	0.015	0.42	0.042
15	10.00	0.015	0.42	0.042

Steady Flow Rate, Q (in³/min): 0.046



Soil Matric Flux Potential, ϕ_m

$\phi_m =$ 0.00060 in²/min

Field-Saturated Hydraulic Conductivity (Infiltration Rate)

$K_{sat} =$ 6.07E-05 in/min 0.004 in/hr



Borehole Infiltration Test


Project Name: Nakano
 Project Number: 07516-42-02
 Test Number: A-2

Date: 12/20/2019
 By: BRK
 Ref. EL (feet, MSL): 100.0
 Bottom EL (feet, MSL): 92.3

Borehole Diameter, d (in.): 8.00
 Borehole Depth, H (in.): 92.00
 Distance Between Reservoir & Top of Borehole (in.): 26.00
 Height APM Raised from Bottom (in.): 2.00
 Pressure Reducer Used: No

Distance Between Reservoir and APM Float, D (in.): 108.75
 Head Height Measured, h (in.): 4.75

Reading	Time Elapsed (min)	Water Weight Consummed (lbs)	Water Volume Consummed (in ³)	Q (in ³ /min)
1	0.00	0.000	0.00	0.00
2	5.00	11.255	311.68	62.335
3	5.00	1.095	30.32	6.065
4	5.00	0.315	8.72	1.745
5	5.00	0.995	27.55	5.511
6	5.00	1.075	29.77	5.954
7	5.00	0.985	27.28	5.455
8	5.00	0.915	25.34	5.068
9	5.00	0.890	24.65	4.929
10	5.00	0.845	23.40	4.680
11	5.00	0.770	21.32	4.265
12	5.00	0.740	20.49	4.098
13	5.00	0.695	19.25	3.849
14	5.00	0.665	18.42	3.683
15	5.00	0.655	18.14	3.628
16	6.00	0.750	20.77	3.462
17	4.00	0.440	12.18	3.046
18	5.00	0.565	15.65	3.129
19	5.00	0.535	14.82	2.963
20	5.00	0.530	14.68	2.935
21	5.00	0.510	14.12	2.825
22	6.00	0.610	16.89	2.815
23	4.00	0.405	11.22	2.804
Steady Flow Rate, Q (in ³ /min):				2.815



Soil Matric Flux Potential, ϕ_m

$\phi_m =$ 0.0538 in²/min

Field-Saturated Hydraulic Conductivity (Infiltration Rate)

$K_{sat} =$ 1.37E-03 in/min 0.082 in/hr

Appendix C: Geotechnical and Groundwater Investigation Requirements

Worksheet C.4-1: Categorization of Infiltration Feasibility Condition Based on Geotechnical Conditions⁹

Categorization of Infiltration Feasibility Condition based on Geotechnical Conditions	Worksheet C.4-1: Form I-8A ¹⁰
Part 1 - Full Infiltration Feasibility Screening Criteria	
DMA(s) Being Analyzed:	Project Phase:
Entire Site	Design
Criteria 1: Infiltration Rate Screening	
1A	<p>Is the mapped hydrologic soil group according to the NRCS Web Soil Survey or UC Davis Soil Web Mapper Type A or B and corroborated by available site soil data¹¹?</p> <p><input type="checkbox"/> Yes; the DMA may feasibly support full infiltration. Answer “Yes” to Criteria 1 Result or continue to Step 1B if the applicant elects to perform infiltration testing.</p> <p><input type="checkbox"/> No; the mapped soil types are A or B but is not corroborated by available site soil data (continue to Step 1B).</p> <p><input checked="" type="checkbox"/> No; the mapped soil types are C, D, or “urban/unclassified” and is corroborated by available site soil data. Answer “No” to Criteria 1 Result.</p> <p><input type="checkbox"/> No; the mapped soil types are C, D, or “urban/unclassified” but is not corroborated by available site soil data (continue to Step 1B).</p>
1B	<p>Is the reliable infiltration rate calculated using planning phase methods from Table D.3-1?</p> <p><input type="checkbox"/> Yes; Continue to Step 1C.</p> <p><input type="checkbox"/> No; Skip to Step 1D.</p>
1C	<p>Is the reliable infiltration rate calculated using planning phase methods from Table D.3-1 greater than 0.5 inches per hour?</p> <p><input type="checkbox"/> Yes; the DMA may feasibly support full infiltration. Answer “Yes” to Criteria 1 Result.</p> <p><input type="checkbox"/> No; full infiltration is not required. Answer “No” to Criteria 1 Result.</p>
1D	<p>Infiltration Testing Method. Is the selected infiltration testing method suitable during the design phase (see Appendix D.3)? Note: Alternative testing standards may be allowed with appropriate rationales and documentation.</p> <p><input type="checkbox"/> Yes; continue to Step 1E.</p> <p><input type="checkbox"/> No; select an appropriate infiltration testing method.</p>

⁹ Note that it is not required to investigate each and every criterion in the worksheet, a single “no” answer in Part 1, Part 2, Part 3, or Part 4 determines a full, partial, or no infiltration condition.

¹⁰ This form must be completed each time there is a change to the site layout that would affect the infiltration feasibility condition. Previously completed forms shall be retained to document the evolution of the site stormwater design.

¹¹ Available data includes site-specific sampling or observation of soil types or texture classes, such as obtained from borings or test pits necessary to support other design elements.



Appendix C: Geotechnical and Groundwater Investigation Requirements

Categorization of Infiltration Feasibility Condition based on Geotechnical Conditions	Worksheet C.4-1: Form I-8A ¹⁰
1E	<p>Number of Percolation/Infiltration Tests. Does the infiltration testing method performed satisfy the minimum number of tests specified in Table D.3-2?</p> <p><input type="checkbox"/> Yes; continue to Step 1F.</p> <p><input type="checkbox"/> No; conduct appropriate number of tests.</p>
1F	<p>Factor of Safety. Is the suitable Factor of Safety selected for full infiltration design? See guidance in D.5; Tables D.5-1 and D.5-2; and Worksheet D.5-1 (Form I-9).</p> <p><input type="checkbox"/> Yes; continue to Step 1G.</p> <p><input type="checkbox"/> No; select appropriate factor of safety.</p>
1G	<p>Full Infiltration Feasibility. Is the average measured infiltration rate divided by the Factor of Safety greater than 0.5 inches per hour?</p> <p><input type="checkbox"/> Yes; answer “Yes” to Criteria 1 Result.</p> <p><input type="checkbox"/> No; answer “No” to Criteria 1 Result.</p>
Criteria 1 Result	<p>Is the estimated reliable infiltration rate greater than 0.5 inches per hour within the DMA where runoff can reasonably be routed to a BMP?</p> <p><input type="checkbox"/> Yes; the DMA may feasibly support full infiltration. Continue to Criteria 2.</p> <p><input checked="" type="checkbox"/> No; full infiltration is not required. Skip to Part 1 Result.</p>
<p>We performed two borehole infiltration tests in the area of the proposed basin. The test results are summarized below. The rates are not high enough to support full or partial infiltration.</p> <p>A-1: 0.004 in/hr (0.002 in/hr using a factor of 2 for feasibility determination)</p> <p>A-2: 0.082 in/hr (0.041 in/hr using a factor of 2 for feasibility determination)</p>	



Appendix C: Geotechnical and Groundwater Investigation Requirements

Categorization of Infiltration Feasibility Condition based on Geotechnical Conditions		Worksheet C.4-1: Form I-8A ¹⁰	
Criteria 2: Geologic/Geotechnical Screening			
2A	<p>If all questions in Step 2A are answered “Yes,” continue to Step 2B.</p> <p>For any “No” answer in Step 2A answer “No” to Criteria 2, and submit an “Infiltration Feasibility Condition Letter” that meets the requirements in Appendix C.1.1. The geologic/geotechnical analyses listed in Appendix C.2.1 do not apply to the DMA because one of the following setbacks cannot be avoided and therefore result in the DMA being in a no infiltration condition. The setbacks must be the closest horizontal radial distance from the surface edge (at the overflow elevation) of the BMP.</p>		
2A-1	Can the proposed full infiltration BMP(s) avoid areas with existing fill materials greater than 5 feet thick below the infiltrating surface?	<input type="checkbox"/> Yes	<input type="checkbox"/> No
2A-2	Can the proposed full infiltration BMP(s) avoid placement within 10 feet of existing underground utilities, structures, or retaining walls?	<input type="checkbox"/> Yes	<input type="checkbox"/> No
2A-3	Can the proposed full infiltration BMP(s) avoid placement within 50 feet of a natural slope (>25%) or within a distance of 1.5H from fill slopes where H is the height of the fill slope?	<input type="checkbox"/> Yes	<input type="checkbox"/> No
2B	<p>When full infiltration is determined to be feasible, a geotechnical investigation report must be prepared that considers the relevant factors identified in Appendix C.2.1.</p> <p>If all questions in Step 2B are answered “Yes,” then answer “Yes” to Criteria 2 Result. If there are “No” answers continue to Step 2C.</p>		
2B-1	<p>Hydroconsolidation. Analyze hydroconsolidation potential per approved ASTM standard due to a proposed full infiltration BMP.</p> <p>Can full infiltration BMPs be proposed within the DMA without increasing hydroconsolidation risks?</p>	<input type="checkbox"/> Yes	<input type="checkbox"/> No
2B-2	<p>Expansive Soils. Identify expansive soils (soils with an expansion index greater than 20) and the extent of such soils due to proposed full infiltration BMPs.</p> <p>Can full infiltration BMPs be proposed within the DMA without increasing expansive soil risks?</p>	<input type="checkbox"/> Yes	<input type="checkbox"/> No



Appendix C: Geotechnical and Groundwater Investigation Requirements

Categorization of Infiltration Feasibility Condition based on Geotechnical Conditions		Worksheet C.4-1: Form I-8A ¹⁰	
2B-3	<p>Liquefaction. If applicable, identify mapped liquefaction areas. Evaluate liquefaction hazards in accordance with Section 6.4.2 of the City of San Diego's Guidelines for Geotechnical Reports (2011 or most recent edition). Liquefaction hazard assessment shall take into account any increase in groundwater elevation or groundwater mounding that could occur as a result of proposed infiltration or percolation facilities.</p> <p>Can full infiltration BMPs be proposed within the DMA without increasing liquefaction risks?</p>	<input type="checkbox"/> Yes	<input type="checkbox"/> No
2B-4	<p>Slope Stability. If applicable, perform a slope stability analysis in accordance with the ASCE and Southern California Earthquake Center (2002) Recommended Procedures for Implementation of DMG Special Publication 117, Guidelines for Analyzing and Mitigating Landslide Hazards in California to determine minimum slope setbacks for full infiltration BMPs. See the City of San Diego's Guidelines for Geotechnical Reports (2011) to determine which type of slope stability analysis is required.</p> <p>Can full infiltration BMPs be proposed within the DMA without increasing slope stability risks?</p>	<input type="checkbox"/> Yes	<input type="checkbox"/> No
2B-5	<p>Other Geotechnical Hazards. Identify site-specific geotechnical hazards not already mentioned (refer to Appendix C.2.1).</p> <p>Can full infiltration BMPs be proposed within the DMA without increasing risk of geologic or geotechnical hazards not already mentioned?</p>	<input type="checkbox"/> Yes	<input type="checkbox"/> No
2B-6	<p>Setbacks. Establish setbacks from underground utilities, structures, and/or retaining walls. Reference applicable ASTM or other recognized standard in the geotechnical report.</p> <p>Can full infiltration BMPs be proposed within the DMA using established setbacks from underground utilities, structures, and/or retaining walls?</p>	<input type="checkbox"/> Yes	<input type="checkbox"/> No

Appendix C: Geotechnical and Groundwater Investigation Requirements

Categorization of Infiltration Feasibility Condition based on Geotechnical Conditions		Worksheet C.4-1: Form I-8A ¹⁰	
2C	<p>Mitigation Measures. Propose mitigation measures for each geologic/geotechnical hazard identified in Step 2B. Provide a discussion of geologic/geotechnical hazards that would prevent full infiltration BMPs that cannot be reasonably mitigated in the geotechnical report. See Appendix C.2.1.8 for a list of typically reasonable and typically unreasonable mitigation measures.</p> <p>Can mitigation measures be proposed to allow for full infiltration BMPs? If the question in Step 2 is answered “Yes,” then answer “Yes” to Criteria 2 Result. If the question in Step 2C is answered “No,” then answer “No” to Criteria 2 Result.</p>	<input type="checkbox"/> Yes	<input type="checkbox"/> No
Criteria 2 Result	Can infiltration greater than 0.5 inches per hour be allowed without increasing risk of geologic or geotechnical hazards that cannot be reasonably mitigated to an acceptable level?	<input type="checkbox"/> Yes	<input type="checkbox"/> No
Summarize findings and basis; provide references to related reports or exhibits.			
Part 1 Result – Full Infiltration Geotechnical Screening ¹²		Result	
<p>If answers to both Criteria 1 and Criteria 2 are “Yes”, a full infiltration design is potentially feasible based on Geotechnical conditions only.</p> <p>If either answer to Criteria 1 or Criteria 2 is “No”, a full infiltration design is not required.</p>		<p><input type="checkbox"/> Full infiltration Condition</p> <p><input checked="" type="checkbox"/> Complete Part 2</p>	

¹² To be completed using gathered site information and best professional judgement considering the definition of MEP in the MS4 Permit. Additional testing and/or studies may be required by City Engineer to substantiate findings.



Appendix C: Geotechnical and Groundwater Investigation Requirements

Categorization of Infiltration Feasibility Condition based on Geotechnical Conditions	Worksheet C.4-1: Form I-8A ¹⁰
Part 2 – Partial vs. No Infiltration Feasibility Screening Criteria	
DMA(s) Being Analyzed:	Project Phase:
Entire Site	Design
Criteria 3 : Infiltration Rate Screening	
3A	<p>NRCS Type C, D, or “urban/unclassified”: Is the mapped hydrologic soil group according to the NRCS Web Soil Survey or UC Davis Soil Web Mapper is Type C, D, or “urban/unclassified” and corroborated by available site soil data?</p> <p><input type="checkbox"/> Yes; the site is mapped as C soils and a reliable infiltration rate of 0.15 in/hr. is used to size partial infiltration BMPS. Answer “Yes” to Criteria 3 Result.</p> <p><input type="checkbox"/> Yes; the site is mapped as D soils or “urban/unclassified” and a reliable infiltration rate of 0.05 in/hr. is used to size partial infiltration BMPS. Answer “Yes” to Criteria 3 Result.</p> <p><input checked="" type="checkbox"/> No; infiltration testing is conducted (refer to Table D.3-1), continue to Step 3B.</p>
3B	<p>Infiltration Testing Result: Is the reliable infiltration rate (i.e. average measured infiltration rate/2) greater than 0.05 in/hr. and less than or equal to 0.5 in/hr?</p> <p><input type="checkbox"/> Yes; the site may support partial infiltration. Answer “Yes” to Criteria 3 Result.</p> <p><input checked="" type="checkbox"/> No; the reliable infiltration rate (i.e. average measured rate/2) is less than 0.05 in/hr., partial infiltration is not required. Answer “No” to Criteria 3 Result.</p>
Criteria 3 Result	<p>Is the estimated reliable infiltration rate (i.e., average measured infiltration rate/2) greater than or equal to 0.05 inches/hour and less than or equal to 0.5 inches/hour at any location within each DMA where runoff can reasonably be routed to a BMP?</p> <p><input type="checkbox"/> Yes; Continue to Criteria 4.</p> <p><input checked="" type="checkbox"/> No; Skip to Part 2 Result.</p>
<p>We performed two borehole infiltration tests in the area of the proposed basin. The test results are summarized below. The rates are not high enough to support full or partial infiltration.</p> <p>A-1: 0.004 in/hr (0.002 in/hr using a factor of 2 for feasibility determination)</p> <p>A-2: 0.082 in/hr (0.041 in/hr using a factor of 2 for feasibility determination)</p>	



Appendix C: Geotechnical and Groundwater Investigation Requirements

Categorization of Infiltration Feasibility Condition based on Geotechnical Conditions		Worksheet C.4-1: Form I-8A ¹⁰	
Criteria 4: Geologic/Geotechnical Screening			
4A	<p>If all questions in Step 4A are answered “Yes,” continue to Step 2B.</p> <p>For any “No” answer in Step 4A answer “No” to Criteria 4 Result, and submit an “Infiltration Feasibility Condition Letter” that meets the requirements in Appendix C.1.1. The geologic/geotechnical analyses listed in Appendix C.2.1 do not apply to the DMA because one of the following setbacks cannot be avoided and therefore result in the DMA being in a no infiltration condition. The setbacks must be the closest horizontal radial distance from the surface edge (at the overflow elevation) of the BMP.</p>		
4A-1	Can the proposed partial infiltration BMP(s) avoid areas with existing fill materials greater than 5 feet thick?	<input type="checkbox"/> Yes	<input type="checkbox"/> No
4A-2	Can the proposed partial infiltration BMP(s) avoid placement within 10 feet of existing underground utilities, structures, or retaining walls?	<input type="checkbox"/> Yes	<input type="checkbox"/> No
4A-3	Can the proposed partial infiltration BMP(s) avoid placement within 50 feet of a natural slope (>25%) or within a distance of 1.5H from fill slopes where H is the height of the fill slope?	<input type="checkbox"/> Yes	<input type="checkbox"/> No
4B	<p>When full infiltration is determined to be feasible, a geotechnical investigation report must be prepared that considers the relevant factors identified in Appendix C.2.1</p> <p>If all questions in Step 4B are answered “Yes,” then answer “Yes” to Criteria 4 Result. If there are any “No” answers continue to Step 4C.</p>		
4B-1	<p>Hydroconsolidation. Analyze hydroconsolidation potential per approved ASTM standard due to a proposed full infiltration BMP.</p> <p>Can partial infiltration BMPs be proposed within the DMA without increasing hydroconsolidation risks?</p>	<input type="checkbox"/> Yes	<input type="checkbox"/> No
4B-2	<p>Expansive Soils. Identify expansive soils (soils with an expansion index greater than 20) and the extent of such soils due to proposed full infiltration BMPs.</p> <p>Can partial infiltration BMPs be proposed within the DMA without increasing expansive soil risks?</p>	<input type="checkbox"/> Yes	<input type="checkbox"/> No
4B-3	<p>Liquefaction. If applicable, identify mapped liquefaction areas. Evaluate liquefaction hazards in accordance with Section 6.4.2 of the City of San Diego's Guidelines for Geotechnical Reports (2011). Liquefaction hazard assessment shall take into account any increase in groundwater elevation or groundwater mounding that could occur as a result of proposed infiltration or percolation facilities.</p> <p>Can partial infiltration BMPs be proposed within the DMA without increasing liquefaction risks?</p>	<input type="checkbox"/> Yes	<input type="checkbox"/> No



Appendix C: Geotechnical and Groundwater Investigation Requirements

Categorization of Infiltration Feasibility Condition based on Geotechnical Conditions		Worksheet C.4-1: Form I-8A ¹⁰	
4B-4	<p>Slope Stability. If applicable, perform a slope stability analysis in accordance with the ASCE and Southern California Earthquake Center (2002) Recommended Procedures for Implementation of DMG Special Publication 117, Guidelines for Analyzing and Mitigating Landslide Hazards in California to determine minimum slope setbacks for full infiltration BMPs. See the City of San Diego's Guidelines for Geotechnical Reports (2011) to determine which type of slope stability analysis is required.</p> <p>Can partial infiltration BMPs be proposed within the DMA without increasing slope stability risks?</p>	<input type="checkbox"/> Yes	<input type="checkbox"/> No
4B-5	<p>Other Geotechnical Hazards. Identify site-specific geotechnical hazards not already mentioned (refer to Appendix C.2.1).</p> <p>Can partial infiltration BMPs be proposed within the DMA without increasing risk of geologic or geotechnical hazards not already mentioned?</p>	<input type="checkbox"/> Yes	<input type="checkbox"/> No
4B-6	<p>Setbacks. Establish setbacks from underground utilities, structures, and/or retaining walls. Reference applicable ASTM or other recognized standard in the geotechnical report.</p> <p>Can partial infiltration BMPs be proposed within the DMA using recommended setbacks from underground utilities, structures, and/or retaining walls?</p>	<input type="checkbox"/> Yes	<input type="checkbox"/> No
4C	<p>Mitigation Measures. Propose mitigation measures for each geologic/geotechnical hazard identified in Step 4B. Provide a discussion on geologic/geotechnical hazards that would prevent partial infiltration BMPs that cannot be reasonably mitigated in the geotechnical report. See Appendix C.2.1.8 for a list of typically reasonable and typically unreasonable mitigation measures.</p> <p>Can mitigation measures be proposed to allow for partial infiltration BMPs? If the question in Step 4C is answered "Yes," then answer "Yes" to Criteria 4 Result. If the question in Step 4C is answered "No," then answer "No" to Criteria 4 Result.</p>	<input type="checkbox"/> Yes	<input type="checkbox"/> No
Criteria 4 Result	<p>Can infiltration of greater than or equal to 0.05 inches/hour and less than or equal to 0.5 inches/hour be allowed without increasing the risk of geologic or geotechnical hazards that cannot be reasonably mitigated to an acceptable level?</p>	<input type="checkbox"/> Yes	<input type="checkbox"/> No

Appendix C: Geotechnical and Groundwater Investigation Requirements

Categorization of Infiltration Feasibility Condition based on Geotechnical Conditions	Worksheet C.4-1: Form I-8A ¹⁰
<p>Summarize findings and basis; provide references to related reports or exhibits.</p>	
Part 2 – Partial Infiltration Geotechnical Screening Result ¹³	Result
<p>If answers to both Criteria 3 and Criteria 4 are “Yes”, a partial infiltration design is potentially feasible based on geotechnical conditions only.</p> <p>If answers to either Criteria 3 or Criteria 4 is “No”, then infiltration of any volume is considered to be infeasible within the site.</p>	<p><input type="checkbox"/> Partial Infiltration Condition</p> <p><input checked="" type="checkbox"/> No Infiltration Condition</p>

¹³ To be completed using gathered site information and best professional judgement considering the definition of MEP in the MS4 Permit. Additional testing and/or studies may be required by City Engineer to substantiate findings.



City of Chula Vista Infiltration Feasibility Letter
(For Review by City of Chula Vista)

APPENDIX C

STORM WATER MANAGEMENT

We understand storm water management devices are being proposed in accordance with the current Storm Water Standards (SWS). If not properly constructed, there is a potential for distress to improvements and properties located hydrologically down gradient or adjacent to these devices. Factors such as the amount of water to be detained, its residence time, and soil permeability have an important effect on seepage transmission and the potential adverse impacts that may occur if the storm water management features are not properly designed and constructed. We have not performed a hydrogeological study at the site. If infiltration of storm water runoff occurs, downstream properties and improvements may be subjected to seeps, springs, slope instability, raised groundwater, movement of foundations and slabs, or other undesirable impacts as a result of water infiltration.

Hydrologic Soil Group

The United States Department of Agriculture (USDA), Natural Resources Conservation Services, possesses general information regarding the existing soil conditions for areas within the United States. The USDA website also provides the Hydrologic Soil Group. Table C-1 presents the descriptions of the hydrologic soil groups. In addition, the USDA website also provides an estimated saturated hydraulic conductivity for the existing soil.

**TABLE C-1
HYDROLOGIC SOIL GROUP DEFINITIONS**

Soil Group	Soil Group Definition
A	Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.
B	Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.
C	Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.
D	Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

The property is underlain by undocumented fill, surficial deposits such as topsoil, colluvium and alluvium, Terrace Deposits, and the Mission Valley Formation. Table C-2 presents the information from the USDA website for the subject property.

**TABLE C-2
USDA WEB SOIL SURVEY – HYDROLOGIC SOIL GROUP**

Map Unit Name	Map Unit Symbol	Approximate Percentage of Property	Hydrologic Soil Group
Olivenhain cobbly loam, 9 to 30 percent slopes	OhE	5.0	D
Riverwash	Rm	18.5	D
Salinas clay loam, 0 to 2 percent slopes, warm MAAT, MLRA 19	SbA	76.6	C

Infiltration Testing

We performed two borehole infiltration tests at the locations shown on Figure 2. The tests were performed in 8-inch-diameter, drilled borings. Table C-3 presents the results of the testing. The calculation sheets are provided herein.

We used the guidelines presented in the Riverside County Low Impact Development BMP Design Handbook. Based on this widely accepted guideline, the saturated hydraulic conductivity (Ksat) is equivalent to the infiltration rate. Therefore, the Ksat value determined from our testing is assumed to be the unfactored infiltration rate.

**TABLE C-3
UNFACTORED, FIELD-SATURATED, INFILTRATION TEST RESULTS**

Test No.	Depth (inches)	Geologic Unit	Field Infiltration Rate, I (in/hr)	Factored* Field Infiltration Rate, I (in/hr)
A-1	68	Qudf	0.004	0.002
A-2	92	Qudf	0.244	0.12

* Factor of Safety of 2.0 for feasibility determination.

STORM WATER MANAGEMENT CONCLUSIONS

Soil Types

Undocumented Fill (Qpudf) – We encountered undocumented fill up to 18 feet thick at the north end of the property. The undocumented fill within structural improvement areas will be removed and replaced with compacted fill. Water that is allowed to migrate into the undocumented fill or

compacted fill will cause settlement. Therefore, full and partial infiltration should be considered infeasible within fill.

Topsoil (Unmapped) – We encountered topsoil varying between 0.5 and 3 feet thick across the site. Topsoil within structural improvement areas will be removed and replaced with compacted fill. Water that is allowed to migrate into the topsoil will cause settlement. Therefore, full and partial infiltration should be considered infeasible within topsoil.

Colluvium (Qcol) – We encountered colluvium on the north-facing slopes at the south property boundary, varying between 0.5 and 5 feet thick. Colluvium within structural improvement areas will be removed and replaced with compacted fill. Water that is allowed to migrate into colluvium will cause settlement. Therefore, full and partial infiltration should be considered infeasible within areas underlain by colluvium.

Alluvium (Qal) – Alluvium is present in a drainage located at the southeast corner of the property. Alluvium was also encountered in Trench T-20 beneath undocumented fill at the north end of the site. Alluvium within structural improvement areas will be removed and replaced with compacted fill. Water that is allowed to migrate into alluvium will cause settlement. Therefore, full and partial infiltration should be considered infeasible within areas underlain by alluvium.

Terrace Deposits (Qt) – We encountered Terrace Deposits underlying most of the site below the artificial fill, topsoil, and alluvium. Infiltration into Terrace Deposits may be possible.

Mission Valley Formation (Tmv) – We encountered age Mission Valley in slopes along the southern portion of the site. Mission Valley Formation may also be present underlying the Terrace Deposits in the central portion of the site. Infiltration into the Mission Valley Formation is not feasible due to low infiltration characteristics.

Groundwater Elevation

Groundwater was not encountered in our borings or trenches to a depths explored. Infiltration should not impact groundwater.

Existing Utilities

Existing utilities are located on the north side of the property and along the west and east property margins. Infiltration near these utilities is considered infeasible. Otherwise, infiltration due to utility concerns would be feasible.

Soil or Groundwater Contamination

We are unaware of contaminated soil or groundwater on the property. Therefore, full and partial infiltration associated with this risk is considered feasible.

Slopes

There are no existing slopes that would be impacted by infiltration. There are proposed fill slopes where infiltration adjacent to the slopes is not feasible.

Infiltration Rates

Our test results indicated slow infiltration rates. The factored rates were 0.002 and 0.12 inches per hour. The infiltration rates are not high enough to support full or partial infiltration in the area of the proposed BMP.

Storm Water Management Devices

Liners should be incorporated in the proposed basin. The liner should be impermeable (e.g. High-density polyethylene, HDPE, with a thickness of about 30 mil or equivalent Polyvinyl Chloride, PVC). Penetration of the liners should be properly sealed. The devices should also be installed in accordance with the manufacturer's recommendations. Overflow protection devices should also be incorporated into the design and construction of the storm water management device.

Storm Water Standard Worksheets

The SWS requests the geotechnical engineer complete the *Categorization of Infiltration Feasibility Condition* (Worksheet C.4-1) worksheet information to help evaluate the potential for infiltration on the property. The attached Worksheet C.4-1 presents the completed information for the submittal process.

The regional storm water standards also have a worksheet (Worksheet Form D.5-1) that helps the project civil engineer estimate the factor of safety based on several factors. Table C-4 describes the suitability assessment input parameters related to the geotechnical engineering aspects for the factor of safety determination.

**TABLE C-4
SUITABILITY ASSESSMENT RELATED CONSIDERATIONS FOR INFILTRATION FACILITY
SAFETY FACTORS**

Consideration	High Concern – 3 Points	Medium Concern – 2 Points	Low Concern – 1 Point
Assessment Methods	Use of soil survey maps or simple texture analysis to estimate short-term infiltration rates. Use of well permeameter or borehole methods without accompanying continuous boring log. Relatively sparse testing with direct infiltration methods	Use of well permeameter or borehole methods with accompanying continuous boring log. Direct measurement of infiltration area with localized infiltration measurement methods (e.g., Infiltrometer). Moderate spatial resolution	Direct measurement with localized (i.e. small-scale) infiltration testing methods at relatively high resolution or use of extensive test pit infiltration measurement methods.
Predominant Soil Texture	Silty and clayey soils with significant fines	Loamy soils	Granular to slightly loamy soils
Site Soil Variability	Highly variable soils indicated from site assessment or unknown variability	Soil boring/test pits indicate moderately homogenous soils	Soil boring/test pits indicate relatively homogenous soils
Depth to Groundwater/ Impervious Layer	<5 feet below facility bottom	5-15 feet below facility bottom	>15 feet below facility bottom

Table C-5 presents the estimated factor values for the evaluation of the factor of safety. This table only presents the suitability assessment safety factor (Part A) of the worksheet. The project civil engineer should evaluate the safety factor for design (Part B) and use the combined safety factor for the design infiltration rate.

**TABLE C-5
FACTOR OF SAFETY WORKSHEET D.5-1 DESIGN VALUES¹**

Suitability Assessment Factor Category	Assigned Weight (w)	Factor Value (v)	Product (p = w x v)
Assessment Methods	0.25	2	0.50
Predominant Soil Texture	0.25	3	0.75
Site Soil Variability	0.25	2	0.50
Depth to Groundwater/Impervious Layer	0.25	1	0.25
Suitability Assessment Safety Factor, $S_A = \Sigma p$			2.0

¹ The project civil engineer should complete Worksheet D.5-1 using the data on this table. Additional information is required to evaluate the design factor of safety.

CONCLUSIONS

Our results indicate the site has relatively slow infiltration characteristics. Because of the site conditions, it is our opinion that there is a potential for lateral water migration. Undocumented and previously placed fill exists on the property and has a high potential for adverse settlement when wetted. It is our opinion that full or partial infiltration is infeasible on this site. Our evaluation included the soil and geologic conditions, estimated settlement and volume change of the underlying soil, slope stability, utility considerations, groundwater mounding, retaining walls, foundations and existing groundwater elevations.



Aardvark Permeameter Data Analysis

Project Name: Nakano
 Project Number: 07516-42-02
 Test Number: A-1

Date: 12/20/2019
 By: BRK


Borehole Diameter, d (in.): 8.00
 Borehole Depth, H (in.): 68.00
 Distance Between Reservoir & Top of Borehole (in.): 26.00
 Height APM Raised from Bottom (in.): 2.00
 Pressure Reducer Used: No

Ref. EL (feet, MSL): 102.0
 Bottom EL (feet, MSL): 96.3

Distance Between Reservoir and APM Float, D (in.): 84.75
 Head Height Measured, h (in.): 5.50

Reading	Time Elapsed (min)	Water Weight Consumed (lbs)	Water Volume Consumed (in ³)	Q (in ³ /min)
1	0.00	0.000	0.00	0.00
2	5.00	11.530	319.29	63.858
3	5.00	1.665	46.11	9.222
4	5.00	0.155	4.29	0.858
5	5.00	0.045	1.25	0.249
6	5.00	0.045	1.25	0.249
7	5.00	0.035	0.97	0.194
8	5.00	0.035	0.97	0.194
9	10.00	0.045	1.25	0.125
10	10.00	0.045	1.25	0.125
11	10.00	0.030	0.83	0.083
12	10.00	0.025	0.69	0.069
13	10.00	0.020	0.55	0.055
14	10.00	0.015	0.42	0.042
15	10.00	0.015	0.42	0.042

Steady Flow Rate, Q (in³/min): 0.046



Soil Matric Flux Potential, ϕ_m

$\phi_m =$ 0.00060 in²/min

Field-Saturated Hydraulic Conductivity (Infiltration Rate)

$K_{sat} =$ 6.07E-05 in/min 0.004 in/hr



Borehole Infiltration Test

Project Name: Nakano
 Project Number: 07516-42-02
 Test Number: A-2


Date: 12/20/2019
 By: BRK
 Ref. EL (feet, MSL): 100.0
 Bottom EL (feet, MSL): 92.3

Borehole Diameter, d (in.): 8.00
 Borehole Depth, H (in.): 92.00
 Distance Between Reservoir & Top of Borehole (in.): 26.00
 Height APM Raised from Bottom (in.): 2.00
 Pressure Reducer Used: No

Distance Between Reservoir and APM Float, D (in.): 108.75
 Head Height Measured, h (in.): 4.75

Reading	Time Elapsed (min)	Water Weight Consummed (lbs)	Water Volume Consummed (in ³)	Q (in ³ /min)
1	0.00	0.000	0.00	0.00
2	5.00	11.255	311.68	62.335
3	5.00	1.095	30.32	6.065
4	5.00	0.315	8.72	1.745
5	5.00	0.995	27.55	5.511
6	5.00	1.075	29.77	5.954
7	5.00	0.985	27.28	5.455
8	5.00	0.915	25.34	5.068
9	5.00	0.890	24.65	4.929
10	5.00	0.845	23.40	4.680
11	5.00	0.770	21.32	4.265
12	5.00	0.740	20.49	4.098
13	5.00	0.695	19.25	3.849
14	5.00	0.665	18.42	3.683
15	5.00	0.655	18.14	3.628
16	6.00	0.750	20.77	3.462
17	4.00	0.440	12.18	3.046
18	5.00	0.565	15.65	3.129
19	5.00	0.535	14.82	2.963
20	5.00	0.530	14.68	2.935
21	5.00	0.510	14.12	2.825
22	6.00	0.610	16.89	2.815
23	4.00	0.405	11.22	2.804

Steady Flow Rate, Q (in³/min): 2.815



Soil Matric Flux Potential, ϕ_m

$\phi_m =$ 0.0538 in²/min

Field-Saturated Hydraulic Conductivity (Infiltration Rate)

$K_{sat} =$ 1.37E-03 in/min 0.082 in/hr

Project Name: _____

Categorization of Infiltration Feasibility Condition based on Geotechnical Conditions		Form I-8A ¹ (Worksheet C.4-1)
Part 1 - Full Infiltration Feasibility Screening Criteria		
DMA(s) Being Analyzed:		Project Phase:
Entire Site		Planning
Criteria 1: Infiltration Rate Screening		
1A	Is the mapped hydrologic soil group according to the NRCS Web Soil Survey or UC Davis Soil Web Mapper Type A or B and corroborated by available site soil data ² ? <input type="checkbox"/> Yes; the DMA may feasibly support full infiltration. Answer “Yes” to Criteria 1 Result or continue to Step 1B if the applicant elects to perform infiltration testing. <input type="checkbox"/> No; the mapped soil types are A or B but is not corroborated by available site soil data (continue to Step 1B). <input checked="" type="checkbox"/> No; the mapped soil types are C, D, or “urban/unclassified” and is corroborated by available site soil data. Answer “No” to Criteria 1 Result. <input type="checkbox"/> No; the mapped soil types are C, D, or “urban/unclassified” but is not corroborated by available site soil data (continue to Step 1B).	
1B	Is the reliable infiltration rate calculated using planning phase methods from Table D.3-1? <input checked="" type="checkbox"/> Yes; Continue to Step 1C. <input type="checkbox"/> No; Skip to Step 1D.	
1C	Is the reliable infiltration rate calculated using planning phase methods from Table D.3-1 greater than 0.5 inches per hour? <input type="checkbox"/> Yes; the DMA may feasibly support full infiltration. Answer “Yes” to Criteria 1 Result. <input checked="" type="checkbox"/> No; full infiltration is not required. Answer “No” to Criteria 1 Result.	
1D	Infiltration Testing Method. Is the selected infiltration testing method suitable during the design phase (see Appendix D.3)? Note: Alternative testing standards may be allowed with appropriate rationales and documentation. <input type="checkbox"/> Yes; continue to Step 1E. <input type="checkbox"/> No; select an appropriate infiltration testing method.	
1E	Number of Percolation/Infiltration Tests. Does the infiltration testing method performed satisfy the minimum number of tests specified in Table D.3-2? <input type="checkbox"/> Yes; continue to Step 1F. <input type="checkbox"/> No; conduct appropriate number of tests.	

¹ This form must be completed each time there is a change to the site layout that would affect the infiltration feasibility condition. Previously completed forms shall be retained to document the evolution of the site storm water design.

² Available data includes site-specific sampling or observation of soil types or texture classes, such as obtained from borings or test pits necessary to support other design elements.



Project Name: _____

Categorization of Infiltration Feasibility Condition based on Geotechnical Conditions		Form I-8A ¹ (Worksheet C.4-1)
IF	<p>Factor of Safety. Is the suitable Factor of Safety selected for full infiltration design? See guidance in D.5; Tables D.5-1 and D.5-2; and Worksheet D.5-1 (Form I-9).</p> <p><input type="checkbox"/> Yes; continue to Step 1G. <input type="checkbox"/> No; select appropriate factor of safety.</p>	
1G	<p>Full Infiltration Feasibility. Is the average measured infiltration rate divided by the Factor of Safety greater than 0.5 inches per hour?</p> <p><input type="checkbox"/> Yes; answer “Yes” to Criteria 1 Result. <input type="checkbox"/> No; answer “No” to Criteria 1 Result.</p>	
Criteria 1 Result	<p>Is the estimated reliable infiltration rate greater than 0.5 inches per hour within the DMA where runoff can reasonably be routed to a BMP?</p> <p><input type="checkbox"/> Yes; the DMA may feasibly support full infiltration. Continue to Criteria 2. <input checked="" type="checkbox"/> No; full infiltration is not required. Skip to Part 1 Result.</p>	
<p>Summarize infiltration testing methods, testing locations, replicates, and results and summarize estimates of reliable infiltration rates according to procedures outlined in D.5. Documentation should be included in project geotechnical report.</p> <p>Infiltration was performed at two locations within the project site using borehole infiltration tests. The test results were as follows:</p> <p>A-1: 0.004 in/hr (0.002 in/hr using a factor of safety of 2.0 for feasibility determination) A-2: 0.082 in/hr (0.041 in/hr using a factor of safety of 2.0 for feasibility determination)</p> <p>Infiltration test information is contained in the geotechnical investigation dated September 18, 2020.</p>		
Criteria 2: Geologic/Geotechnical Screening		
2A	<p>If all questions in Step 2A are answered “Yes,” continue to Step 2B.</p> <p>For any “No” answer in Step 2A answer “No” to Criteria 2 and submit an “Infiltration Feasibility Condition Letter” that meets the requirements in Appendix C.1.1.</p> <p>The geologic/geotechnical analyses listed in Appendix C.2.1 do not apply to the DMA because one of the following setbacks cannot be avoided and therefore result in the DMA being in a no infiltration condition. The setbacks must be the closest horizontal radial distance from the surface edge (at the overflow elevation) of the BMP.</p>	



Project Name: _____

Categorization of Infiltration Feasibility Condition based on Geotechnical Conditions		Form I-8A ¹ (Worksheet C.4-1)	
2A-1	Can the proposed full infiltration BMP(s) avoid areas with existing fill materials greater than 5 feet thick below the infiltrating surface?	<input type="checkbox"/> Yes	<input type="checkbox"/> No
2A-2	Can the proposed full infiltration BMP(s) avoid placement within 10 feet of existing underground utilities, structures, or retaining walls?	<input type="checkbox"/> Yes	<input type="checkbox"/> No
2A-3	Can the proposed full infiltration BMP(s) avoid placement within 50 feet of a natural slope (>25%) or within a distance of 1.5H from fill slopes where H is the height of the fill slope?	<input type="checkbox"/> Yes	<input type="checkbox"/> No
2B	When full infiltration is determined to be feasible, a geotechnical investigation report must be prepared that considers the relevant factors identified in Appendix C.2.1. If all questions in Step 2B are answered "Yes," then answer "Yes" to Criteria 2 Result. If there are "No" answers continue to Step 2C.		
2B-1	Hydroconsolidation. Analyze hydroconsolidation potential per approved ASTM standard due to a proposed full infiltration BMP. Can full infiltration BMPs be proposed within the DMA without increasing hydroconsolidation risks?	<input type="checkbox"/> Yes	<input type="checkbox"/> No
2B-2	Expansive Soils. Identify expansive soils (soils with an expansion index greater than 20) and the extent of such soils due to proposed full infiltration BMPs. Can full infiltration BMPs be proposed within the DMA without increasing expansive soil risks?	<input type="checkbox"/> Yes	<input type="checkbox"/> No
2B-3	Liquefaction. If applicable, identify mapped liquefaction areas. Evaluate liquefaction hazards in accordance with Section 6.4.2 of the City of San Diego's Guidelines for Geotechnical Reports (2011 or most recent edition). Liquefaction hazard assessment shall take into account any increase in groundwater elevation or groundwater mounding that could occur as a result of proposed infiltration or percolation facilities. Can full infiltration BMPs be proposed within the DMA without increasing liquefaction risks?	<input type="checkbox"/> Yes	<input type="checkbox"/> No
2B-4	Slope Stability. If applicable, perform a slope stability analysis in accordance with the ASCE and Southern California Earthquake Center (2002) Recommended Procedures for Implementation of DMG Special Publication 117, Guidelines for Analyzing and Mitigating Landslide Hazards in California to determine minimum slope setbacks for full infiltration BMPs. See the City of San Diego's Guidelines for Geotechnical Reports (2011) to determine which type of slope stability analysis is required. Can full infiltration BMPs be proposed within the DMA without increasing slope stability risks?	<input type="checkbox"/> Yes	<input type="checkbox"/> No
2B-5	Other Geotechnical Hazards. Identify site-specific geotechnical hazards not already mentioned (refer to Appendix C.2.1). Can full infiltration BMPs be proposed within the DMA without increasing risk of geologic or geotechnical hazards not already mentioned?	<input type="checkbox"/> Yes	<input type="checkbox"/> No

Project Name: _____

Categorization of Infiltration Feasibility Condition based on Geotechnical Conditions		Form I-8A ¹ (Worksheet C.4-1)	
2B-6	<p>Setbacks. Establish setbacks from underground utilities, structures, and/or retaining walls. Reference applicable ASTM or other recognized standard in the geotechnical report.</p> <p>Can full infiltration BMPs be proposed within the DMA using established setbacks from underground utilities, structures, and/or retaining walls?</p>	<input type="checkbox"/> Yes	<input type="checkbox"/> No
2C	<p>Mitigation Measures. Propose mitigation measures for each geologic/geotechnical hazard identified in Step 2B. Provide a discussion of geologic/geotechnical hazards that would prevent full infiltration BMPs that cannot be reasonably mitigated in the geotechnical report. See Appendix C.2.1.8 for a list of typically reasonable and typically unreasonable mitigation measures.</p> <p>Can mitigation measures be proposed to allow for full infiltration BMPs? If the question in Step 2 is answered “Yes,” then answer “Yes” to Criteria 2 Result.</p> <p>If the question in Step 2C is answered “No,” then answer “No” to Criteria 2 Result.</p>	<input type="checkbox"/> Yes	<input type="checkbox"/> No
Criteria 2 Result	Can infiltration greater than 0.5 inches per hour be allowed without increasing risk of geologic or geotechnical hazards that cannot be reasonably mitigated to an acceptable level?	<input type="checkbox"/> Yes	<input type="checkbox"/> No
Summarize findings and basis; provide references to related reports or exhibits.			
Part 1 Result – Full Infiltration Geotechnical Screening ³		Result	
<p>If answers to both Criteria 1 and Criteria 2 are “Yes”, a full infiltration design is potentially feasible based on Geotechnical conditions only.</p> <p>If either answer to Criteria 1 or Criteria 2 is “No”, a full infiltration design is not required.</p>		<input type="checkbox"/> Full infiltration Condition <input checked="" type="checkbox"/> Complete Part 2	

³ To be completed using gathered site information and best professional judgement considering the definition of MEP in the MS4 Permit. Additional testing and/or studies may be required by City Engineer to substantiate findings.



Project Name: _____

Categorization of Infiltration Feasibility Condition based on Geotechnical Conditions		Form I-8A ¹ (Worksheet C.4-1)
Part 2 – Partial vs. No Infiltration Feasibility Screening Criteria		
DMA(s) Being Analyzed:		Project Phase:
Entire Site		Planning
Criteria 3 : Infiltration Rate Screening		
3A	<p>NRCS Type C, D, or “urban/unclassified”: Is the mapped hydrologic soil group according to the NRCS Web Soil Survey or UC Davis Soil Web Mapper is Type C, D, or “urban/unclassified” and corroborated by available site soil data?</p> <p><input type="checkbox"/> Yes; the site is mapped as C soils and a reliable infiltration rate of 0.15 in/hr. is used to size partial infiltration BMPS. Answer “Yes” to Criteria 3 Result.</p> <p><input type="checkbox"/> Yes; the site is mapped as D soils or “urban/unclassified” and a reliable infiltration rate of 0.05 in/hr. is used to size partial infiltration BMPS. Answer “Yes” to Criteria 3 Result.</p> <p><input checked="" type="checkbox"/> No; infiltration testing is conducted (refer to Table D.3-1), continue to Step 3B.</p>	
3B	<p>Infiltration Testing Result: Is the reliable infiltration rate (i.e. average measured infiltration rate/2) greater than 0.05 in/hr. and less than or equal to 0.5 in/hr?</p> <p><input type="checkbox"/> Yes; the site may support partial infiltration. Answer “Yes” to Criteria 3 Result.</p> <p><input checked="" type="checkbox"/> No; the reliable infiltration rate (i.e. average measured rate/2) is less than 0.05 in/hr., partial infiltration is not required. Answer “No” to Criteria 3 Result.</p>	
Criteria 3 Result	<p>Is the estimated reliable infiltration rate (i.e., average measured infiltration rate/2) greater than or equal to 0.05 inches/hour and less than or equal to 0.5 inches/hour at any location within each DMA where runoff can reasonably be routed to a BMP?</p> <p><input type="checkbox"/> Yes; Continue to Criteria 4.</p> <p><input checked="" type="checkbox"/> No: Skip to Part 2 Result.</p>	
<p>Summarize infiltration testing and/or mapping results (i.e. soil maps and series description used for infiltration rate).</p> <p>Infiltration testing was performed in the area of the proposed storm water BMP at the northwest corner of the property. The test results were as follows:</p> <p>A-1: 0.004 in/hr (0.002 in/hr using a factor of safety of 2.0 for feasibility determination) A-2: 0.082 in/hr (0.041 in/hr using a factor of safety of 2.0 for feasibility determination)</p> <p>This rate is not fast enough for partial infiltration.</p> <p>Infiltration test information is contained in the geotechnical investigation dated September 18, 2020.</p>		

Project Name: _____

Categorization of Infiltration Feasibility Condition based on Geotechnical Conditions		Form I-8A ¹ (Worksheet C.4-1)	
Criteria 4: Geologic/Geotechnical Screening			
4A	<p>If all questions in Step 4A are answered “Yes,” continue to Step 2B.</p> <p>For any “No” answer in Step 4A answer “No” to Criteria 4 Result, and submit an “Infiltration Feasibility Condition Letter” that meets the requirements in Appendix C.1.1. The geologic/geotechnical analyses listed in Appendix C.2.1 do not apply to the DMA because one of the following setbacks cannot be avoided and therefore result in the DMA being in a no infiltration condition. The setbacks must be the closest horizontal radial distance from the surface edge (at the overflow elevation) of the BMP.</p>		
4A-1	Can the proposed partial infiltration BMP(s) avoid areas with existing fill materials greater than 5 feet thick?	<input type="checkbox"/> Yes	<input type="checkbox"/> No
4A-2	Can the proposed partial infiltration BMP(s) avoid placement within 10 feet of existing underground utilities, structures, or retaining walls?	<input type="checkbox"/> Yes	<input type="checkbox"/> No
4A-3	Can the proposed partial infiltration BMP(s) avoid placement within 50 feet of a natural slope (>25%) or within a distance of 1.5H from fill slopes where H is the height of the fill slope?	<input type="checkbox"/> Yes	<input type="checkbox"/> No
4B	<p>When full infiltration is determined to be feasible, a geotechnical investigation report must be prepared that considers the relevant factors identified in Appendix C.2.1.</p> <p>If all questions in Step 4B are answered “Yes,” then answer “Yes” to Criteria 4 Result. If there are any “No” answers continue to Step 4C.</p>		
4B-1	<p>Hydroconsolidation. Analyze hydroconsolidation potential per approved ASTM standard due to a proposed full infiltration BMP.</p> <p>Can partial infiltration BMPs be proposed within the DMA without increasing hydroconsolidation risks?</p>	<input type="checkbox"/> Yes	<input type="checkbox"/> No
4B-2	<p>Expansive Soils. Identify expansive soils (soils with an expansion index greater than 20) and the extent of such soils due to proposed full infiltration BMPs.</p> <p>Can partial infiltration BMPs be proposed within the DMA without increasing expansive soil risks?</p>	<input type="checkbox"/> Yes	<input type="checkbox"/> No
4B-3	<p>Liquefaction. If applicable, identify mapped liquefaction areas. Evaluate liquefaction hazards in accordance with Section 6.4.2 of the City of San Diego's Guidelines for Geotechnical Reports (2011). Liquefaction hazard assessment shall take into account any increase in groundwater elevation or groundwater mounding that could occur as a result of proposed infiltration or percolation facilities.</p> <p>Can partial infiltration BMPs be proposed within the DMA without increasing liquefaction risks?</p>	<input type="checkbox"/> Yes	<input type="checkbox"/> No

Project Name: _____

Categorization of Infiltration Feasibility Condition based on Geotechnical Conditions		Form I-8A ¹ (Worksheet C.4-1)	
4B-4	<p>Slope Stability. If applicable, perform a slope stability analysis in accordance with the ASCE and Southern California Earthquake Center (2002) Recommended Procedures for Implementation of DMG Special Publication 117, Guidelines for Analyzing and Mitigating Landslide Hazards in California to determine minimum slope setbacks for full infiltration BMPs. See the City of San Diego's Guidelines for Geotechnical Reports (2011) to determine which type of slope stability analysis is required.</p> <p>Can partial infiltration BMPs be proposed within the DMA without increasing slope stability risks?</p>	<input type="checkbox"/> Yes	<input type="checkbox"/> No
4B-5	<p>Other Geotechnical Hazards. Identify site-specific geotechnical hazards not already mentioned (refer to Appendix C.2.1).</p> <p>Can partial infiltration BMPs be proposed within the DMA without increasing risk of geologic or geotechnical hazards not already mentioned?</p>	<input type="checkbox"/> Yes	<input type="checkbox"/> No
4B-6	<p>Setbacks. Establish setbacks from underground utilities, structures, and/or retaining walls. Reference applicable ASTM or other recognized standard in the geotechnical report.</p> <p>Can partial infiltration BMPs be proposed within the DMA using recommended setbacks from underground utilities, structures, and/or retaining walls?</p>	<input type="checkbox"/> Yes	<input type="checkbox"/> No
4C	<p>Mitigation Measures. Propose mitigation measures for each geologic/geotechnical hazard identified in Step 4B. Provide a discussion on geologic/geotechnical hazards that would prevent partial infiltration BMPs that cannot be reasonably mitigated in the geotechnical report. See Appendix C.2.1.8 for a list of typically reasonable and typically unreasonable mitigation measures.</p> <p>Can mitigation measures be proposed to allow for partial infiltration BMPs? If the question in Step 4C is answered "Yes," then answer "Yes" to Criteria 4 Result.</p> <p>If the question in Step 4C is answered "No," then answer "No" to Criteria 4 Result.</p>	<input type="checkbox"/> Yes	<input type="checkbox"/> No
Criteria 4 Result	<p>Can infiltration of greater than or equal to 0.05 inches/hour and less than or equal to 0.5 inches/hour be allowed without increasing the risk of geologic or geotechnical hazards that cannot be reasonably mitigated to an acceptable level?</p>	<input type="checkbox"/> Yes	<input type="checkbox"/> No

Project Name: _____

Categorization of Infiltration Feasibility Condition based on Geotechnical Conditions	Form I-8A ¹ (Worksheet C.4-1)
<p>Summarize findings and basis; provide references to related reports or exhibits.</p>	
Part 2 – Partial Infiltration Geotechnical Screening Result ⁴	Result
<p>If answers to both Criteria 3 and Criteria 4 are “Yes”, a partial infiltration design is potentially feasible based on geotechnical conditions only.</p> <p>If answers to either Criteria 3 or Criteria 4 is “No”, then infiltration of any volume is considered to be infeasible within the site.</p>	<p><input type="checkbox"/> Partial Infiltration Condition</p> <p><input checked="" type="checkbox"/> No Infiltration Condition</p>

⁴ To be completed using gathered site information and best professional judgement considering the definition of MEP in the MS4 Permit. Additional testing and/or studies may be required by City Engineer to substantiate findings.


**ATTACHMENT 1E – POLLUTANT CONTROL BMP DESIGN
WORKSHEETS/CALCULATIONS**

San Diego County 85 th Percentile Isopluvials


Legend

- 85th PERCENTILE ISOPLUVIAL
- INCORPORATED CITY

NOTE:
The 85th percentile is a 24 hour rainfall total. It represents a value such that 85% of the observed 24 hour rainfall totals will be less than that value.



THIS MAP/DATA IS PROVIDED WITHOUT WARRANTY OF ANY KIND, EITHER EXPRESS OR IMPLIED, INCLUDING BUT NOT LIMITED TO, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. Note: This product may contain information reproduced with permission from SANDAG. This product may contain information reproduced with permission granted by Rand McNally & Company® to SanGIS. This map is copyrighted by Rand McNally & Company®. It is unlawful to copy or reproduce all or any part thereof, whether for personal use or resale, without the prior, written permission of Rand McNally & Company®. Copyright SanGIS 2014. All Rights Reserved. Full text of this legal notice can be found at: http://www.sandag.org/legal_notice.htm



PROJECT SITE

ATTACHMENT 1B: Worksheet B.2-1: DCV

85th percentile 24-hr storm depth from Figure B.1.= 0.515 in

DMA ID	BMP ID	BMP Drainage Area (ac)	BMP Drainage Area (SF)	Impervious Area (ac)	Amended Soils (ac) (C=0.1)	Natural A Soils (ac) (C=0.1)	Natural B Soils (ac) (C=0.14)	Natural C Soils (ac) (C=0.23)	Natural D Soils (ac) (C=0.3)	% Impervious	Composite C ¹	Tree Credit Volume (cf)	Rain Barrels Credit Volume (cf)	Design Capture Volume (DCV) (CF)
Project Site	1,2,3	20.3	884339	13.08	4.47			2.75	0	64.4%	0.633			24027

Notes:

1) Equation for composite C factor = $(0.9 \times \text{Impervious Area} + C \times \text{Pervious Area}) / \text{Total Area}$ per BMP Design Manual.

C factors are from Table B.1-1 of August 2021 City BMP Design Manual.

2) Volume Retention will be met with Biofiltration Basins and Impervious Dispersion



Project Name Nakano

BMP ID Site

Sizing Method for Volume Retention Criteria

Worksheet B.5-2

1	Area draining to the BMP	884339	sq. ft.
2	Adjusted runoff factor for drainage area (Refer to Appendix B.1 and B.2)	0.633078818	
3	85 th percentile 24-hour rainfall depth	0.515	inches
4	Design capture volume [Line 1 x Line 2 x (Line 3/12)]	24027	cu. ft.
Volume Retention Requirement			
5	<p>Measured infiltration rate in the DMA</p> <p>Note:</p> <p>When mapped hydrologic soil groups are used enter 0.10 for NRCS Type D soils and for NRCS Type C soils enter 0.30</p> <p>When in no infiltration condition and the actual measured infiltration rate is unknown enter 0.0 if there are geotechnical and/or groundwater hazards identified in Appendix C or enter 0.05</p>	0	in/hr.
6	Factor of safety	2	
7	Reliable infiltration rate, for biofiltration BMP sizing [Line 5 / Line 6]	0	in/hr.
8	<p>Average annual volume reduction target (Figure B.5-2)</p> <p>When Line 7 > 0.01 in/hr. = Minimum (40, 166.9 x Line 7 + 6.62)</p> <p>When Line 7 ≤ 0.01 in/hr. = 3.5%</p>	3.5	%
9	<p>Fraction of DCV to be retained (Figure B.5-3)</p> <p>When Line 8 > 8% =</p> $0.0000013 \times \text{Line } 8^3 - 0.000057 \times \text{Line } 8^2 + 0.0086 \times \text{Line } 8 - 0.014$ <p>When Line 8 ≤ 8% = 0.023</p>	0.023	
10	Target volume retention [Line 9 x Line 4]	553	cu. ft.



Project Name Nakano

BMP ID Site

Volume Retention for No Infiltration Condition

Worksheet B.5-6

1	Area draining to the biofiltration BMP				884339	sq. ft.
2	Adjusted runoff factor for drainage area (Refer to Appendix B.1 and B.2)				0.63307882	
3	Effective impervious area draining to the BMP [Line 1 x Line 2]				559856	sq. ft.
4	Required area for Evapotranspiration [Line 3 x 0.03]				16796	sq. ft.
5	Biofiltration BMP Footprint				8131	sq. ft.
Landscape Area (must be identified on DS-3247)						
	Identification	1	2	3	4	5
6	Landscape area that meet the requirements in SD-B and SD-F Fact Sheet (sq. ft.)	11469				
7	Impervious area draining to the landscape area (sq. ft.)	13651				
8	Impervious to Pervious Area ratio [Line 7/Line 6]	1.19	0.00	0.00	0.00	0.00
9	Effective Credit Area If (Line 8 >1.5, Line 6, Line 7/1.5)	9101	0	0	0	0
10	Sum of Landscape area [sum of Line 9 Id's 1 to 5]				9101	sq. ft.
11	Provided footprint for evapotranspiration [Line 5 + Line 10]				17232	sq. ft.
Volume Retention Performance Standard						
12	Is Line 11 ≥ Line 4?	Volume Retention Performance Standard is Met				
13	Fraction of the performance standard met through the BMP footprint and/or landscaping [Line 11/Line 4]				1.03	
14	Target Volume Retention [Line 10 from Worksheet B.5.2]				553	cu. ft.
15	Volume retention required from other site design BMPs [(1-Line 13) x Line 14]				-16.57874435	cu. ft.
Site Design BMP						
	Identification	Site Design Type			Credit	
16	1					cu. ft.
	2					cu. ft.
	3					cu. ft.
	4					cu. ft.
	5					cu. ft.
	Sum of volume retention benefits from other site design BMPs (e.g. trees; rain barrels etc.). [sum of Line 16 Credits for Id's 1 to 5] Provide documentation of how the site design credit is calculated in the PDP SWQMP.				0	cu. ft.
17	Is Line 16 ≥ Line 15?	Volume Retention Performance Standard is Met				

ATTACHMENT 1B: Worksheet B.2-1: DCV

85th percentile 24-hr storm depth from Figure B.1.= 0.515 in

DMA ID	BMP ID	BMP Drainage Area (ac)	BMP Drainage Area (SF)	Impervious Area (ac)	Amended Soils (ac) (C=0.1)	Natural A Soils (ac) (C=0.1)	Natural B Soils (ac) (C=0.14)	Natural C Soils (ac) (C=0.23)	Natural D Soils (ac) (C=0.3)	% Impervious	Composite C ¹	Tree Credit Volume (cf)	Rain Barrels Credit Volume (cf)	Design Capture Volume (DCV) (CF)
1	1	2.49	108312	1.77	0.72			0		71.1%	0.669			3108

Notes:

1) Equation for composite C factor = $(0.9 * \text{Impervious Area} + C * \text{Pervious Area}) / \text{Total Area}$ per BMP Design Manual.

C factors are from Table B.1-1 of August 2021 City BMP Design Manual.

CALCULATION FOR MEDIA FILTRATION RATE WHEN CONTROLLED BY UNDERDRAIN ORIFICE

Surface ponding [6 inch minimum, 12 inch maximum]	6
Media thickness [18 inches minimum], also add mulch layer and washed ASTM 33 fine aggregate sand thickness to this line for sizing calculations	24
Aggregate storage (also add ASTM No 8 stone) above underdrain invert (12 inches typical) – use 0 inches if the aggregate is not over the entire bottom surface area	12
Diameter of underdrain orifice	1 in
H	3.46
Max hydromod Q through underdrain	0.04884 cfs
Footprint of the BMP	3608 ft ²
Media filtration rate to be used for sizing (maximum filtration rate of 5 in/hr. with no outlet control; if the filtration rate is controlled by the outlet use the outlet controlled rate (includes infiltration into the soil and flow rate through the outlet structure) which will be less than 5 in/hr.)	0.58 in/hr



Project Name Nakano

BMP ID 1

Sizing Method for Pollutant Removal Criteria

Worksheet B.5-1

1	Area draining to the BMP	108312	sq. ft.
2	Adjusted runoff factor for drainage area (Refer to Appendix B.1 and B.2)	0.668674699	
3	85 th percentile 24-hour rainfall depth	0.515	inches
4	Design capture volume [Line 1 x Line 2 x (Line 3/12)]	3108	cu. ft.
BMP Parameters			
5	Surface ponding [6 inch minimum, 12 inch maximum]	6	inches
6	Media thickness [18 inches minimum], also add mulch layer and washed ASTM 33 fine aggregate sand thickness to this line for sizing calculations	24	inches
7	Aggregate storage (also add ASTM No 8 stone) above underdrain invert (12 inches typical) – use 0 inches if the aggregate is not over the entire bottom surface area	12	inches
8	Aggregate storage below underdrain invert (3 inches minimum) – use 0 inches if the aggregate is not over the entire bottom surface area	3	inches
9	Freely drained pore storage of the media	0.2	in/in
10	Porosity of aggregate storage	0.4	in/in
11	Media filtration rate to be used for sizing (maximum filtration rate of 5 in/hr. with no outlet control; if the filtration rate is controlled by the outlet use the outlet controlled rate (includes infiltration into the soil and flow rate through the outlet structure) which will be less than 5 in/hr.)	0.58	in/hr.
Baseline Calculations			
12	Allowable routing time for sizing	6	hours
13	Depth filtered during storm [Line 11 x Line 12]	3.48	inches
14	Depth of Detention Storage [Line 5 + (Line 6 x Line 9) + (Line 7 x Line 10) + (Line 8 x Line 10)]	16.8	inches
15	Total Depth Treated [Line 13 + Line 14]	20.28	inches
Option 1 – Biofilter 1.5 times the DCV			
16	Required biofiltered volume [1.5 x Line 4]	4662	cu. ft.
17	Required Footprint [Line 16/ Line 15] x 12	2759	sq. ft.
Option 2 - Store 0.75 of remaining DCV in pores and ponding			
18	Required Storage (surface + pores) Volume [0.75 x Line 4]	2331	cu. ft.
19	Required Footprint [Line 18/ Line 14] x 12	1665	sq. ft.
Footprint of the BMP			
20	BMP Footprint Sizing Factor (Default 0.03 or an alternative minimum footprint sizing factor from Line 11 in Worksheet B.5-4)	0.03	
21	Minimum BMP Footprint [Line 1 x Line 2 x Line 20]	2173	sq. ft.
22	Footprint of the BMP = Maximum(Minimum(Line 17, Line 19), Line 21)	2173	sq. ft.
23	Provided BMP Footprint	3608	sq. ft.
24	Is Line 23 ≥ Line 22?	Yes, Performance Standard is Met	

ATTACHMENT 1B: Worksheet B.2-1: DCV

85th percentile 24-hr storm depth from Figure B.1.= 0.515 in

DMA ID	BMP ID	BMP Drainage Area (ac)	BMP Drainage Area (SF)	Impervious Area (ac)	Amended Soils (ac) (C=0.1)	Natural A Soils (ac) (C=0.1)	Natural B Soils (ac) (C=0.14)	Natural C Soils (ac) (C=0.23)	Natural D Soils (ac) (C=0.3)	% Impervious	Composite C ¹	Tree Credit Volume (cf)	Rain Barrels Credit Volume (cf)	Design Capture Volume (DCV) (CF)
2	2	4.01	174893	2.41	0.75			0.86		60.1%	0.609			4571

Notes:

1) Equation for composite C factor = $(0.9 \times \text{Impervious Area} + C \times \text{Pervious Area}) / \text{Total Area}$ per BMP Design Manual.

C factors are from Table B.1-1 of Aug 2021 City BMP Design Manual.



CALCULATION FOR MEDIA FILTRATION RATE WHEN CONTROLLED BY UNDERDRAIN ORIFICE

Surface ponding [6 inch minimum, 12 inch maximum]	6
Media thickness [18 inches minimum], also add mulch layer and washed ASTM 33 fine aggregate sand thickness to this line for sizing calculations	24
Aggregate storage (also add ASTM No 8 stone) above underdrain invert (12 inches typical) – use 0 inches if the aggregate is not over the entire bottom surface area	12
Diameter of underdrain orifice	1 in
H	3.46
Max hydromod Q through underdrain	0.04884 cfs
Footprint of the BMP	684 ft ²
Media filtration rate to be used for sizing (maximum filtration rate of 5 in/hr. with no outlet control; if the filtration rate is controlled by the outlet use the outlet controlled rate (includes infiltration into the soil and flow rate through the outlet structure) which will be less than 5 in/hr.)	3.08 in/hr



Project Name Nakano

BMP ID 2

Sizing Method for Pollutant Removal Criteria

Worksheet B.5-1

1	Area draining to the BMP	174893	sq. ft.
2	Adjusted runoff factor for drainage area (Refer to Appendix B.1 and B.2)	0.608927681	
3	85 th percentile 24-hour rainfall depth	0.515	inches
4	Design capture volume [Line 1 x Line 2 x (Line 3/12)]	4571	cu. ft.
BMP Parameters			
5	Surface ponding [6 inch minimum, 12 inch maximum]	6	inches
6	Media thickness [18 inches minimum], also add mulch layer and washed ASTM 33 fine aggregate sand thickness to this line for sizing calculations	24	inches
7	Aggregate storage (also add ASTM No 8 stone) above underdrain invert (12 inches typical) – use 0 inches if the aggregate is not over the entire bottom surface area	15	inches
8	Aggregate storage below underdrain invert (3 inches minimum) – use 0 inches if the aggregate is not over the entire bottom surface area	3	inches
9	Freely drained pore storage of the media	0.2	in/in
10	Porosity of aggregate storage	0.4	in/in
11	Media filtration rate to be used for sizing (maximum filtration rate of 5 in/hr. with no outlet control; if the filtration rate is controlled by the outlet use the outlet controlled rate (includes infiltration into the soil and flow rate through the outlet structure) which will be less than 5 in/hr.)	3.08	in/hr.
Baseline Calculations			
12	Allowable routing time for sizing	6	hours
13	Depth filtered during storm [Line 11 x Line 12]	18.5069092	inches
14	Depth of Detention Storage [Line 5 + (Line 6 x Line 9) + (Line 7 x Line 10) + (Line 8 x Line 10)]	18	inches
15	Total Depth Treated [Line 13 + Line 14]	36.5069092	inches
Option 1 – Biofilter 1.5 times the DCV			
16	Required biofiltered volume [1.5 x Line 4]	6856	cu. ft.
17	Required Footprint [Line 16/ Line 15] x 12	2254	sq. ft.
Option 2 - Store 0.75 of remaining DCV in pores and ponding			
18	Required Storage (surface + pores) Volume [0.75 x Line 4]	3428	cu. ft.
19	Required Footprint [Line 18/ Line 14] x 12	2285	sq. ft.
Footprint of the BMP			
20	BMP Footprint Sizing Factor (Default 0.03 or an alternative minimum footprint sizing factor from Line 11 in Worksheet B.5-4)	0.03	
21	Minimum BMP Footprint [Line 1 x Line 2 x Line 20]	3195	sq. ft.
22	Footprint of the BMP = Maximum(Minimum(Line 17, Line 19), Line 21)	3195	sq. ft.
23	Provided BMP Footprint	4523	sq. ft.
24	Is Line 23 ≥ Line 22?	Yes, Performance Standard is Met	

ATTACHMENT 1B: Worksheet B.2-1: DCV

85th percentile 24-hr storm depth from Figure B.1.= 0.515 in


DMA ID	BMP ID	BMP Drainage Area (ac)	BMP Drainage Area (SF)	Impervious Area (ac)	Amended Soils (ac) (C=0.1)	Natural A Soils (ac) (C=0.1)	Natural B Soils (ac) (C=0.14)	Natural C Soils (ac) (C=0.23)	Natural D Soils (ac) (C=0.3)	% Impervious	Composite C ¹	Tree Credit Volume (cf)	Rain Barrels Credit Volume (cf)	Design Capture Volume (DCV) (CF)
3	3	13.8	601134	8.95	2.95			1.9	0	64.9%	0.637			16427

Notes:

1) Equation for composite C factor = $(0.9 \times \text{Impervious Area} + C \times \text{Pervious Area}) / \text{Total Area}$ per BMP Design Manual.

C factors are from Table B.1-1 of Aug 2021 City BMP Design Manual.

Vault Drawdown






Figure B.4-1: Percent Capture Nomograph

B.5.2.2 Sizing Biofiltration BMPs Downstream of a Storage Unit

Introduction

In scenarios, where the BMP footprint is governed based on Option 1 (Line 17 of Worksheet B.5-1) or the required volume reduction for partial infiltration conditions (Line 10 of Worksheet B.5-2) the footprint of the biofiltration BMP can be reduced using the sizing calculations in this **Appendix B.5.2.2** when there is an upstream storage unit (e.g. cistern) that can be used to regulate the flows through the biofiltration BMP.

When this approach is used for sizing biofiltration BMPs the applicant must also verify that the storage unit meets the hydromodification management drawdown requirements and the discharge from the downstream biofiltration BMP will still meet the hydromodification flow control requirements. These calculations must be documented in the PDP SWQMP.

This methodology is **not** applicable when the minimum footprint factor is governed based on the alternative minimum footprint sizing factor calculated using Worksheet B.5-4 (Line 11). A biofiltration BMP smaller than the alternative minimum footprint sizing factor is considered compact biofiltration BMP and may be allowed at the discretion of the City Engineer if the BMP meets the requirements in **Appendix F** and the applicant submits a completed Form I-10.

Sizing Calculation

Sizing calculations for the biofiltration footprint must demonstrate that one of the following two equivalent performance standards is met:

1. Use continuous simulation and demonstrate the following is met:
 - (a) The BMP or series of BMPs biofilters at least 92 percent of average annual (long term) runoff volume and achieves a volume reduction equivalent to Line 10 of **Worksheet B.5-2**. This can be demonstrated through reporting of output from the San Diego Hydrology Model, or through other continuous simulation modeling meeting the criteria in **Appendix G**, as acceptable to the City Engineer. The 92 percent of average annual runoff treatment corresponds to the average capture achieved by implementing a BMP with 1.5 times the DCV and a drawdown time of 36 hours (**Appendix B.4.2**).
2. Use the simple optimized method in **Worksheet B.5-5**. The applicant is also required to complete Worksheet B.5-1, B.5-2 and B.5-4 when the applicant elects to use Worksheet B.5-5 to reduce the biofiltration BMP footprint. **Worksheet B.5-5** was developed to satisfy the following two criteria as applicable:
 - (a) Greater than 92 percent of the average annual runoff volume from the storage unit is routed to the biofiltration BMP through the low flow orifice and the peak flow from the low flow orifice can instantaneously be filtered through the biofiltration media. If the outlet design for the storage unit includes orifices at different elevations and an overflow structure, only flows from the overflow structure should be excluded from the calculation (both for 92 percent capture and for peak flow to the biofiltration BMP that needs to be instantaneously filtered), unless the flows from other orifices also bypass the biofiltration BMP, in which case flows from the orifices that bypass should also be excluded.

Table B.5-5

Drawdown Time (hours)	Storage requirement (below the overflow elevation, or below outlet elevation that bypass the biofiltration BMP)
12	0.85 DCV
24	1.25 DCV
36	1.50 DCV
48	1.80 DCV
72	2.20 DCV
96	2.60 DCV
120	2.80 DCV



PROJECT DESIGN CONSULTANTS

PLANNING | LANDSCAPE ARCHITECTURE
ENGINEERING | SURVEY

WWW.PROJECTDESIGN.COM


PROJECT NAKANO BMP System

SUBJECT _____

PAGE : _____ OF _____ JOB NO. : _____

DRAWN BY : J.N. DATE : 6/22/22

CHECKED BY : _____ DATE : _____



VAULT
12,376 ft² AREA
5 ft DEPTH

2 - 1.48" ORIFICES @ BOT MWS ELEV = 98.5' (EQUATES TO 1 - 2.2" ORIFICE)

4' WEIR WALL @ 103.06' w/ 8' LENGTH

FOR BYPASS + EMERGENCY OVERFLOW

Nakano Project MWS Calculations

Project Site DCV=	16427 ft ³		
96 hour drawdown=2.6*DCV			
2.6*DCV=	42710 ft ³		
$Q_{avg} = \text{Volume}/(96*3600)$			
$Q_{avg} =$	0.124 cfs		
$Q_{avg} =$	55.46 gpm	Conversion	
		448.8 gpm/cfs	
Volume based loading rate	0.28 gpm/sf		
Loading Rate = Q_{avg}/A_{filter}			
$A_{filter} = \text{Perimeter length} * \text{Height}$		Height used=	4.5 ft
P=	44.02 ft		
Perimeter Capacity of 8-24 Unit=	88.8 ft		
	44.02 ft <		88.8 ft
MWS 8-24 Unit will work			





SITE SPECIFIC DATA			
PROJECT NUMBER	14850		
PROJECT NAME	NAKANO		
PROJECT LOCATION	CHULA VISTA, CA		
STRUCTURE ID	N/A		
TREATMENT REQUIRED			
VOLUME BASED (CF)	FLOW BASED (CFS)		
42,710	N/A		
TREATMENT HGL AVAILABLE (FT)	N/K		
PEAK BYPASS REQUIRED (CFS) - IF APPLICABLE	N/A		
PIPE DATA	I.E.	MATERIAL	DIAMETER
INLET PIPE 1	99.00	PVC	8"
INLET PIPE 2	N/A	N/A	N/A
OUTLET PIPE	98.50	PVC	8"
	PRETREATMENT	BIOFILTRATION	DISCHARGE
RIM ELEVATION	104.50	104.50	104.50
SURFACE LOAD	PEDESTRIAN	N/A	PEDESTRIAN
FRAME & COVER	3EA Ø30"	OPEN PLANTER	2EA Ø30"
WETLANDMEDIA VOLUME (CY)	18.00		
ORIFICE SIZE (DIA. INCHES)	Ø1.48 EA		
NOTES: PRELIMINARY NOT FOR CONSTRUCTION. UPSTREAM BYPASS WEIR SET AT 103.06			

INSTALLATION NOTES


- CONTRACTOR TO PROVIDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS REQUIRED TO OFFLOAD AND INSTALL THE SYSTEM AND APPURTENANCES IN ACCORDANCE WITH THIS DRAWING AND THE MANUFACTURERS' SPECIFICATIONS, UNLESS OTHERWISE STATED IN MANUFACTURER'S CONTRACT.
- UNIT MUST BE INSTALLED ON LEVEL BASE. MANUFACTURER RECOMMENDS A MINIMUM 6" LEVEL ROCK BASE UNLESS SPECIFIED BY THE PROJECT ENGINEER. CONTRACTOR IS RESPONSIBLE FOR VERIFYING PROJECT ENGINEER'S RECOMMENDED BASE SPECIFICATIONS.
- CONTRACTOR TO SUPPLY AND INSTALL ALL EXTERNAL CONNECTING PIPES. ALL PIPES MUST BE FLUSH WITH INSIDE SURFACE OF CONCRETE (PIPES CANNOT INTRUDE BEYOND FLUSH). INVERT OF OUTFLOW PIPE MUST BE FLUSH WITH DISCHARGE CHAMBER FLOOR. ALL PIPES SHALL BE SEALED WATERTIGHT PER MANUFACTURER'S STANDARD CONNECTION DETAIL.
- CONTRACTOR RESPONSIBLE FOR INSTALLATION OF ALL PIPES, RISERS, MANHOLES, AND HATCHES. CONTRACTOR TO USE GROUT AND/OR BRICKS TO MATCH COVERS WITH FINISHED SURFACE UNLESS SPECIFIED OTHERWISE.
- VEGETATION SUPPLIED AND INSTALLED BY OTHERS. ALL UNITS WITH VEGETATION MUST HAVE DRIP OR SPRAY IRRIGATION SUPPLIED AND INSTALLED BY OTHERS.
- CONTRACTOR RESPONSIBLE FOR CONTACTING BIO CLEAN FOR ACTIVATION OF UNIT. MANUFACTURER'S WARRANTY IS VOID WITHOUT PROPER ACTIVATION BY A BIO CLEAN REPRESENTATIVE.

GENERAL NOTES

- MANUFACTURER TO PROVIDE ALL MATERIALS UNLESS OTHERWISE NOTED.
- ALL DIMENSIONS, ELEVATIONS, SPECIFICATIONS AND CAPACITIES ARE SUBJECT TO CHANGE. FOR PROJECT SPECIFIC DRAWINGS DETAILING EXACT DIMENSIONS, WEIGHTS AND ACCESSORIES PLEASE CONTACT BIO CLEAN.



REQUIRED TREATMENT VOLUME (CF)	42,710
DRAINDOWN DURATION (HOURS)	82
AVERAGE DISCHARGE RATE PER MWS UNIT(GPM)	110.69
OPERATING HEAD (FT)	4.5
WETLANDMEDIA INFILTRATION RATE (IN/HR)	27.7
WETLANDMEDIA LOADING RATE (GPM/SF)	OR 0.28



PROPRIETARY AND CONFIDENTIAL:
THE INFORMATION CONTAINED IN THIS DOCUMENT IS THE SOLE PROPERTY OF FORTERRA AND ITS COMPANIES. THIS DOCUMENT, IN OR ANY PART THEREOF, MAY BE USED, REPRODUCED OR MODIFIED IN ANY MANNER WITH OUT THE WRITTEN CONSENT OF FORTERRA.



MWS-L-8-24-5'-11"-V
STORMWATER BIOFILTRATION SYSTEM
STANDARD DETAIL

6/23/22/REVIEWS



A Forterra Company

MWS SIZING Nakano Chula Vista, CA

Mike Billings

06/23/2022



A Forterra Company

The MWS Linear will be sized in accordance with its TAPE GULD approval. The system is approved at a loading rate of 1 gpm/sq ft. The MWS Linear has General Use Level Designation at this loading rate for TSS (Basic), phosphorous and dissolved metals (Enhanced). For this project design, sizing, loading will be reviewed by a Modular Wetland representative for final approval to ensure the system is sized appropriately.

For this project we are sizing the MWS units to treat a large volume. Due to this large volume, we are using a 72% safety factor on our media loading rate and only sizing at a loading rate of 0.277 gpm/sf. Using a safety factor between 65% and 75% will greatly prolong the life of the Wetland MEDIA and decrease the long-term maintenance costs.

The orifice has been sized using the standard orifice sizing below. Sizing is based on the discharge rate of 110.69 gpm split between the two orifices. $110.69 \text{ gpm} / 2 = 55.35 \text{ gpm}$

MWS ORIFICE SIZING

$$\text{Given that: } Q = VA; \quad Q = \text{treatment flow rate, } V = c_d \sqrt{2gh}, \quad A = \frac{\pi D^2}{4}$$

c_d is the discharge coefficient & h is the treatment HGL

Rewrite to solve for the diameter of the orifice.

$$\left[A = \frac{Q}{V} \right] \xrightarrow{\text{rewrite}} \frac{\pi D^2}{4} = \frac{Q}{c_d \sqrt{2gh}}$$

$$D = \sqrt{\frac{4Q}{\pi c_d \sqrt{2gh}}}; \quad c_d = c_v c_c = (0.98)(0.62) = 0.6076$$

MWS-L-8-24-V-HC:

Given: $Q = 55.35 \text{ gpm (per orifice)} = 0.123 \text{ cfs}$, $h = 4.5 \text{ ft}$

$$D = \sqrt{\frac{4(0.123)}{\pi(0.6076)\sqrt{2(32.17)(4.5)}}} = 0.123' = \boxed{1.48" \text{ each}}$$

The diameter of each orifice needs to be 1.48" in order to produce a head of 4.5' in the MWS unit.



July 2017

GENERAL USE LEVEL DESIGNATION FOR BASIC, ENHANCED, AND PHOSPHORUS TREATMENT

For the

MWS-Linear Modular Wetland

Ecology's Decision:

Based on Modular Wetland Systems, Inc. application submissions, including the Technical Evaluation Report, dated April 1, 2014, Ecology hereby issues the following use level designation:

1. General use level designation (GULD) for the MWS-Linear Modular Wetland Stormwater Treatment System for Basic treatment
 - Sized at a hydraulic loading rate of 1 gallon per minute (gpm) per square foot (sq ft) of wetland cell surface area. For moderate pollutant loading rates (low to medium density residential basins), size the Prefilters at 3.0 gpm/sq ft of cartridge surface area. For high loading rates (commercial and industrial basins), size the Prefilters at 2.1 gpm/sq ft of cartridge surface area.
2. General use level designation (GULD) for the MWS-Linear Modular Wetland Stormwater Treatment System for Phosphorus treatment
 - Sized at a hydraulic loading rate of 1 gallon per minute (gpm) per square foot (sq ft) of wetland cell surface area. For moderate pollutant loading rates (low to medium density residential basins), size the Prefilters at 3.0 gpm/sq ft of cartridge surface area. For high loading rates (commercial and industrial basins), size the Prefilters at 2.1 gpm/sq ft of cartridge surface area.
3. General use level designation (GULD) for the MWS-Linear Modular Wetland Stormwater Treatment System for Enhanced treatment
 - Sized at a hydraulic loading rate of 1 gallon per minute (gpm) per square foot (sq ft) of wetland cell surface area. For moderate pollutant loading rates (low to medium density residential basins), size the Prefilters at 3.0 gpm/sq ft of cartridge surface area. For high loading rates (commercial and industrial basins), size the Prefilters at 2.1 gpm/sq ft of cartridge surface area.

4. Ecology approves the MWS - Linear Modular Wetland Stormwater Treatment System units for Basic, Phosphorus, and Enhanced treatment at the hydraulic loading rate listed above. Designers shall calculate the water quality design flow rates using the following procedures:

- Western Washington: For treatment installed upstream of detention or retention, the water quality design flow rate is the peak 15-minute flow rate as calculated using the latest version of the Western Washington Hydrology Model or other Ecology-approved continuous runoff model.
- Eastern Washington: For treatment installed upstream of detention or retention, the water quality design flow rate is the peak 15-minute flow rate as calculated using one of the three methods described in Chapter 2.2.5 of the Stormwater Management Manual for Eastern Washington (SWMMEW) or local manual.
- Entire State: For treatment installed downstream of detention, the water quality design flow rate is the full 2-year release rate of the detention facility.

5. These use level designations have no expiration date but may be revoked or amended by Ecology, and are subject to the conditions specified below.

Ecology's Conditions of Use:

Applicants shall comply with the following conditions:

1. Design, assemble, install, operate, and maintain the MWS – Linear Modular Wetland Stormwater Treatment System units, in accordance with Modular Wetland Systems, Inc. applicable manuals and documents and the Ecology Decision.
2. Each site plan must undergo Modular Wetland Systems, Inc. review and approval before site installation. This ensures that site grading and slope are appropriate for use of a MWS – Linear Modular Wetland Stormwater Treatment System unit.
3. MWS – Linear Modular Wetland Stormwater Treatment System media shall conform to the specifications submitted to, and approved by, Ecology.
4. The applicant tested the MWS – Linear Modular Wetland Stormwater Treatment System with an external bypass weir. This weir limited the depth of water flowing through the media, and therefore the active treatment area, to below the root zone of the plants. This GULD applies to MWS – Linear Modular Wetland Stormwater Treatment Systems whether plants are included in the final product or not.
5. Maintenance: The required maintenance interval for stormwater treatment devices is often dependent upon the degree of pollutant loading from a particular drainage basin. Therefore, Ecology does not endorse or recommend a “one size fits all” maintenance cycle for a particular model/size of manufactured filter treatment device.

- Typically, Modular Wetland Systems, Inc. designs MWS - Linear Modular Wetland systems for a target prefilter media life of 6 to 12 months.
- Indications of the need for maintenance include effluent flow decreasing to below the design flow rate or decrease in treatment below required levels.
- Owners/operators must inspect MWS - Linear Modular Wetland systems for a minimum of twelve months from the start of post-construction operation to determine site-specific

maintenance schedules and requirements. You must conduct inspections monthly during the wet season, and every other month during the dry season. (According to the SWMMWW, the wet season in western Washington is October 1 to April 30. According to SWMMEW, the wet season in eastern Washington is October 1 to June 30). After the first year of operation, owners/operators must conduct inspections based on the findings during the first year of inspections.

- Conduct inspections by qualified personnel, follow manufacturer's guidelines, and use methods capable of determining either a decrease in treated effluent flowrate and/or a decrease in pollutant removal ability.
- When inspections are performed, the following findings typically serve as maintenance triggers:

- Standing water remains in the vault between rain events, or
- Bypass occurs during storms smaller than the design storm.
- If excessive floatables (trash and debris) are present (but no standing water or excessive sedimentation), perform a minor maintenance consisting of gross solids removal, not prefilter media replacement.
- Additional data collection will be used to create a correlation between pretreatment chamber sediment depth and pre-filter clogging (see *Issues to be Addressed by the Company* section below)

6. Discharges from the MWS - Linear Modular Wetland Stormwater Treatment System units shall not cause or contribute to water quality standards violations in receiving waters.

Applicant: Modular Wetland Systems, Inc.
Applicant's Address: PO. Box 869
Oceanside, CA 92054

Application Documents:

- *Original Application for Conditional Use Level Designation*, Modular Wetland System, Linear Stormwater Filtration System Modular Wetland Systems, Inc., January 2011
- *Quality Assurance Project Plan: Modular Wetland system – Linear Treatment System performance Monitoring Project*, draft, January 2011.
- *Revised Application for Conditional Use Level Designation*, Modular Wetland System, Linear Stormwater Filtration System Modular Wetland Systems, Inc., May 2011
- *Memorandum: Modular Wetland System-Linear GULD Application Supplementary Data*, April 2014
- *Technical Evaluation Report: Modular Wetland System Stormwater Treatment System Performance Monitoring*, April 2014.

Applicant's Use Level Request:

General use level designation as a Basic, Enhanced, and Phosphorus treatment device in accordance with Ecology's Guidance for Evaluating Emerging Stormwater Treatment Technologies Technology Assessment Protocol – Ecology (TAPE) January 2011 Revision.

Applicant's Performance Claims:

- The MWS – Linear Modular wetland is capable of removing a minimum of 80-percent of TSS from stormwater with influent concentrations between 100 and 200 mg/l.
- The MWS – Linear Modular wetland is capable of removing a minimum of 50-percent of Total Phosphorus from stormwater with influent concentrations between 0.1 and 0.5 mg/l.
- The MWS – Linear Modular wetland is capable of removing a minimum of 30-percent of dissolved Copper from stormwater with influent concentrations between 0.005 and 0.020 mg/l.
- The MWS – Linear Modular wetland is capable of removing a minimum of 60-percent of dissolved Zinc from stormwater with influent concentrations between 0.02 and 0.30 mg/l.

Ecology Recommendations:

- Modular Wetland Systems, Inc. has shown Ecology, through laboratory and field-testing, that the MWS - Linear Modular Wetland Stormwater Treatment System filter system is capable of attaining Ecology's Basic, Total phosphorus, and Enhanced treatment goals.

Findings of Fact:Laboratory Testing

The MWS-Linear Modular wetland has the:

- Capability to remove 99 percent of total suspended solids (using Sil-Co-Sil 106) in a quarter-scale model with influent concentrations of 270 mg/L.
- Capability to remove 91 percent of total suspended solids (using Sil-Co-Sil 106) in laboratory conditions with influent concentrations of 84.6 mg/L at a flow rate of 3.0 gpm per square foot of media.
- Capability to remove 93 percent of dissolved Copper in a quarter-scale model with influent concentrations of 0.757 mg/L.
- Capability to remove 79 percent of dissolved Copper in laboratory conditions with influent concentrations of 0.567 mg/L at a flow rate of 3.0 gpm per square foot of media.
- Capability to remove 80.5-percent of dissolved Zinc in a quarter-scale model with influent concentrations of 0.95 mg/L at a flow rate of 3.0 gpm per square foot of media.
- Capability to remove 78-percent of dissolved Zinc in laboratory conditions with influent concentrations of 0.75 mg/L at a flow rate of 3.0 gpm per square foot of media.

Field Testing

- Modular Wetland Systems, Inc. conducted monitoring of an MWS-Linear (Model # MWS-L-4-13) from April 2012 through May 2013, at a transportation maintenance facility in Portland, Oregon. The manufacturer collected flow-weighted composite samples of the system's influent and effluent during 28 separate storm events. The system treated approximately 75 percent of the runoff from 53.5 inches of rainfall during the monitoring period. The applicant sized the system at 1 gpm/sq ft. (wetland media) and 3gpm/sq ft. (prefilter).
- Influent TSS concentrations for qualifying sampled storm events ranged from 20 to 339 mg/L. Average TSS removal for influent concentrations greater than 100 mg/L (n=7) averaged 85 percent. For influent concentrations in the range of 20-100 mg/L (n=18), the upper 95 percent confidence interval about the mean effluent concentration was 12.8 mg/L.
- Total phosphorus removal for 17 events with influent TP concentrations in the range of 0.1 to 0.5 mg/L averaged 65 percent. A bootstrap estimate of the lower 95 percent confidence limit (LCL95) of the mean total phosphorus reduction was 58 percent.
- The lower 95 percent confidence limit of the mean percent removal was 60.5 percent for dissolved zinc for influent concentrations in the range of 0.02 to 0.3 mg/L (n=11). The lower 95 percent confidence limit of the mean percent removal was 32.5 percent for dissolved copper for influent concentrations in the range of 0.005 to 0.02 mg/L (n=14) at flow rates up to 28 gpm (design flow rate 41 gpm). Laboratory test data augmented the data set, showing dissolved copper removal at the design flow rate of 41 gpm (93 percent reduction in influent dissolved copper of 0.757 mg/L).

Issues to be addressed by the Company:

1. Modular Wetland Systems, Inc. should collect maintenance and inspection data for the first year on all installations in the Northwest in order to assess standard maintenance requirements for various land uses in the region. Modular Wetland Systems, Inc. should use these data to establish required maintenance cycles.
2. Modular Wetland Systems, Inc. should collect pre-treatment chamber sediment depth data for the first year of operation for all installations in the Northwest. Modular Wetland Systems, Inc. will use these data to create a correlation between sediment depth and pre-filter clogging.

Technology Description:

Download at <http://www.modularwetlands.com/>

Contact Information:

Applicant: Zach Kent
BioClean A Forterra Company.
398 Vi9a El Centro
Oceanside, CA 92058
zach.kent@forterrabp.com

Applicant website: <http://www.modularwetlands.com/>

Ecology web link: <http://www.ecy.wa.gov/programs/wg/stormwater/newtech/index.html>

Ecology: Douglas C. Howie, P.E.
Department of Ecology
Water Quality Program
(360) 407-6444
douglas.howie@ecy.wa.gov

Revision History

Date	Revision
June 2011	Original use-level-designation document
September 2012	Revised dates for TER and expiration
January 2013	Modified Design Storm Description, added Revision Table, added maintenance discussion, modified format in accordance with Ecology standard
December 2013	Updated name of Applicant
April 2014	Approved GULD designation for Basic, Phosphorus, and Enhanced treatment
December 2015	Updated GULD to document the acceptance of MWS-Linear Modular Wetland installations with or without the inclusion of plants
July 2017	Revised Manufacturer Contact Information (name, address, and email)